



	Title-Sujet	Date
RETURN BIDS TO:	FH Terreplein	Fahmun 0, 2010
RETOURNER LES SOUMISSIONS À:	Waterproofing	February 8, 2018
Parks Canada		
National Contracting Services Mailroom	Solicitation No No. de l'invitation 5P201-17-5187/A	Client Ref. No. – No. de réf du client.
Parks Canada	SF201-17-518//A	
30 Victoria Street	Solicitation Closes	Time Zone
Gatineau, Quebec, J8X 0B3	L'invitation prend fin –	Fuseau horaire -
AMENDMENT # 5	at à 02.00 PM	
AWLINDWILINT # 3	at – à 02:00 PM on – le 2018-02-13	Eastern Standard Time (EST)
		(EST)
The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Contract remain the same	F.O.B F.A.B. Plant-Usine: Destination: Other-Autre: D	
	Address Inquiries to: - Adresser toute demande de renseignements à :	
	Ginette Aliaga	
Ce document est par la présente revise; sauf indication contraire, les modalités du contrat demeurent les mêmes.	Ginette.Aliaga@pc.gc.ca	
	Telephone No No de téléphone	Fax No. – No de FAX:
Comments – Commentaires	(819)-420-4667	
	Destination of Goods, Services, and Construction: Destinations des biens, services et construction:	
Vendor/Firm Name and Address	See Herein	
Raison sociale et adresse du		
fournisseur/de l'entrepreneur		
	Vendor/Firm Name and Address	
Issuing Office - Bureau de distribution	Raison sociale et adresse du fournisseur/de l'entrepreneur	
Parks Canada	Telephone No No de telephone:	
Mailroom	Facsimile No N° de télécopieur:	
30 Victoria Street Gatineau, Quebec, J8X 0B3	Email - Courriel :	
	Name and title of person authorized to Nom et titre de la personne autorisée à l'entrepreneur	
	Name / Nom	Title / Titre
	Signature	Date



## **SOLICITATION AMENDMENT # 5**

# THIS AMENDMENT CONSISTS OF QUESTION AND ANSWERS TO THE ITT AND AMENDMENT TO THE SOLICITATION CLOSING.

### 1. ANSWERS TO QUESTIONS ASKED BY POTENTIAL BIDDERS.

Q-1. As per Bid and Acceptance Form, item BA06, "The contractor shall perform and complete the work from date of contract award to the latest December 31, 2018", as per section 00 01 11, item 3.2, All 3 phases are to be completed from May 7, 2018 to September 1, 2018.

Question: Please confirm the project schedule.

A-1 : Construction to achieve "substantial completion" no later than 01 September, "final completion" no later than 31 December.

Q-2. As per section 00 01 11, item 3.8, "Pay all fees and obtain all permits". **Question: Please advise which permits will be required to carry in our tender price.** 

A-2: "Form 1000" for the Ministry of Labour is required. In addition any necessary permits for disposal of materials.

Q-3. As per drawing TW-17, Photographs are provided for repointing work. Question: For pricing purpose, can you please provide the approximate linear feet of repointing required.

A-3: Include in the lump sum price 400 linear meters of repointing. The location of the repointing will be determined by the departmental representative. This will not be sufficient to fix all areas around the work site at the fort but is intended to address the worst of the areas.

Q-4. As per drawing TW-18, detail has been provided for Skyward Facing – Special stone masonry joint finish.

Question: Please advise and provide the locations and approximate linear feet if we are required to provide the skyward facing caulking.

Answer 4: Include in the lump sum price 100 linear meters of skyward facing special joint treatment at deteriorated locations as directed. The location of the repairs to skyward facing joints will be as directed by the Departmental Representative. This will not be sufficient to fix all areas around the work site at the fort but is intended to address the worst of the areas. Note on the drawing TW-9 details C and D it is indicated that the joint at the top of the flashing on the firing steps the entire distance around

the fort will be repointed with finished layer of pointing replaced with sealant. The sealant in this case will be pre-sanded acrylic latex sealant as per the specification and this quantity will be part of the lump sum price and not part of the 100 linear meter included above.

- Q-5. As per section 01 14 00, item 1.5.3, "No digging or damage to the existing ground surface is to occur during the installation of the bridge.
  Question: To support the temporary bridge, we may require to provide the abutment on ground. Please advise.
- A-5: The site is archaeologically sensitive. Disturbance to the soils is limited to a depth of 100mm maximum. Note, passage under the bridge is required in the ditch for vehicles and equipment of other contractors and the tenant.
- Q-6. As per detail 4A on drawing TW-7, "Wooden platform for carronade cannon, to be removed, salvaged and replaced upon completion of installation of waterproofing system.

Question: Can you please confirm, is the replacement is required or reinstallation of existing wooden platform is required.

- A-6: The contract includes the Salvage and reinstallation of existing wooden platform. When the platform is removed the Departmental Representative will review the condition of the platforms.
- Q-7. As per detail 1A on drawing TW-9, "Existing steel racer rail (Remove newer rails, salvage and reinstall, Older racer rail to be left in place)" at Barbette locations.

Question: Can you please advise, how many steel racer rails are newer that required removal and reinstallation and how many steel racer rails are original and older that does not required removal.

A-7: The Notes of the phase drawings and the section details provide direction regarding the treatment of the racer rail areas. Phase 1 on drawings contains Heritage Racer rails that are to stay intact, be protected and not be removed. Phase 2 and Phase 3 contain all newer racer rail that can be removed, require re-anchoring etc and reinstallation as per the direction of Departmental Representative.

#### 2. AMENDMENT TO THE ITT

#### 1. ON PAGE 1 OF THE ITT EXTEND THE BID SOLICITATION PERIOD.

#### DELETE:

Solicitation closes L'invitation prend fin – at – à 02:00 PM on – le 2018-02-09

#### INSERT

Solicitation closes L'invitation prend fin – at – à 02:00 PM on – le 2018-02-13

#### END OF SECTION. ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.