




1 PLAN - RM 408 SERVERY
SCALE : 1:100




3 PLAN - RM 500X OFFICE
SCALE : 1:100




6 PLAN - LEVEL 600 DEMOLITION
SCALE : 1:100




2 PLAN - RM 408D OFFICE
SCALE : 1:100



4 PLAN - # 508D OFFICE
SCALE : 1:100



7 PLAN - LEVEL 600 DEMOLITION
SCALE : 1:100



5 PLAN - RM 508 SERVERY/ 508F COPY
SCALE : 1:100

DEMOLITION LEGEND

==== DENOTES DEMOLITION (WALL, DOORS, FRAMES, etc.)

DEMOLITION NOTES

1.0 THE GENERAL CONTRACTOR IS RESPONSIBLE TO PROTECT AND MAINTAIN THE INTEGRITY OF EXISTING FINISHES IN ALL BUILDING CORE AREAS NOT SCHEDULED FOR DEMOLITION WORK.

1.2 CONTRACTOR TO PROTECT ALL EXISTING WORK. ANY DAMAGE TO EXISTING PARTITION, CEILING OR FINISHES CAUSED BY DEMOLITION MUST BE REPAIRED / REPLACED BY CONTRACTOR.

1.3 CONTRACTOR TO REMOVE ALL DEBRIS RESULTING FROM DEMOLITION AND CONSTRUCTION. COORDINATE REMOVAL WITH THE PROJECT MANAGER AND/OR DEPARTMENTAL REPRESENTATIVE.

1.4 ALL DEMOLITION WASTE MUST BE SORTED AND TAKEN TO APPROPRIATE FACILITIES FOR RECYCLING.

1.5 CONTRACTOR TO SEAL AND REPAIR CUTOUPS FOR MECHANICAL AND ELECTRICAL PENETRATIONS IN FLOORS, WALLS AND CEILINGS. PROVIDE FINISHES TO MATCH EXISTING, UNLESS NOTED TO RECEIVE NEW.

1.6 CONTRACTOR TO PATCH FLOOR, ADJACENT WALLS AND CEILING AFTER DEMOLITION. PREPARE SURFACES TO RECEIVE NEW FINISH.

1.7 CONTRACTOR TO REVIEW ANY MATERIAL (I.E. MILLWORK, LIGHTING AND PLUMBING FIXTURES, ETC.) THAT THEY MAY WISH TO RETAIN. COORDINATE DISPOSAL AND STORAGE WITH PROJECT MANAGER AND/OR DEPARTMENTAL REPRESENTATIVE.

1.8 REMOVE ALL REDUNDANT EXISTING TELEPHONE, COMMUNICATIONS, ELECTRICAL OUTLETS, THERMOSTATS, SWITCHES, AND OTHER CABLING FROM WALLS TO BE DEMOLISHED, UNLESS NOTED OTHERWISE. ALL SERVICES TO BE REMOVED ARE TO BE PULLED BACK TO SOURCE. CONTRACTOR TO REVIEW EXTENT OF IT AND SECURITY CABLING REMOVAL.


1.09 CONTRACTOR TO VERIFY IN ADVANCE OF DEMOLITION IF ANY POWER AND COMMUNICATION OUTLETS AND COVER PLATES ARE TO BE REUSED AND NOTIFY PROJECT MANAGER AND/OR DEPARTMENTAL REPRESENTATIVE.

1.10 ALLOW FOR PROPER VENTILATION OF THE PREMISES UPON COMPLETION OF DEMOLITION.

PROJECT SPECIFIC NOTES

- 01) REMOVE EXISTING MILLWORK, SINK AND STUB WALL, MILLWORK & FITTINGS TO BE REPLACED WITH NEW ACCESSIBLE UNITS.
- 02) REMOVE EXISTING DOOR, FRAME, HARDWARE AND SIDELIGHT. STORE IN SECURE LOCATION. TO BE REUSED IN THIS WORK.
- 03) MAINTAIN EXISTING GWB BULKHEAD OVER EXISTING SERVERY

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada



kadesigns

(902) 454.9889 kadesigns@eastlink.ca
3873 Memorial Drive, Halifax, N.S. B3K 5A4



1	ISSUED FOR TENDER	01.26.2018
revisions		date
project		projet

CCG WP2.0 FIT-UP
MARITIME HEADQUARTERS
BEDFORD INSTITUTE OF OCEANOGRAPHY
DARTMOUTH
NOVA SCOTIA

drawing dessin

LEVEL 400, 500 & 600
DEMOLITION PLAN

designed KADesigns conçu

date

drawn KAD dessiné

date OCT.02.2017

approved approuvé

date

Tender IAN SCELES Soumission

PWGC Project Manager Administrateur de projets TPSGC

project number no. du projet

R.082156.001

drawing no. no. du dessin

A.03