

INTERIOR WINDOW SECTION

SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm

1
A6

ROOM FINISH SCHEDULE

ROOM NAME	ROOM No.	FLOOR		BASE		W A L L S								CEILING			REMARKS
						NORTH		SOUTH		EAST		WEST					
		MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	MAT.	FIN.	HGT.	
CRUSHING, RECEIVING AND BOTTLING	2045	EX	EP	EX	EP	EX	TL	EX	TL	CB	TL	EX	TL	EX	EX	EX	
VESTIBULE	2046A	EX	EP	EX	EP	EX	TL	-	-	EX	TL	EX	TL	EX	EX	EX	
STORAGE	2049	EX	EP	EX	EP	EX	TL	EX	TL	EX	TL	EX/CB	TL	EX	EX	EX	
CORRIDOR	2050	EX	EP	EX	EP	EX	TL	EX	TL	CB/GB	TL	EX	TL	EX	EX	EX	
WINE CELLAR	2051	EX	EP	EX	EP	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	
LARGE FERMENTATION	2052	EX	EP	EX	EP	EX	-	CWP	-	EX	-	EX	-	EX	EX	EX	
SMALL FERMENTATION	2052A	EX	EP	EX	EP	CWP	-	EX	-	EX	-	EX	-	EX	EX	EX	
WINE TASTING ROOM	201	EX	RSF	EX	R	GB	FWC	EX	FWC	GB	FWC	GB	FWC	-	P	-	REMOVE EXISTING CEILING AND PAINT STRUCTURE.
STAIRWELL	202	EX	RSF	EX	R	GB	TL	EX	TL	GB	TL	EX	TL	-	P	-	REMOVE EXISTING CEILING AND PAINT STRUCTURE.
STORAGE	203	EX	RSF	EX	R	GB	TL	GB	TL	GB	TL	GB	TL	-	P	-	REMOVE EXISTING CEILING AND PAINT STRUCTURE.

NOTE: ROOMS NOT LISTED IN ROOM FINISH SCHEDULE DO NOT REQUIRE ANY REPAIRS/REFINISH WORK. EXISTING MATERIALS/FINISHES TO REMAIN.


DOOR SCHEDULE

DOOR No.	DIMENSIONS			DOOR				FRAME				FIRE RATING	REMARKS
	W	H	Th.	Elev.	Type	Fin.	Hdwe.	Elev.	Type	Jamb	Fin.		
2045A	915	2134	45	1	HM	PT	4	1	PS	B	PT	-	
2045B	3048	3048	45	3	OHD	PT	-	3	PS	B	PT	-	HARDWARE BY DOOR MANUFACTURER.
2045C	915	2134	45	1	HM	PT	4	1	PS	B	PT	-	
2045D	3048	3048	45	3	OHD	PT	-	3	PS	B	PT	-	HARDWARE BY DOOR MANUFACTURER.
2049	2-915	2134	45	2	HM	PT	3	2	PS	B	PT	-	
2051	EX	EX	-	-	-	-	-	-	-	-	-	-	PROVIDE NEW HARDWARE. SEE ELECTRICAL.
2052	915	2134	-	-	-	-	-	-	-	-	-	-	COOLER DOOR. HARDWARE BY DOOR MANUFACTURER.
2052A	915	2134	-	-	-	-	-	-	-	-	-	-	COOLER DOOR. HARDWARE BY DOOR MANUFACTURER.
201	915	2134	45	1	HM	PT	2	1	PS	B	PT	-	
203	915	2134	45	1	HM	PT	1	1	PS	B	PT	-	


LEGEND

CB	CONCRETE BLOCK
CWP	COOLER WALL PANEL
EP	EPOXY FINISH
EX	EXISTING MATERIAL OR FINISH
FWC	FABRIC WALL COVER
GB	GYPSUM BOARD
HM	HOLLOW METAL
OHD	OVERHEAD DOOR
PT	PAINT
PS	PRESSED STEEL
R	RUBBER BASE
RSF	RESILIENT SHEET FLOORING
TL	WALL TILE FINISH


DOOR ELEVATIONS



DOOR TYPE 1




DOOR TYPE 2



DOOR TYPE 3

INTERIOR WINDOW




FINISH FLOOR


FRAME ELEVATIONS



FRAME TYPE 1




FRAME TYPE 2




FRAME TYPE 3

JAMB DETAILS



JAMB TYPE A




JAMB TYPE B




SNC-LAVALIN Inc.
Halifax, Nova Scotia, Canada

Member of the SNC-LAVALIN Group



KEY PLAN



01	ISSUED FOR TENDER	01/25 2018
revisions		date
project		projet

AAFC RESEARCH
CENTRE MICRO WINERY
AAFC KENTVILLE
RESEARCH CENTRE
KENTVILLE, NS

drawing dessin

SCHEDULES

designed	NS	conçu
date	2018-01-25	
drawn	AM	dessiné
date	2018-01-25	
approved	JB	approuvé
date	2018-01-25	
Tender		Soumission
PWGSC Project Manager	Administrateur de projets TPSGC	
project number	no. du projet	
R.083308.001		
drawing no.	no. du dessin	

A6