


EXISTING REFLECTED CEILING PLAN - PROCESSING AREA LEVEL 2

SCALE : 1:100  
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

1  
A7



DEMOLITION REFLECTED CEILING PLAN - MEZZANINE

SCALE : 1:100  
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

2  
A7

#### GENERAL NOTES

1. THESE DRAWINGS REASONABLY REPRESENT EXISTING CONDITIONS. ACTUAL CONDITIONS MAY DEVIATE FROM THAT SHOWN/IDENTIFIED ON THE DRAWINGS. THE CONTRACTOR SHALL VERIFY ACTUAL CONDITIONS, CHECK ALL DIMENSIONS, AND VERIFY MATERIALS REQUIRED TO COMPLETE THIS WORK. CONTRACTOR SHALL INFORM THE DEPARTMENTAL REPRESENTATIVE OF ANY DISCREPANCIES PRIOR TO COMMENCING WORK.
2. REMOVE FROM SITE DEMOLISHED MATERIALS, DEBRIS, AND RUBBISH. DISPOSE DEMOLISHED MATERIALS AS PER THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
3. THE CONTRACTOR IS RESPONSIBLE FOR TEMPORARY REMOVAL/RELOCATION OF ELECTRICAL AND MECHANICAL SYSTEMS WHICH INTERFERE WITH COMPLETING THE REPAIR WORK INDICATED ON THE DRAWINGS. ELECTRICAL AND MECHANICAL SYSTEMS TO BE REINSTATED ONCE REPAIR WORK IS COMPLETE. ALL WORK MUST BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES. BY LICENSED TRADES PEOPLE.
4. COMPLETE ALL WORK IN ACCORDANCE WITH THE NATIONAL BUILDING CODE OF CANADA (LATEST EDITION).
5. BUILDING IS TO REMAIN OPERATIONAL DURING DEMOLITION AND CONSTRUCTION. CONTRACTOR TO MAINTAIN OPERATIONAL, SECURITY AND WEATHER TIGHT.
6. PATCH, MATCH AND MAKE GOOD ALL EXISTING SURFACES AND SURFACES THAT HAVE BEEN AFFECTED BY DEMOLITION. REPAIR AFFECTED SURFACES AS REQUIRED TO ACCEPT NEW FINISHES. PROVIDE NEW FINISHES OR NEW TO MATCH AND BLEND WITH EXISTING. PROVIDE INFILL TO FILL OR REDUCE WALL OPENINGS THAT HAVE BEEN AFFECTED BY THE DEMOLITION.
7. FOR PAINTED SURFACES THAT HAVE BEEN AFFECTED BY DEMOLITION, REPAIR ENTIRE SURFACE TO NEAREST WALL, CEILING AND FLOOR INTERSECTION.
8. EXECUTE WORK BY METHODS TO AVOID DAMAGE TO OTHER EXISTING COMPONENTS AND FINISHES WHERE POSSIBLE.
9. ALL EXISTING SURFACES THAT ARE TO RECEIVE NEW FINISHES ARE TO BE PREPARED AS PER MANUFACTURERS RECOMMENDATION AND INSTRUCTIONS.
10. ALL WALL MOUNTED ITEMS, SUCH AS MECHANICAL AND ELECTRICAL EQUIPMENT, FIXTURES, PIPING, COUNTERS, FITTINGS, ETC TO BE REMOVED AND REINSTATED TO ALLOW FOR THE INSTALLATION OF THE NEW WALL TILE.

#### REFLECTED CEILING PLAN DEMOLITION NOTES:

- ① AREA OF WORK.
- ② EXISTING BEAMS TO REMAIN, TYP.
- ③ REMOVE EXISTING METAL LINEAR CEILING AND STORE IN SAFE PLACE TO BE RE-USED IN THE PROCESSING AREA (NEW CRUSHING, RECEIVING AND BOTTLING 2045).
- ④ EXISTING METAL LINEAR CEILING TO REMAIN.

#### REFLECTED CEILING PLAN DEMOLITION LEGEND:


- AREA OF WORK
- EXISTING BEAMS TO REMAIN
- EXISTING METAL LINEAR CEILING TO BE REMOVED
- EXISTING METAL LINEAR CEILING TO REMAIN

Public Works and Government Services Canada  
Travaux Publics et Services gouvernementaux Canada




SNC-LAVALIN Inc.  
Halifax, Nova Scotia, Canada

Member of the SNC-LAVALIN Group



KEY PLAN



01	ISSUED FOR TENDER	01/25 2018
revisions		date
project		projet

AAFC RESEARCH  
CENTRE MICRO WINERY  
AAFC KENTVILLE  
RESEARCH CENTRE  
KENTVILLE, NS

drawing dessin

EXISTING/DEMOLITION  
REFLECTED CEILING  
PLANS

designed NS	conçu
date 2018-01-25	
drawn AM	dessiné
date 2018-01-25	
approved JB	approuvé
date 2018-01-25	

Tender Soumission

PWGSC Project Manager Administrateur de projets TPSGC

project number no. du projet

R.083308.001

drawing no. no. du dessin

A7