

**Supply and Install AHU Cooling Coil
AAFC Research and Development Centre -St. John's, NL**

AMENDMENT # 2

THE FOLLOWING AMENDMENT TO THE TENDER DOCUMENTS IS EFFECTIVE IMMEDIATELY.
THE AMENDMENT SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

ADDENDUM NO. 2

DRAWINGS

1. On Drawing M1, detail 2, delete note 7 and replace with new note 7 to read:

“7. Two new condenser unit supports. Length of supports to be coordinated with unit supplier (approximate length 1.8 metres) and installed in accordance with unit manufacturer's installation requirements. See detail 3 on Drawing M2. Provide crickets as required to provide positive drainage to each side of unit.”
2. On Drawing M2, detail 3, add “New” to existing reference W 310 x 39 steel beam welded or bolted to existing beam.

By submission of its tender, the Tenderer confirms that it has read and understands the requirements expressed in all addenda and has included all costs of these requirements in its Total Tender Amount.

All other terms & conditions remain unchanged.
