



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving Public Works & Government Services
Canada/Réception des soumissions Travaux publics et
Services gouvernementaux Canada**

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

Halifax

Nova Scotia

B3J 1T3

Bid Fax: (902) 496-5016

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

**Atlantic Region Acquisitions/Région de l'Atlantique
Acquisitions**

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

Halifax

Nova Scot

B3J 1T3

Title - Sujet CCG WP 2.0 Construction	
Solicitation No. - N° de l'invitation EB144-182527/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client EB144-18-2527	Date 2018-02-23
GETS Reference No. - N° de référence de SEAG PW-\$PWA-405-5718	
File No. - N° de dossier PWA-7-78131 (405)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-03-01	Time Zone Fuseau horaire Atlantic Standard Time AST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Kendell (PWA), Byron	Buyer Id - Id de l'acheteur pwa405
Telephone No. - N° de téléphone (902) 402-9436 ()	FAX No. - N° de FAX (902) 496-5016
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 002 is raised for the following:

Solicitation closing date:

Delete: 27 February 2018

Insert: 1 March 2018

Specification: Division 25 Integrated Automation

DELETE: Section 25 30 02 – EMCS: Field Control Devices, para 2.2.2.2, which reads:

‘Buttons for occupant selection of temperature set-point and occupied/unoccupied mode’

Question 1 - At the site visit it was mentioned that removal of existing furniture in renovation areas is by general contractor. Could you please confirm the contractor is to remove/demolish furniture on level 200 (partial), level 400, level 500, and level 600?

Answer 1 – Refer to attached Addendum no. 2 Clarifications, item .3.

Question 2 - At the site visit it was mentioned that new furniture is by owner. Could you please confirm supply and install of furniture is by owner?

Answer 2 – Refer to attached Addendum no. 2 Clarification, item .4.

Question 3 - Wall Types in Partition Type Legend on drawing A.04 & A.05 do not agree with corresponding Wall Types as described in detail 3/A.04 "Section - Partition Types". Please clarify all wall assemblies and height requirements.

Answer 3 – Refer to attached Addendum no. 2 ASK.2A.

Question 4 - Curved walls in Quiet Rooms have 5/8" drywall in the assembly but 5/8" will not bend to that radius. 1/4" flexible in multiple layers would have to be used instead. Should ¼" flexible multiple layers rather than 5/8" sheet of drywall be included with the bid?

Answer 4 – Refer to attached Addendum no. 2 Clarification, item .6.

Question 5 - Can the ceiling tile types/manufacturers that we need to match be provided?

Answer 5 – Refer to attached Addendum no. 2 Clarification, item .7.

Question 6 - As for the phasing. Will the floors be unoccupied as work in that phase is taking place?

Answer 6 – Yes, all floors will be unoccupied as work in that phase is taking place.

Question 7 – Whose responsibility will it be to move soft seating, filing cabinets, bookshelves, wall art, personal belongings, etc.?

Answer 7 – Client Representative will remove these items.

Question 8 - Are all the floors in the scope of work getting new work stations?

Answer 8 – Yes. Refer to attached Addendum no. 2 Clarifications, item .4.

Question 9 - Is there a preferred sprinkler company?

Answer 9 – No.

Question 10 - Is there a preferred control company?

Answer 10 – No.

Question 11 - Is there a preferred fire alarm company?

Answer 11 – No.

Question 12 - Will Shared Services being responsible for data?

Answer 12 – No. Refer to attached Addendum no. 2 Clarifications, item .5.

Question 13 – Are we able to have a return visit to the site?

Solicitation No. - N° de l'invitation
EB144-182527

Amd. No. - N° de la modif.
002

Buyer ID - Id de l'acheteur
PWA405

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

Answer 13 – No additional site visits will be scheduled during the Solicitation Period.

All other terms and conditions remain the same.

PARTITION TYPE LEGEND:

PLEASE NOTE THE FOLLOWING CORRECTIONS
WHICH APPLIES TO BOTH SHEET A.04 AND A.05

PARTITION TYPE LEGEND - REVISED FEB.19.2018


TYPE ~~P1~~ P1



117.4mm THK
- NON RATED
- STC 35 min

- ONE LAYER 12.7mm GYPSUM BOARD FROM FINISHED FLOOR TO UNDERSIDE OF ACOUSTICAL CEILING @ 2435mm +/-
- ACOUSTIC BATT INSULATION
- 92mm RESILIENT METAL STUDS @ 610mm O/C
- ONE LAYER 12.7mm GYPSUM BOARD FROM FINISHED FLOOR TO UNDERSIDE OF ACOUSTICAL CEILING

TYPE ~~P2~~ P2



117.4mm THK
- NON RATED
- STC 45 min


- ONE LAYER 12.7mm GYPSUM BOARD FROM FINISHED FLOOR TO U/S SLAB ABOVE @ 3600mm AFF
- ACOUSTIC BATT INSULATION
- 92mm RESILIENT METAL STUDS @ 610mm O/C
- ONE LAYER 12.7mm GYPSUM BOARD FROM FINISHED FLOOR TO U/S SLAB ABOVE @ 3600mm AFF
- CONTINUOUS SEALANT AT ALL PENETRATIONS & PERIMETER

TYPE ~~P3~~ P3



133.3mm THK
- NON RATED
- STC 52 min

- TWO LAYERS 12.7mm GYPSUM BOARD FROM FINISHED FLOOR TO U/S SLAB ABOVE @ 3600mm AFF
- ACOUSTIC BATT INSULATION
- 92mm RESILIENT METAL STUDS @ 610mm O/C
- ONE LAYER 15.9mm GYPSUM BOARD FROM FINISHED FLOOR TO U/S SLAB ABOVE @ 3600mm AFF
- CONTINUOUS SEALANT AT ALL PENETRATIONS & PERIMETER

 Public Works and Government Services Canada	Travaux publics et Services gouvernementaux Canada	Drawing title Titre du dessin		designed conçu KAD	date FEB.23.2018
		ADDENDUM # 2 PARTITION LEGEND		drawn dessiné	date
project CCG WP2.0 FIT-UP MARITIME HEADQUARTERS BEDFORD INSTITUTE OF OCEANOGRAPHY DARTMOUTH, N.S.	projet	Tender IAN SCELES		Soumission	
		PWGSC Project Manager		Administrateur de projets TPSGC	
		project number R.082156.001	no. du projet	drawing no. ASK.2A	no. du dessin

ADDENDUM # 2 CLARIFICATIONS;

.1 ELEVATOR; APPROXIMATE SIZE OF ELEVATOR IS 2032mm L x 1664mm W x 2858mm H (80" x 65.5" x 112.5").

.2 CEILING HEIGHTS; FINISHED FLOOR TO ACOUSTICAL CEILING IS 2438mm +/- FINISHED FLOOR TO SLAB ABOVE IS 3600mm.

.3 EXISTING FURNITURE SYSTEMS; THE GENERAL CONTRACTOR IS RESPONSIBLE TO DISCONNECT THE POWER AND DATA IN THE EXISTING FURNITURE SYSTEMS ON LEVEL 200, 400, 500 AND 600. IN REGARDS TO LEVEL 300 PLEASE REFER TO ADDENDUM # 1 FOR THE DISMANTLING OF WORKSTATIONS 11, 12, 13 & 14. BALANCE OF WORKSTATIONS ON LEVEL 300 TO REMAIN AS IS. THE GENERAL CONTRACTOR IS ALSO RESPONSIBLE TO DISASSEMBLE AND DISPOSE ALL THE COMPONENTS IN THE FURNITURE SYSTEM, INCLUDING PANELS, WORKSURFACES, STORAGE TOWERS AND BINS.


Div 01 Section 01 10 10 General Conditions Item 1.1 Description of Work: Add power and data disconnections, removal and disposal of existing systems furniture, including all workstation components, towers and pedestals.

.4 NEW FURNITURE SYSTEMS; THE NEW FURNITURE SYSTEMS INDICATED ON LEVEL 200, 400, 500 AND 600 ARE BEING SUPPLIED BY OTHERS. THIS INCLUDES PANELS, WORKSURFACES, STORAGE BINS & TOWERS AND POWER WHIPS. THIS CONTRACT HAS BEEN AWARDED.

.5 NEW FURNITURE SYSTEM POWER/DATA; AS PER ELECTRICAL DRAWINGS NOTES # 5/ E.10, # 9/ E.11 AND #6/ E.12 THE GENERAL CONTRACTOR IS RESPONSIBLE TO MAKE ALL CONNECTIONS BETWEEN THE BASE BUILDING AND THE POWER WHIPS.

.6 QUIET ROOM CURVED WALLS; THE CURVED WALLS IN THE QUIET ROOMS HAVE 12.7mm (1/2") THK GWB AS PER ADDENDUM # 2 CORRECTION - SEE ASK.2A. TWO LAYERS OF 6mm (1/4") GWB IS ACCEPTABLE. WALL CONSTRUCTION MUST MEET STC45 RATING.

.7 EXISTING ACOUSTICAL CEILING; MANUFACTURER IS ARMSTRONG, SERIES 'OPTIMA PLAN # 3153 OR 3155. PLEASE CONFIRM ON SITE. TYPE IS RECTANGULAR LAY-IN. SIZE IS 1220 x 610

 Public Works and Government Services Canada	Travaux publics et Services gouvernementaux Canada	Drawing title		Titre du dessin		designed	conçu	date	
		ADDENDUM # 2 CLARIFICATION NOTES		KAD		FEB.23.2018			
				drawn	dessiné	date			
project		project		approved	approuvé	date			
CCG WP2.0 FIT-UP MARITIME HEADQUARTERS BEDFORD INSTITUTE OF OCEANOGRAPHY DARTMOUTH, N.S.		Tender						Soumission	
		IAN SCELES							
		PWGSC Project Manager						Administrateur de projets TPSGC	
project number		no. du projet		drawing no.		no. du dessin			
R.082156.001				ASK.2B					