


EXISTING ROOF R1:


- EPDM MEMBRANE
- 1/2" FIBERBOARD
- MULTI-PLY BUILT-UP ASPHALTIC MEMBRANE
- 1/2" FIBERBOARD
- COAL TAR PITCH MEMBRANE
- SLOPED WOOD DECK
- CONCRETE DECK



SYMBOLS:

RD	- ROOF DRAIN
RA	- ROOF ANCHOR
EX	- EXHAUST FAN
VS	- VENT STACK



SPARKS STREET



signs	description	date
	A detail no. no. du détail B location drawing no. sur dessin no. C drawing no. dessin no.	

HOPE BUILDING
ROOF
REPLACEMENT

ROOFING DEMOLITION PLAN

Signature	J. ARVAI	Conçu par
Date	2017/09/12	(yyyy/mm/dd)
Approuvé par	C. WOODCOCK	Dessiné par
Date	2017/09/15	(yyyy/mm/dd)
Examiné par	J. CIARMELA	Examiné par
Date	2017/09/15	(yyyy/mm/dd)
Approuvé par		Approuvé par
Date		(yyyy/mm/dd)
Remission		Remission
Administrateur de projets		
Administrateur de projets		
No. du projet		
No. du dessin		

1
A01

- 1 REMOVE AND DISPOSE OF EXISTING ROOF SYSTEM. MAINTAIN EXISTING SLOPED WOOD ROOF DECK.
- 2 REMOVE AND DISPOSE OF PREFINISHED METAL COPINGS AND FLASHINGS.
- 3 REMOVE AND DISPOSE OF PREFINISHED METAL COUNTERFLASHING. EXISTING COPPER PANELS TO REMAIN WHERE APPLICABLE.
- 4 REMOVE AND DISPOSE OF EXISTING ROOF DRAIN.
- 5 MAINTAIN ROOF ANCHORS (TYPICAL).
- 6 REMOVE, STORE AND RE-INSTALL EQUIPMENT. ADJUST SLEEPERS TO ALLOW FOR NEW WORK.
- 7 REMOVE, STORE AND RE-INSTALL ELECTRICAL CONDUIT. TEMPORARILY REMOVE FROM ROOF AND WALL SURFACES AS NECESSARY FOR ROOFING REMOVAL.
- 8 REMOVE AND DISPOSE OF ASPHALT SHINGLE ROOF ASSEMBLY TO WOOD DECK.