


1 SECOND FLOOR PLAN - DEMOLITIONS
ED2.1 SCALE: 1 : 100



GENERAL NOTES

- A. COORDINATE ALL WORK REQUIRING SHUT-DOWN OF EXISTING SYSTEMS THAT COULD AFFECT EXISTING TENANTS WITH THE BUILDING OWNER AT A TIME AND MANNER SUITABLE TO THEM.
- B. CONTRACTOR SHALL DISCONNECT AND REMOVE ALL EXISTING LIGHT FIXTURES COMPLETE WITH CONDUIT & WIRING BACK TO SOURCE.
- C. CONTRACTOR SHALL REMOVE ALL EXISTING ABANDONED WIRING IN CEILING SPACE BACK TO SOURCE. SECURE ALL EXISTING UN-SUPPORTED WIRING, CONDUIT AND JUNCTION BOXES TO MEET MINIMUM CODE REQUIREMENTS.
- D. REUSE EXISTING CIRCUITS FOR RELOCATED OR REMOVED POWER LOADS WITHIN THE SPACE. PROVIDE NEW BREAKERS AS REQUIRED. PROVIDE TYPEWRITTEN PANEL DIRECTORIES INDICATING UPDATED CIRCUITING.
- E. REMOVE ALL EXISTING CAT 5 DATA/VOICE CABLING ONLY. ALL DATA RACKS, CABLING, INSTALLATION AND TERMINATION BY SSC (NIC). ELECTRICAL CONTRACTOR SHALL PROVIDE ALL PATHWAY AND ROUGH-IN REQUIRED FOR COMMUNICATION OUTLETS.
- F. CONTRACTOR SHALL REMOVE ALL EXISTING ABANDONED WIRING IN CEILING SPACE BACK TO SOURCE.
- G. CONTRACTOR SHALL SECURE ALL EXISTING UN-SUPPORTED WIRING, CONDUIT AND JUNCTION BOXES TO MEET MINIMUM CODE REQUIREMENTS.
- H. DEMOLISH ALL EXISTING POWER POLES.
- I. CONTRACTOR SHALL CONFIRM ALL EXISTING SYSTEMS TO BE IN WORKING CONDITION PRIOR TO CARRYING OUT MODIFICATIONS. WHERE EXISTING SYSTEMS ARE NOT OPERABLE, NOTIFY THE DEPARTMENTAL REPRESENTATIVE PRIOR TO CARRYING OUT WORK.

KEY NOTES

- 1. CONFIRM EXISTING TELECOM GROUND BAR AND GROUND WIRE ON-SITE. EXTEND GROUND WIRE TO NEW TELECOM GROUND BAR AS APPLICABLE.
- 2. RETAIN EXISTING EMERGENCY LIGHTING CIRCUITS AND EXIT SIGNAGE CIRCUITS FOR NEW FIXTURES.
- 3. EXISTING SECURITY DEVICES TO BE REMOVED BY OTHERS (NIC).
- 4. EXISTING DOUBLE TUB PANEL TO REMAIN, 2IGC1/2IGC2, 225A 120/208V 3 PHASE 4WIRE 60 CCT SIEMENS EQ, FED FROM CDP 05-210-001 WITH 100A/3P BREAKER 05-120-036.
- 5. EXISTING PANEL TO REMAIN, 2IG (05-212-006), 100A 120/208V 3 PHASE 3 WIRE, SYLVANIA, FED FROM CDP 05-210-001 WITH 100A/3P BREAKER 05-120-045.
- 6. EXISTING DOUBLE TUB PANEL TO REMAIN, 2WJ, 200A 120/208V 3 PHASE 4 WIRE 60 CCT, ITE, FED FROM CDP 05-210-001 WITH 150A/3P BREAKER 05-120-032.

Association of Professional Engineers & Geoscientists
of Saskatchewan

CERTIFICATE OF AUTHORIZATION
Epp Siepman Engineering Inc.
Number 22814

Permission to Consult held by:
Discipline Sk. Reg. No. Signature
Mechanical 22813
Electrical 31291

Public Works and
Government Services
Canada

Travaux publics et
Services gouvernementaux
Canada

REAL PROPERTY SERVICES
Western Region
SERVICES IMMOBILIERS
Région de l'ouest

epp siepman
engineering

400 - 136 Market Avenue
Winnipeg, MB R3B 0P4
T 204 453 1080

ARCHITECTURE | 49

1800 BUFFALO PLACE
WINNIPEG MANITOBA CANADA R3T 6B8
TEL: 204-477-1260 | FAX: 204-477-6346 | www.architecture49.com

KEY PLAN
NTS

O	Issued for Construction	18-02-16
Revision	Description	Date
Client		client

SUITE 201

Project title

Projet

GOCB OFFICE FIT-UP
SASKATOON, SASKATCHEWAN

Designed by JF Concu par

Drawn by JF Dessine par

Approved by JF Approuve par

PWCSC Project Manager Administrateur de Projets TPSCG
AR

Drawing title Titre du dessin
SECOND FLOOR - DEMOLITION
PLAN

Project no./No. du projet Drawing no./No. du dessin Revision no.
R.055494.001 ED2.1 0
2 OF 4