161-17879-00



1 SITE PLAN
SCALE 1:1000

LEGEND

SYMBOL	DESCRIPTION
	JUNCTION BOX
	MOTOR AS NOTED
	PANEL AS NOTED
T	DE-ICING SENSOR EQUAL TO RAYCHEM #SIT-6E
	PUSH BUTTON CONTROL
	15A, 120V, DUPLEX RECEPTACLE
C	DE-ICING CONTROLLER EQUAL TO RAYCHEM #ETI-PD-PRO
P	HEAT TRACE POWER/END KIT EQUAL TO RAYCHEM #EMK-XP
	19mm X 300mm GROUND ROD
	DISCONNECT SWITCH
	UNDERGROUND CONDUIT AS NOTED
	ABOVE GROUND CONDUIT AS NOTED
	HEAT TRACE AS NOTED

ELECTRICAL DEMOLITION NOTE AND SALVAGE

1. UNLESS OTHERWISE NOTED ALL EXISTING ELECTRICAL SYSTEMS WHICH BECOME REDUNDANT SHALL BE REMOVED BY THE CONTRACTOR.
2. REMOVE ALL REDUNDANT EXISTING CONDUIT WHERE ACCESSIBLE.
3. REMOVE ALL REDUNDANT EXISTING CONDUCTORS TO POINT OF SOURCE.
4. CUT AND PATCH EXISTING WALLS WHERE REQUIRED TO ACCOMMODATE A NEW EQUIPMENT OR CONDUIT. LEAVE FINISHED SURFACE OF WALL IN "READY TOP PAINT" CONDITION.
5. TURN ALL SALVAGE MATERIAL OVER TO BUILDING OWNER
6. CONTRACTOR SHALL VISIT SITE PRIOR TO TENDER TO DETERMINE EXTENT OF DEMOLITION
   REQUIRED. NO EXTRAS WILL BE CONSIDERED FOR WORK RESULTING FROM CONDITIONS THAT WOULD HAVE BEEN EVIDENT UPON THOROUGH EXAMINATION OF THE SITE
7. CONTRACTOR SHALL UPDATE AND CONFIRM PANEL SCHEDULES AND LOADS FOR ALL PANELS AFFECTED BY THIS RENOVATION.
8. MAINTAIN CONTINUITY OF EXISTING BRANCH CIRCUITS AS REQUIRED TO PROVIDE POWER TO REMAINING EQUIPMENT, DEVICES AND LUMINAIRES THAT ARE NOT BEING REMOVED.
9. ANY EXISTING CONDITIONS INDICATED ARE BASED UPON INFORMATION PROVIDED BY OTHERS THE CONTRACTOR SHALL ADJUST FOR ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE.

NOTES

1. LOCATIONS OF EXISTING CONDUIT SHOWN ON THIS DRAWINGS WERE DERIVED FROM EXISTING AS-BUILD DRAWINGS AND ARE SHOWN FOR REFERENCE PURPOSES ONLY. CONTRACTOR IS RESPONSIBLE LOCATE CONDUIT AND DETERMINE EXACT ROUTING.
2. FENCE/GATE REPLACEMENT TO INCLUDE REMOVAL AND REINSTALLATION OF EXISTING FENCE DETECTION SYSTEM (FDS) SENSTAR #INTELLI-FLEX. WORK ONLY TO BE DONE BY A QUALIFIED FDS SECURITY SPECIALIST . CONTRACTOR TO COORDINATE WORK,TESTING,AND COMMISSIONING WITH CSC/RPC PERSONNEL. NOTE FDS IS A DISCONTINUED PRODUCT,CSC WILL PROVIDE CABLE IN LIMITED QUANTITIES IF REQUIRED.
3. WORK DONE NEAR/IN THE "NO MAN ZONE"/"STERILE AREA" TO BE COGNIZANT OF UNDERGROUND MOTION DETECTOR SYSTEM SENSTAR #PERIMITRAX. LOCATE DETECTOR SYSTEM PRIOR TO COMMENCING OF WORK, AS DETECTION SYSTEM IS LOCATED NEAR GROUND SURFACE, TO AVOID DAMAGE FROM HEAVY LOADS AND/OR EXCAVATING.
4. ALL EXISTING SECURITY SYSTEMS ARE TO REMAIN FUNCTIONAL DURING CONSTRUCTION TO THE SATISFACTION CSC/RPC. ANY SHUTDOWN OF EQUIPMENT ARE TO BE COORDINATED WITH CSC/RPC.

Public Works and Government Services Canada / Travaux publics et Services gouvernementaux Canada

REAL PROPERTY SERVICES
Western Region

Client / Client

CORRECTIONAL SERVICES CANADA

CSC REGIONAL PSYCHIATRIC CENTRE

Client / Client

COUPLAND KRAEMER
Architecture + Interior Design Inc.
Contact: Michael Coupland
mcoupland@ckaid.com
Suite 101
4632 1st Street SE
Calgary, Alberta
T2G 2L3
T. 403.269.7109
F. 403.269.7595

203 WELLMAN CRESCENT
SASKATOON SASKATCHEWAN CANADA S7T 0J1
TEL.: 306-665-6223 | FAX: 306-665-8589 | WWW.WSPGROUP.COM

PROFESSIONAL ENGINEER
H.R. JAMES
MEMBER 26625
18 02 15
YR MO DAY
SASKATCHEWAN

Association of Professional Engineers & Geoscientists of Saskatchewan
CERTIFICATE OF AUTHORIZATION
WSP CANADA INC.
Number C0865
Permission to Consult held by:
Discipline | No. Reg. No. | Signature
Electrical | 26625 |

REVISIONS	DESCRIPTION	DATE
0	TENDER SUBMISSION	18/02/15

A detail number / number du detail
B source drawing no. / de dessin no.
C detail on drawing no. / detail sur dessin no.

project title / titre du projet

Fence Assessment and Repair

CSC REGIONAL PSYCHIATRIC CENTRE SASKATOON, SASKATCHEWAN

drawing title / titre du dessin

PRINCIPAL ENTRY GATE SP1 & SP2

SITE PLAN

designed by / conçu par	HJ
drawn by / dessiné par	ZW
approved by / approuvé par	
PWGSC Project Manager / Administrateur de Projets TPSGC	BRET WARD
scale / echelle	AS SHOWN
project no. / projet no.	R.084540.001
date / date	2018/02/15
sheet / feuille	E1.0
	14 OF 16

81 1000 x 707