

PART 1 - GENERAL**1.1 RELATED SECTIONS**

- .1 Section 21 05 01 - Common Work Results for Mechanical.
- .2 Section 23 01 31 - Air Duct Cleaning for HVAC Systems.

1.2 REFERENCE STANDARDS

- .1 Code de construction du Québec - Chapitre I - Bâtiment 2010.

PART 2 - PRODUCTS

- .1 Not Used.

PART 3 - EXECUTION**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for electric and electronic control systems installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied [and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Coordinate temporary demolition of equipment in the work area with the Contractor and the Departmental Representative.
- .2 Protect existing control/control devices from dust and impact in the work area. Replace, at no cost to the Departmental Representative, any equipment that has been damaged due to lack of proper protection.
- .3 Connect equipment that has been temporarily removed. Check operation and re-calibrate.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

END OF SECTION