

5			
4			
3			
2			
1	ISSUED FOR TENDER	2016/03/16	
0	Revision / Description	Date / Date	
	Client / client		

**Immigration, Refugees and
Citizenship Canada**
Saskatoon
Saskatchewan


Project title/Titre du projet
Government of Canada Building
101 - 22 Street East
**Saskatoon Relocation Fit-up
Saskatoon, Saskatchewan**

Approved by/Approve par
BD
Designed by/Concept par
M.V.
Drawn by/Dessiné par
M.L.
PWSSC Project Manager/Administrateur de Projets TPSSC
PWSSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSSC
Client/client


Drawing Title/Titre du dessin
**SECOND FLOOR PLAN
HVAC & PLUMBING**
Project No./No. du
R.076325.006
Sheet/Feuille
M22
Revision no./
no. de version
0

TYPE	DIMENSIONS		
	a	b	c
1	280	280	380
2	250	380	375

NOTE: A & B ARE CLEAR INSIDE DIMENSIONS
(PREP AREA)



4 CROSS-TALK SILENCER DETAIL
N.T.S.




1 SECOND FLOOR HVAC PLAN
1:100

UNIT	NOTES
S-1	SINK: TYPE 304, 18-10 STAINLESS STEEL, 20 GA. SELF-RIMMING WITH POSITIVE HOLD DOWN CLAMPS. SATIN FINISH ON EXPOSED SURFACES. UNDERCOUNTER ON BOTTOM. 89 MM GRUBB CAP WASTES. LEDGE BACK DRILLED TO FIT FAUCET. BOWL DIMENSIONS TO MEET MILLWORK REQUIREMENTS (COORDINATE WITH ARCHITECTURAL DRAWINGS). TRIM: DECKMOUNT, 200MM CENTRES. TWO HANDLE WITH GOOSENECK FAUCET. CHROME PLATED CAST BRASS WITH 5.7 L/M VANDAL RESISTANT FLOW CONTROL AERATOR AND 76 MM BLADE HANDLES. CERAMIC TRIM.
WC-1	FLOOR MOUNTED FLUSH VALVE, BARRIER FREE. FIXTURE: WHITE VITREOUS CHINA WITH ELONGATED RIM, 432 MM HIGH, HIGH EFFICIENCY FLUSH BOWL, SIMON 1.1 ACTION WITH FULLY GAZED 50 MM BALL PASS TRAVEL, 4.8 L/P, .300 MM ROUGH-IN, C/W OPEN FRONT SEAT.
C/W	THERMOSTATIC MIXING VALVE, OFFSET OPEN GRID STRAINER AND CARRIER. VITREOUS CHINA, WALL MOUNT, BARRIER FREE WITH CARRIER (REQUIRED TO FLOOR), ELECTRONIC FAUCET, FIXTURE: WHITE VITREOUS CHINA, CONTIGUOUS RECTANGULAR BASIN, REAR OVERFLOW, MOUNTING BRACKET, BACK SPASH LEDGE, FCG CONCALED ARM CARRIER INSTALLATION, DECK MOUNT, ELECTRONIC FAUCET, ALL METAL SPOUT CONSTRUCTION, PROXIMITY SENSING TECHNOLOGY, HANDWIRE C/W 21 VAC TO 6 VDC CONVERTER, SURFACE MOUNT CONTROL BOX, VANDAL RESISTANT 1.9 L/M LAMINAR OUTLET. PROVIDE TRANSFORMER AND THERMOSTATIC MIXING VALVE MIXING VALVE TO BE INSTALLED IN CEILING SPACE IN CORRIDOR.

- KEYNOTES:
- EXISTING FORCE FLOWS TO REMAIN. MECH. CONTRACTOR TO REVIEW UNIFORM FLOOR COVER TO MATCH NEW WALL COLOUR PAINTING BY GENERAL CONTRACTOR.
 - TYPE "T" CROSS TALK SILENCER TO BE INSTALLED IN CEILING SPACE REFER TO DRAWING DETAIL 3.
 - 20MM PEW WATER LINES TO REMOVE AND COVER W/VALVE. OTHER LINES TO BE COVERED.

2 PARTIAL SECOND FLOOR PLUMBING PLAN
1:50



FIXTURE	DCW	DHW	SNM
(WC-) WATER CLOSET (TANK)	12	12	75
(L-) LAVATORY	12	11	32
(DW-) DISHWASHER	12	12	12
	12	12	12