

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for all equipment for this section.
- .3 Shop Drawings:
 - .1 Submit drawings reviewed by a professional engineer registered or licensed in Saskatchewan, Canada.
 - .2 Indicate on drawings:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
- .4 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Reduction Workplan highlighting recycling and salvage requirements.

1.2 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00- Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for this section.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Consultant before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .3 Maintenance data to include:

- .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
- .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93- Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
 - .1 Submit two (2) copies of draft Operation and Maintenance Manual to consultant for approval. Submission of individual data will not be accepted unless directed by Consultant.
 - .2 Make changes as required and re-submit as directed by consultant.
- .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
 - .1 Consultant will provide one (1) set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Consultant for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00- Closeout Submittals.
- .2 Furnish spare parts as follows:
 - .1 One set of packing for each pump.
 - .2 One casing joint gasket for each size pump.
 - .3 One head gasket set for each heat exchanger.
 - .4 One glass for each gauge glass.
 - .5 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.
- .3 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .4 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect against nicks, scratches, and blemishes
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.

Part 2 Products

2.1 MATERIALS

- .1 Not Used.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of installations correspond to work shown on drawings.
 - .1 Visually inspect site conditions.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 PAINTING REPAIRS AND RESTORATION

- .1 Do painting in accordance with Section 09 91 23- Interior Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

3.3 SYSTEM CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00- Quality Control and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.5 DEMONSTRATION

- .1 Consultant will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Trial usage to apply to following equipment and systems:
 - .1 Air Distribution
 - .2 Hydronic or Electric heating equipment
- .3 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .4 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .5 Instruction duration time requirements as specified in appropriate sections.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.

- .3 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.

- .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.7 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 QUALITY ASSURANCE

- .1 Sustainability Standards Certification:
 - .1 Low-Emitting Materials: provide listing of sealants, coatings used in building, comply with VOC and chemical component limits or restriction requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

Part 2 Products

2.1 MATERIAL

- .1 Paint: zinc-rich to CAN/CGSB-1.181.
- .2 Sealants: in accordance with Section 07 92 00- Joint Sealants.
 - .1 Sealants: maximum VOC limit to SCAQMD Rule 1168.
- .3 Sealants: maximum VOC limit to SCAQMD Rule 1168.
- .4 Adhesives: maximum VOC limit to SCAQMD Rule 1168.
- .5 Fire Stopping: in accordance with all NFPA requirements.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 CONNECTIONS TO EQUIPMENT

- .1 In accordance with manufacturer's instructions unless otherwise indicated.
- .2 Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3 Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

3.3 CLEARANCES

- .1 Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer, CSA B139 and the National Fire Code of Canada.
- .2 Provide space for disassembly, removal of equipment and components as recommended by manufacturer, CSA B139, as indicated without interrupting operation of other system, equipment, and components.

3.4 DRAINS

- .1 Install piping with grade in direction of flow except as indicated.
- .2 Install drain valve at low points in piping systems, at equipment and at section isolating valves.
- .3 Pipe each drain valve discharge separately to above floor drain.
 - .1 Discharge to be visible.
- .4 Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

3.5 AIR VENTS

- .1 Install air vents to at high points in piping systems CSA B139.
- .2 Install isolating valve at each automatic air valve.
- .3 Install drain piping to approved location and terminate where discharge is visible.

3.6 DIELECTRIC COUPLINGS

- .1 General: compatible with system, to suit pressure rating of system.
- .2 Locations: where dissimilar metals are joined.
- .3 NPS 2 and under: isolating unions or bronze valves.

3.7 PIPEWORK INSTALLATION

- .1 Install pipework to CSA B139.
- .2 Screwed fittings jointed with Teflon tape.
- .3 Protect openings against entry of foreign material.
- .4 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .5 Assemble piping using fittings manufactured to ANSI standards.
- .6 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
 - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .7 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .8 Install concealed pipework to minimize furring space, maximize headroom, conserve space.
- .9 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .10 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .11 Group piping wherever possible and as indicated.
- .12 Ream pipes, remove scale and other foreign material before assembly.
- .13 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.
- .14 Provide for thermal expansion as indicated.
- .15 Valves:
 - .1 Install in accessible locations.
 - .2 Remove interior parts before soldering.
 - .3 Install with stems above horizontal position unless indicated.
 - .4 Valves accessible for maintenance without removing adjacent piping.
 - .5 Install globe valves in bypass around control valves.
 - .6 Use valves at branch take-offs for isolating purposes except where specified.
 - .7 Install plug cocks ball valves for glycol service.
 - .8 Use chain operators on valves NPS 2 1/2 and larger where installed more than 2400mm above floor in Mechanical Rooms.

3.8 ESCUTCHEONS

- .1 Install on pipes passing through walls, partitions, floors, and ceilings in finished areas.
- .2 Construction: one piece type with set screws.
 - .1 Chrome or nickel plated brass or type 302 stainless steel..
- .3 Sizes: outside diameter to cover opening or sleeve.

- .1 Inside diameter to fit around pipe or outside of insulation if so provided.

3.9 PREPARATION FOR FIRE STOPPING

- .1 Install firestopping within annular space between pipes, ducts, insulation and adjacent fire separation.
- .2 Uninsulated unheated pipes not subject to movement: no special preparation.
- .3 Uninsulated heated pipes subject to movement: wrap with non-combustible smooth material to permit pipe movement without damaging firestopping material or installation.
- .4 Insulated pipes and ducts: ensure integrity of insulation and vapour barriers.

3.10 FLUSHING OUT OF PIPING SYSTEMS

- .1 Flush system in accordance with Section 23 08 02- Cleaning and Start-up of Mechanical Piping Systems.
- .2 Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

3.11 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK

- .1 Advise Consultant 48 hours minimum prior to performance of pressure tests.
- .2 PIPework: test as specified in relevant sections of heating, ventilating and air conditioning work.
- .3 Maintain specified test pressure without loss for 4 hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Pay costs for repairs or replacement, retesting, and making good. Consultant to determine whether repair or replacement is appropriate.
- .5 Insulate or conceal work only after approval and certification of tests by Consultant.

3.12 EXISTING SYSTEMS

- .1 Connect into existing piping systems at times approved by building operation staff outside of regular office hours.
- .2 Request written approval by ten (10) days minimum, prior to commencement of work.
- .3 Be responsible for damage to existing plant by this work.

3.13 CLEANING

- .1 Clean in accordance with Section 01 74 11- Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 230500 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 National Research Council Canada (NRC)
 - .1 National Plumbing Code of Canada 2015(NPC).
- .2 Underwriter's Laboratories of Canada (ULC)

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for hangers and supports and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
 - .1 Consultant will make available one (1) copy of systems supplier's installation instructions.

1.4 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00- Closeout Submittals.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Design Requirements:

- .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
- .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP58.
- .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
- .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
- .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

2.2 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15- Sustainable Requirements: Construction.

2.3 GENERAL

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP58. ANSI B31.1
- .2 Use components for intended design purpose only. Do not use for rigging or erection purposes.

2.4 PIPE HANGERS

- .1 Finishes:
 - .1 Pipe hangers and supports: galvanized after manufacture.
 - .2 Ensure steel hangers in contact with copper piping are epoxy coated or copper plated.
- .2 Upper attachment structural: suspension from lower flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: malleable iron C-clamp with hardened steel cup point setscrew, locknut.
 - .1 Rod: 9 mm UL listed.
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron beam clamp, eye rod, jaws and extension with carbon steel retaining clip, tie rod, nuts and washers, UL listed.
- .3 Upper attachment structural: suspension from upper flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: ductile iron top-of-beam C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip, UL listed.
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron top-of-beam jaw-clamp with hooked rod, spring washer, plain washer and nut UL listed.
- .4 Upper attachment to concrete:
 - .1 Ceiling: carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.

- .2 Concrete inserts: wedge shaped body with knockout protector plate UL listed.
- .3 Hanger rods: threaded rod material UL listed:
- .4 Ensure that hanger rods are subject to tensile loading only.
- .5 Provide linkages where lateral or axial movement of pipework is anticipated.
- .6 Do not use 22 mm or 28 mm rod.
- .5 Pipe attachments:
 - .1 Attachments for steel piping: carbon steel.
 - .2 Attachments for copper piping: copper plated black steel.
 - .3 Use insulation shields for hot pipework.
 - .4 Oversize pipe hangers and supports.
- .6 Adjustable clevis: material to UL listed, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
 - .1 Ensure "U" has hole in bottom for rivetting to insulation shields.
- .7 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to CSA standards.
- .8 U-bolts: carbon steel to CSA standards with 2 nuts at each end to ASTM A563.
 - .1 Finishes for steel pipework: black or galvanized.
 - .2 Finishes for copper, glass, brass or aluminum pipework: black, epoxy coated or galvanized , with formed portion plastic coated.
- .9 Pipe rollers: cast iron roll and roll stand with carbon steel rod. To be UL or ULC Listed.

2.5 RISER CLAMPS

- .1 Steel or cast iron pipe: black or galvanized carbon steel type 42, UL listed.
- .2 Copper pipe: carbon steel copper plated to MSS SP58, type 42.
- .3 Bolts: to ASTM A307.
- .4 Nuts: to ASTM A563.

2.6 INSULATION PROTECTION SHIELDS

- .1 Insulated cold piping:
 - .1 64 kg/m³ density insulation plus insulation protection shield :
 - .1 galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
 - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel.

2.7 EQUIPMENT ANCHOR BOLTS AND TEMPLATES

- .1 Provide templates to ensure accurate location of anchor bolts.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with:
 - .1 Manufacturer's instructions and recommendations.
- .2 Vibration Control Devices:
 - .1 Install on piping systems at pumps, boilers, chillers, cooling towers, and as indicated.
- .3 Clamps on riser piping:
 - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.
 - .2 Bolt-tightening torques to industry standards.
 - .3 Steel pipes: install below coupling or shear lugs welded to pipe.
 - .4 Cast iron pipes: install below joint.
- .4 Clevis plates:
 - .1 Attach to concrete with four (4) minimum concrete inserts, one (1) at each corner.
- .5 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.

3.3 HANGER SPACING

- .1 Plumbing piping: to National Plumbing Code of Canada (NPC).
- .2 Fire protection: to applicable fire code.
- .3 Gas and fuel oil piping: up to NPS 1/2: every 1.8 m.
- .4 Copper piping: up to NPS 1/2: every 1.5 m.
- .5 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.
- .6 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.4 m	1.8 m
1-1/2	3.0 m	2.4 m
2	3.0 m	2.4 m
2-1/2	3.7 m	3.0 m
4	3.7 m	3.6 m

- .7 Pipework greater than NPS 12: to MSS SP69.

3.4 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.5 HORIZONTAL MOVEMENT

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.6 FINAL ADJUSTMENT

- .1 Adjust hangers and supports:
 - .1 Ensure that rod is vertical under operating conditions.
 - .2 Equalize loads.
- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

3.7 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.
- .2 Verification requirements in accordance with Section 01 47 17- Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.

- .2 Storage and collection of recyclables.
- .3 Construction waste management.
- .4 Resource reuse.
- .5 Recycled content.
- .6 Local/regional materials.
- .7 Certified wood.
- .8 Low-emitting materials.

3.8 CLEANING

- .1 Clean in accordance with Section 01 74 11- Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling or reuse in accordance with 01 74 21- Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Consultant within ninety (90) days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 PRE-TAB REVIEW

- .1 Review Contract Documents before project construction is started, confirm in writing to Consultant of adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report Consultant in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.8 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Consultant for verification of TAB reports.

1.9 START OF TAB

- .1 Notify consultant seven (7) days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
 - .3 Installation of ceilings, doors, windows, other construction affecting TAB.
 - .4 Application of weatherstripping, sealing, and caulking.
 - .5 Pressure, leakage, other tests specified elsewhere.
 - .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.

- .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
- .4 Correct fan rotation.
- .5 Fire, smoke, volume control dampers installed and open.
- .6 Coil fins combed, clean.
- .7 Access doors, installed, closed.
- .8 Outlets installed, volume control dampers open.
- .3 Liquid systems:
 - .1 Filled, vented.
 - .2 Isolating and balancing valves installed, open.

1.10 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 5%, minus 5%.

1.11 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2% of actual values.

1.12 INSTRUMENTS

- .1 Prior to TAB, submit to list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Consultant.

1.13 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Consultant, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.
 - .4 Summaries.

1.15 TAB REPORT

- .1 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.

- .2 Submit three (3) copies of TAB Report to Consultant for verification and approval, in English in D-ring binders, complete with index tabs.

1.16 VERIFICATION

- .1 Reported results subject to verification by Consultant.
- .2 Provide personnel and instrumentation to verify up to 30% of reported results.
- .3 Number and location of verified results as directed by Consultant.
- .4 Pay costs to repeat TAB as required to satisfaction of Consultant.

1.17 SETTINGS

- .1 After TAB is completed to satisfaction of Consultant, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Consultant.

1.19 AIR SYSTEMS

- .1 Standard: TAB to most stringent of ASHRAE, SMACNA, or NEBB.
- .2 Do TAB of all systems and components in this contract.
- .3 Qualifications: personnel performing TAB qualified to all Regulations and standards.
- .4 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .5 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .6 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

.1 Not used.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 230500 – Common Work Results for HVAC

1.2 REFERENCE STANDARDS

- .1 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
- .2 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (2005).
- .3 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-03, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-05, Standard for Thermal Insulation, Polystyrene, Boards and Pipe Covering.

1.3 DEFINITIONS

- .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - means "not concealed" as previously defined.
 - .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
- .2 TIAC Codes:
 - .1 CRD: Code Round Ductwork,
 - .2 CRF: Code Rectangular Finish.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for duct insulation, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .1 Description of equipment giving manufacturer's name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.
 - .2 Mount sample on 12 mm plywood board.
 - .3 Affix typewritten label beneath sample indicating service.

1.5 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: specialist in performing work of this section, and have at least 3 years successful experience in this size and type of project, qualified to standards.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00- Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address and ULC markings.

Part 2 Products

2.1 FIRE AND SMOKE RATING

- .1 To CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre: glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma.
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 JACKETS

- .1 Canvas:
 - .1 220gm/m²cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .2 Lagging adhesive: compatible with insulation.
 - .1 Maximum VOC limit 70g/L.
- .3 Aluminum:
 - .1 To ASTM B209 with moisture barrier as scheduled in PART 3 of this section.
 - .2 Thickness: 0.50 mm sheet.
 - .3 Finish: Smooth

- .4 Jacket banding and mechanical seals: 19 mm wide, 0.5 mm thick stainless steel.
 - .1 Stainless steel:
- .5 Type: 304.
- .6 Thickness: 0.50mm sheet.
- .7 Finish: Smooth
- .8 Jacket banding and mechanical seals: 12mm wide, 0.5 mm thick stainless steel.

2.4 ACCESSORIES

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.
 - .1 Maximum VOC limit 50g/L.
 - .2 SPEC NOTE: Specify when indoor vapour retarder finish is required over insulation.
- .2 Indoor Vapour Retarder Finish:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 ULC Listed Canvas Jacket:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .5 Tape: self-adhesive, aluminum, reinforced, 50mm wide minimum.
- .6 Contact adhesive: quick-setting
 - .1 Maximum VOC limit 50g/L.
- .7 Canvas adhesive: washable.
 - .1 Maximum VOC limit 50g/L.
- .8 Tie wire: 1.5mm stainless steel.
- .9 Banding: 12 mm wide, 0.5mm thick stainless steel.
- .10 Facing: 25mm galvanized or stainless steel hexagonal wire mesh stitched on both faces of insulation.
- .11 Fasteners: 4 mm diameter pins with 35mm clips, length to suit thickness of insulation.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 PRE-INSTALLATION REQUIREMENTS

- .1 Pressure test ductwork systems complete, witness and certify.

- .2 Ensure surfaces are clean, dry, and free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and as indicated.
- .3 Use 2 layers with staggered joints when required nominal thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
- .1 Ensure hangers, and supports are outside vapour retarder jacket.
- .5 Hangers and supports in accordance with Section 23 05 29- Hangers and Supports for HVAC Piping and Equipment.
- .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: install at 300 mm on centre in horizontal and vertical directions, minimum (2) rows each side.

3.4 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: conform to following table:

Duct Type	Vapour Retarder	Thickness (mm)
Rectangular dual temperature supply air ducts	Yes	50
Round dual temperature supply air ducts	Yes	50
Round warm air ducts	Yes	25
Acoustically lined ducts	No	

- .2 Exposed round ducts 600 mm and larger, smaller sizes where subject to abuse:

- .1 Use TIAC code C-1 insulation, scored to suit diameter of duct.

- .1 Finishes: conform to following table:

Duct Type		
Rectangular	Round	
Indoor, concealed	none	none
Indoor, exposed within mechanical room	CRF/1	CRD/2

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11- Cleaning.
- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling or reuse in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Thermal insulation for piping and piping accessories in commercial type applications.
- .2 Related Requirements
 - .1 Section 23 05 00 – Common Work Results for HVAC
 - .2 Section 22 05 00 – Common Work Results for Plumbing

1.2 REFERENCE STANDARDS

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 Manufacturer's Trade Associations
 - .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (Revised 2004).
- .3 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-03, Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-01, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
 - .3 CAN/ULC-S702-1997, Thermal Insulation, Mineral Fibre, for Buildings
 - .4 CAN/ULC-S702.2-03, Thermal Insulation, Mineral Fibre, for Buildings, Part 2: Application Guidelines.

1.3 DEFINITIONS

- .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC ss:
 - .1 CRF: Code Rectangular Finish.
 - .2 CPF: Code Piping Finish.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:

- .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00- Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit 2 (two) copies of Workplace Hazardous Materials Information System (WHMIS) or Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00- Submittal Procedures.

1.5 QUALITY ASSURANCE

- .1 Qualifications:
- .2 Installer: specialist in performing work of this Section, and have at least three (3) years successful experience in this size and type of project, qualified to standards of TIAC.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00- Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Storage and Protection:
 - .1 Protect from weather, construction traffic.
 - .2 Protect against damage.
 - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for recycling or reuse in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .2 Place excess or unused insulation and insulation accessory materials in designated containers.
 - .3 Divert unused metal materials from landfill to metal recycling facility approved by Consultant.
 - .4 Dispose of unused adhesive material at official hazardous material collections site approved by Consultant

Part 2 Products

2.1 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15- Sustainable Requirements: Construction.

2.2 FIRE AND SMOKE RATING

- .1 In accordance with CAN/ULC-S102.
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.3 INSULATION

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.
 - .2 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-3: rigid moulded mineral fibre with factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to CAN/ULC-S702.
- .5 TIAC Code C-2: mineral fibre blanket faced with factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to CAN/ULC-S702.
- .6 TIAC Code A-6: flexible unicellular tubular elastomer.
 - .1 Insulation: with vapour retarder jacket.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Certified by manufacturer: free of potential stress corrosion cracking corrodants.
- .7 TIAC Code A-2: rigid moulded calcium silicate in sections and blocks, and with special shapes to suit project requirements.
 - .1 Insulation: to (ASTM C533).
 - .2 Design to permit periodic removal and re-installation.

2.4 INSULATION SECUREMENT

- .1 Tape: self-adhesive, aluminum, reinforced, 50 mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Tie wire: 1.5mm diameter stainless steel.
- .5 Bands: stainless steel, 19mm wide, 0.5mm thick.

2.5 CEMENT

- .1 Thermal insulating and finishing cement:
 - .1 Air drying on mineral wool, to ASTM C449/C449M.

2.6 VAPOUR RETARDER LAP ADHESIVE

- .1 Water based, fire retardant type, compatible with insulation.

2.7 INDOOR VAPOUR RETARDER FINISH

- .1 Vinyl emulsion type acrylic, compatible with insulation.

2.8 OUTDOOR VAPOUR RETARDER FINISH

- .1 Vinyl emulsion type acrylic, compatible with insulation.
- .2 Reinforcing fabric: fibrous glass, untreated 305 g/m².

2.9 JACKETS

- .1 Polyvinyl Chloride (PVC):
 - .1 One-piece moulded type to CAN/CGSB-51.53 with pre-formed shapes as required.
 - .2 Colours: White.
 - .3 Minimum service temperatures: -20 degrees C.
 - .4 Maximum service temperature: 65 degrees C.
 - .5 Moisture vapour transmission: 0.02 perm.
 - .6 Fastenings: Use solvent weld adhesive compatible with insulation to seal laps and joints.
 - .1 Tacks.
 - .2 Pressure sensitive vinyl tape of matching colour.

2.10 WEATHERPROOF CAULKING FOR JACKETS INSTALLED OUTDOORS

- .1 Caulking to: Section 07 92 00- Joint Sealants.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PRE-INSTALLATION REQUIREMENT

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and this specification.
- .3 Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Install hangers, supports outside vapour retarder jacket.
- .5 Supports, Hangers:
 - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

3.4 REMOVABLE, PRE-FABRICATED, INSULATION AND ENCLOSURES

- .1 Application: at expansion joints, valves.
- .2 Design: to permit movement of expansion joint without damage to adjacent insulation.
- .3 Insulation:
 - .1 Insulation, fastenings and finishes: same as system.
 - .2 Jacket: PVC

3.5 INSTALLATION OF ELASTOMERIC INSULATION

- .1 Insulation to remain dry. Overlaps to manufacturer's instructions. Ensure tight joints.
- .2 Provide vapour retarder as recommended by manufacturer.

3.6 PIPING INSULATION SCHEDULES

- .1 Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2 TIAC Code: (A-1).
 - .1 Securements: Tape wire/band at 300 mm on centre.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code 1501-H.
- .3 TIAC Code: (A-3).
 - .1 Securements: Tape at 300 mm on centre.
 - .2 Seals: VR lap seal adhesive, VR lagging adhesive.
 - .3 Installation: TIAC Code: 1501-C.

Application	Temp degrees C	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)
Hot Water Heating	60 - 94	A-1	25
Domestic HWS	All	A-1	25
Domestic CWS	All	A-3	25

- .4 Finishes:
 - .1 Exposed indoors: PVC jacket.
 - .2 Exposed in mechanical rooms: PVC jacket.
 - .3 Concealed: PVC Jacket
 - .4 Use vapour retarder jacket on TIAC code A-3 insulation compatible with insulation.
 - .5 Installation: to appropriate TIAC code CRF/1 through CPF/5.

3.7 CLEANING

- .1 Proceed in accordance with Section 01 74 11- Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Procedures and cleaning solutions for cleaning mechanical piping systems.
- .2 Related Requirements
 - .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM E202-00, Standard Test Methods for Analysis of Ethylene Glycols and Propylene Glycols.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00- Submittal Procedures. Include product characteristics, performance criteria, and limitations.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00- Submittal Procedures.
 - .1 Instructions: submit manufacturer's installation instructions.
 - .1 Consultant will make available one (1) copy of systems supplier's installation instructions.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00- Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for recycling or reuse in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 CLEANING SOLUTIONS

- .1 Tri-sodium phosphate: 0.40 kg per 100 L water in system.
- .2 Sodium carbonate: 0.40 kg per 100 L water in system.
- .3 Low-foaming detergent: 0.01 kg per 100 L water in system.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 CLEANING HYDRONIC AND STEAM SYSTEMS

- .1 Timing: systems operational, hydrostatically tested and with safety devices functional, before cleaning is carried out.
- .2 Cleaning Agency:
 - .1 Retain qualified water treatment specialist to perform system cleaning.
- .3 Install instrumentation such as flow meters, orifice plates, pitot tubes, flow metering valves only after cleaning is certified as complete by water treatment specialist.
- .4 Cleaning procedures:
 - .1 Provide detailed report outlining proposed cleaning procedures at least four (4) weeks prior to proposed starting date. Report to include:
 - .1 Cleaning procedures, flow rates, elapsed time.
 - .2 Chemicals and concentrations used.
 - .3 Inhibitors and concentrations.
 - .4 Specific requirements for completion of work.
 - .5 Special precautions for protecting piping system materials and components.
 - .6 Complete analysis of water used to ensure water will not damage systems or equipment.
- .5 Conditions at time of cleaning of systems:
 - .1 Systems: free from construction debris, dirt and other foreign material.
 - .2 Control valves: operational, fully open to ensure that terminal units can be cleaned properly.
 - .3 Strainers: clean prior to initial fill.
 - .4 Install temporary filters on pumps not equipped with permanent filters.
 - .5 Install pressure gauges on strainers to detect plugging.
- .6 Report on Completion of Cleaning:
 - .1 When cleaning is completed, submit report, complete with certificate of compliance with specifications of cleaning component supplier.
- .7 Hydronic Systems:
 - .1 Fill system with water, ensure air is vented from system.
 - .2 Fill expansion tanks 1/3 to 1/2 full, charge system with compressed air to at least 35 kPa (does not apply to diaphragm type expansion tanks).
 - .3 Use water metre to record volume of water in system to +/- 0.5%.

- .4 Add chemicals under direct supervision of chemical treatment supplier.
- .5 Closed loop systems: circulate system cleaner at 60 degrees C for at least 36 h. Drain as quickly as possible. Refill with water and inhibitors. Test concentrations and adjust to recommended levels.
- .6 Flush velocity in system mains and branches to ensure removal of debris. System pumps may be used for circulating cleaning solution provided that velocities are adequate.
- .7 Add chemical solution to system.
- .8 Establish circulation, raise temperature slowly to 82 degrees C minimum. Circulate for 12 h, ensuring flow in all circuits. Remove heat, continue to circulate until temperature is below 38 degrees C. Drain as quickly as possible. Refill with clean water. Circulate for 6 hours at design temperature. Drain and repeat procedures specified above. Flush through low point drains in system. Refill with clean water adding to sodium sulphite (test for residual sulphite).
- .8 Glycol Systems:
 - .1 In addition to procedures specified above perform specified procedures.
 - .2 Test to prove concentration will prevent freezing to minus 40 degrees C. Test inhibitor strength and include in procedural report. Refer to ASTM E202.

3.3 START-UP OF HYDRONIC SYSTEMS

- .1 After cleaning is completed and system is filled:
 - .1 Establish circulation and expansion tank level, set pressure controls.
 - .2 Ensure air is removed.
 - .3 Check pumps to be free from air, debris, possibility of cavitation when system is at design temperature.
 - .4 Dismantle system pumps used for cleaning, inspect, replace worn parts, install new gaskets and new set of seals.
 - .5 Clean out strainers repeatedly until system is clean.
 - .6 Check water level in expansion tank with cold water with circulating pumps OFF and again with pumps ON.
 - .7 Repeat with water at design temperature.
 - .8 Check pressurization to ensure proper operation and to prevent water hammer, flashing, cavitation. Eliminate water hammer and other noises.
 - .9 Bring system up to design temperature and pressure slowly 48 hour period.
 - .10 Perform TAB as specified in Section 23 05 93- Testing, Adjusting and Balancing for HVAC.
 - .11 Adjust pipe supports, hangers, springs as necessary.
 - .12 Monitor pipe movement, performance of expansion joints, loops, guides, anchors.
 - .13 Re-tighten bolts using torque wrench, to compensate for heat-caused relaxation. Repeat several times during commissioning.
 - .14 Check operation of drain valves.
 - .15 Adjust valve stem packings as systems settle down.

- .16 Fully open balancing valves (except those that are factory-set).
- .17 Check operation of over-temperature protection devices on circulating pumps.
- .18 Adjust alignment of piping at pumps to ensure flexibility, adequacy of pipe movement, absence of noise or vibration transmission.

3.4 FIELD QUALITY CONTROL

- .1 Verification requirements in accordance with Section 01 47 17- Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.
 - .2 Storage and collection of recyclables.
 - .3 Construction waste management.
 - .4 Resource reuse.
 - .5 Recycled content.
 - .6 Local/regional materials.
 - .7 Certified wood.
 - .8 Low-emitting materials.

3.5 CLEANING

- .1 Proceed in accordance with Section 01 74 11- Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for piping, valves and fittings for gas fired equipment.
- .2 Related Requirements
 - .1 Section 23 05 00 - Common Work Results for HVAC

1.2 REFERENCE STANDARDS

- .1 Canadian Standards Association (CSA International)
 - .1 CSA W47.1-03, Certification of Companies for Fusion Welding of Steel.
- .2 Canadian Standards Association (CSA)/Canadian Gas Association (CGA)
 - .1 CAN/CSA B149.1HB-00, Natural Gas and Propane Installation Code Handbook.
 - .2 CAN/CSA B149.2-00, Propane Storage and Handling Code.
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet for piping, fittings and equipment.
 - .2 Indicate on manufacturers catalogue literature following: valves.
 - .3 Indicate VOC's for adhesive and solvents during application and curing.
- .3 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Closeout Submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00- Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Pre-Installation Meeting:
 - .1 Review existing conditions.
 - .2 Co-ordination with other building subtrades and utility company.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Separate waste materials for recycling or reuse in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal packaging material for recycling in accordance with Waste Management Plan (WMP).
 - .4 Divert unused metal materials from landfill to metal recycling facility.

Part 2 Products

2.1 MATERIALS

- .1 Materials and products in accordance with Section 01 47 15- Sustainable Requirements: Construction.

2.2 PIPE

- .1 Steel pipe: to ASTM A53/A53M, Schedule 40, seamless as follows:
 - .1 NPS 1/2 to 2, screwed.
 - .2 NPS 2 1/2 and over, plain end.
- .2 Copper tube: to ASTM B837.

2.3 JOINTING MATERIAL

- .1 Screwed fittings: pulverized lead paste.
- .2 Welded fittings: to CSA W47.1.
- .3 Flange gaskets: nonmetallic flat.
- .4 Brazing: to ASTM B837.

2.4 FITTINGS

- .1 Steel pipe fittings, screwed, flanged or welded:
 - .1 Malleable iron: screwed, banded, Class 150.
 - .2 Steel pipe flanges and flanged fittings: to ASME B16.5.
 - .3 Welding: butt-welding fittings.
 - .4 Unions: malleable iron, brass to iron, ground seat, to ASTM A47/A47M.
 - .5 Bolts and nuts: to ASME B18.2.1.
 - .6 Nipples: schedule 40, to ASTM A53/A53M.
- .2 Copper pipe fittings, screwed, flanged or soldered:
 - .1 Cast copper fittings: to ASME B16.18.
 - .2 Wrought copper fittings: to ASME B16.22.

2.5 VALVES

- .1 Provincial Code approved, lubricated ball or plug type.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PIPING

- .1 Install in accordance with Section 23 05 05- Installation of Pipework, CAN/CSA B149.2, applicable Provincial/Territorial Regulations, CAN/CSA B149.1, supplemented as specified.
- .2 Install drip points:
 - .1 At low points in piping system.
 - .2 At connections to equipment.
- .3 Relocate any pipe, including existing vent lines, for natural gas system as required to meet requirements of new line installations and for relocation of meters.

3.3 VALVES

- .1 Install valves with stems upright or horizontal unless otherwise approved by Consultant.
- .2 Install valves at branch take-offs to isolate pieces of equipment, and as indicated.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Test system in accordance with CAN/CSA B149.2 and requirements of authorities having jurisdiction.
- .2 Obtain reports within three (3) days of review and submit immediately to Consultant.
- .3 Verification requirements in accordance with Section 01 47 17- Sustainable Requirements.
- .4 Performance Verification:
 - .1 Refer to Section 23 08 01- Performance Verification of Mechanical Piping Systems.

3.5 ADJUSTING

- .1 Purging: purge after pressure test in accordance with CAN/CSA B149.1.
- .2 Pre-Start-Up Inspections:
 - .1 Check vents from regulators, control valves, terminate outside building in approved location, protected against blockage, damage.

- .2 Check gas trains, entire installation is approved by authority having jurisdiction.

3.6 CLEANING

- .1 Cleaning: in accordance with Section CAN/CSA B149.1, 23 08 02- Cleaning and Start-Up of Mechanical Piping Systems, CAN/CSA B149.2.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

3.7 NATURAL GAS INSTALLED BY LOCAL UTILITY

- .1 General contractor to coordinate and pay all fees associated with relocation of natural gas meter.
- .2 Ensure new work performed by utility provider matches existing and that all new connections can be made to existing system.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible 2005.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for air duct accessories and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Reduction Work plan highlighting recycling and salvage requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00- Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect air duct accessories from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.

Part 2 Products

2.1 GENERAL

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 FLEXIBLE CONNECTIONS

- .1 Frame: galvanized sheet metal frame
- .2 Material:
 - .1 Fire resistant, self-extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3kg/m2.

2.3 ACCESS DOORS IN DUCTS

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: foam rubber or neoprene.
- .4 Hardware:
 - .1 Up to 300 x 300 mm: two sash locks complete with safety chain.

2.4 INSTRUMENT TEST

- .1 1.6mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for air duct accessories installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Consultant.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Flexible Connections:
 - .1 Install in following locations:

- .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
- .2 Length of connection: 1000 mm.
- .3 Minimum distance between metal parts when system in operation: 75mm.
- .4 Install in accordance with recommendations of SMACNA.
- .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.
- .2 Access Doors and Viewing Panels:
 - .1 Size:
 - .1 As indicated.
 - .2 Locations:
 - .1 Fire and smoke dampers.
 - .2 Control dampers.
 - .3 Devices requiring maintenance.
 - .4 Required by code.
 - .5 Reheat coils.
 - .6 Elsewhere as indicated.
- .3 Instrument Test Ports:
 - .1 General:
 - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .2 Locate to permit easy manipulation of instruments.
 - .3 Install insulation port extensions as required.
 - .4 Locations:
 - .1 For traverse readings:
 - .1 Ducted inlets to roof and wall exhausters.
 - .2 Inlets and outlets of other fan systems.
 - .3 Main and sub-main ducts.
 - .4 And as indicated.
 - .2 For temperature readings:
 - .1 At outside air intakes.
 - .2 In mixed air applications in locations as approved by Consultant.
 - .3 At inlet and outlet of coils.
 - .4 Downstream of junctions of two converging air streams of different temperatures.
 - .5 And as indicated.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.
- .3 Waste Management: separate waste materials for reuse or recycling in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 230500 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 Sheet Metal and Air Conditioning National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards, Metal and Flexible-2013.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for dampers and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00- Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for dampers for incorporation into manual.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect dampers from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

Part 2 Products

2.1 GENERAL

- .1 Manufacture to SMACNA standards.

2.2 SINGLE BLADE DAMPERS

- .1 Fabricate from same material as duct, but one sheet metal thickness heavier. V-groove stiffened.
- .2 Size and configuration to recommendations of SMACNA, except maximum height 100 mm.
- .3 Locking quadrant with shaft extension to accommodate insulation thickness where required.
- .4 Inside and outside bronze or nylon end bearings.
- .5 Channel frame of same material as adjacent duct, complete with angle stop.

2.3 MULTI-BLADED DAMPERS

- .1 Factory manufactured of material compatible with duct.
- .2 Opposed blade: configuration, metal thickness and construction to recommendations of SMACNA.
- .3 Maximum blade height: 100 mm.
- .4 Bearings: self-lubricating nylon.
- .5 Linkage: shaft extension with locking quadrant.
- .6 Channel frame of same material as adjacent duct, complete with angle stop.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for damper installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Consultant.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Install;
 - .1 As indicated on drawings,
 - .2 On all new supply branches,
 - .3 On existing branches were sections where balancing dampers are removed for diffuser relocations.

- .2 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
- .3 Locate balancing dampers in each branch duct, for supply, return and exhaust systems.
- .4 Runouts to registers and diffusers: install single blade damper located as close as possible to main ducts.
- .5 Dampers: vibration free.
- .6 Ensure damper operators are observable and accessible.
- .7 Corrections and adjustments conducted by Consultant.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.
- .3 Waste Management: separate waste materials for reuse or recycling in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 230500 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-12, Standard for the Installation of Air Conditioning and Ventilating Systems.
- .2 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S112-10, Standard Test Method of Fire Test of Fire Damper Assemblies.
 - .2 CAN/ULC-S112.2-07, Standard Method of Fire Test of Ceiling Fire Stop Flap Assemblies.
 - .3 ULC-S505-1974, Standard for Fusible Links for Fire Protection Service.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for fire and smoke dampers and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate the following:
 - .1 Fire dampers.
 - .2 Fire stop flaps.
 - .3 Operators.
 - .4 Fusible links.
 - .5 Design details of break-away joints.
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00- Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for fire and smoke dampers for incorporation into manual.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Submit maintenance materials in accordance with Section 01 78 00- Closeout Submittals.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect fire and smoke dampers from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Waste Reduction Work plan related to Work of this Section.

Part 2 Products

2.1 FIRE DAMPERS

- .1 Fire dampers: listed bearing label of UL, meet requirements of authorities having jurisdiction and NFPA 90A, provincial fire authority. Fire damper assemblies' fire tested in accordance with CAN/ULC-S112.
- .2 Mild steel, factory fabricated for fire rating requirement to maintain integrity of fire wall and/or fire separation.
 - .1 Fire dampers: 1-1/2 hour fire rated unless otherwise indicated.
 - .2 Fire dampers: automatic operating type and have dynamic rating suitable for maximum air velocity and pressure differential to which it will be subjected.
- .3 Top hinged: offset, round or square; interlocking type sized to maintain full duct cross section.
- .4 Fusible link actuated, weighted to close and lock in closed position when released or having negator-spring-closing operator for multi-leaf type or roll door type in horizontal position with vertical air flow.
- .5 40 x 40 x 3 mm retaining angle iron frame, on full perimeter of fire damper, on both sides of fire separation being pierced.
- .6 Equip fire dampers with steel sleeve or frame installed disruption ductwork or impair damper operation.
- .7 Equip sleeves or frames with perimeter mounting angles attached on both sides of wall or floor opening. Construct ductwork in fire-rated floor-ceiling or roof-ceiling assembly systems with air ducts that pierce ceiling to conform to ULC.

- .8 Design and construct dampers to not reduce duct or air transfer opening cross-sectional area.
- .9 Dampers shall be installed so that the centerline of the damper depth or thickness is located in the centerline of the wall, partition or floor slab depth or thickness.
- .10 Unless otherwise indicated, the installation details given in SMACNA Install Fire Damp HVAC and in manufacturer's instructions for fire dampers shall be followed.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for fire and smoke damper installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect conditions.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Install in accordance with NFPA 90A and in accordance with conditions of ULC listing.
- .2 Maintain integrity of fire separation.
- .3 After completion and prior to concealment obtain approvals of complete installation from authority having jurisdiction.
- .4 Install access door adjacent to each damper. See Section 23 33 00- Air Duct Accessories.
- .5 Co-ordinate with installer of fire stopping.
- .6 Ensure access doors/panels, fusible links, damper operators are easily observed and accessible.
- .7 Install break-away joints of approved design on each side of fire separation.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-12, Standard for the Installation of Air-Conditioning and Ventilating Systems.
 - .2 NFPA 90B-12, Standard for Installation of Warm Air Heating and Air-Conditioning Systems.
- .3 Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, 2005.
 - .2 SMACNA IAQ Guideline for Occupied Buildings under Construction, 2005.
- .4 Underwriters' Laboratories (UL)
 - .1 UL 181-2005, Standard for Factory-Made Air Ducts and Air Connectors.
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S110-2007, Standard Methods of Tests for Air Ducts.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for flexible ducts and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Thermal properties.
 - .2 Friction loss.
 - .3 Acoustical loss.
 - .4 Leakage.
 - .5 Fire rating.
- .3 Test and Evaluation Reports:
 - .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.
- .4 Sustainable Design Submittals:

- .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Replace defective or damaged materials with new.
- .4 Develop Waste Reduction Workplan related to Work of this Section.

Part 2 Products

2.1 GENERAL

- .1 Factory fabricated to CAN/ULC-S110.
- .2 Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.
- .3 Flame spread rating not to exceed 25. Smoke developed rating not to exceed 50.

2.2 METALLIC - UNINSULATED

- .1 Type 1: spiral wound flexible aluminum as indicated.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

2.3 METALLIC - INSULATED

- .1 Type 2: spiral wound flexible aluminum with factory applied, 37mm thick flexible glass fibre thermal insulation with vapour barrier and aluminum or reinforced mylar/neoprene laminate jacket, as indicated.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for flexible ducts installation in accordance with manufacturer's written instructions.

- .1 Visually inspect substrate in presence of Consultant.
- .2 Inform Consultant of unacceptable conditions immediately upon discovery.
- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed Consultant.

3.2 DUCT INSTALLATION

- .1 Install in accordance with: SMACNA, NFPA 90B, NFPA 90A, CAN/ULC-S110.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for HVAC fans and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings to be reviewed and stamped by professional engineer registered or licensed in Saskatchewan, Canada.
 - .2 Provide:
 - .1 Fan performance curves showing point of operation, kW and efficiency.
 - .2 Sound rating data at point of operation.
 - .3 Indicate:
 - .1 Motors, sheaves, bearings, shaft details.
 - .2 Minimum performance achievable with variable speed controllers.
- .4 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Submit in accordance with Section 01 78 00- Closeout Submittals.
 - .1 Provide:
 - .1 Matched sets of belts.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment, include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .3 List of specialized tools necessary for adjusting, repairing or replacing.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.

- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect HVAC fans from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Waste Reduction Work plan related to Work of this Section.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
 - .2 Capacity: flow rate, total static pressure, W, efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
 - .3 Each fan shall be UL507 listed.

2.2 FANS GENERAL

- .1 Motors:
 - .1 In accordance with Section 23 05 00- Common Requirements for HVAC supplemented as specified herein.
 - .2 For use with variable speed controllers.
 - .3 Sizes as specified.
- .2 Factory primed before assembly in colour standard to manufacturer.
- .3 Scroll casing drains: as indicated.
- .4 Bearing lubrication systems plus extension lubrication tubes where bearings are not easily accessible.
- .5 Flexible connections: to Section 23 33 00- Air Duct Accessories.

2.3 FANS

- .1 Fan wheels:
 - .1 Steel or aluminum construction.
- .2 Bearings: Lubricated ball or roller self-aligning type with oil retaining, dust excluding seals.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for HVAC fans installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Consultant.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 FAN INSTALLATION

- .1 Install fans as indicated, complete with resilient mountings specified in Section flexible electrical leads and flexible connections in accordance with Section 23 33 00- Air Duct Accessories.
- .2 Provide sheaves and belts required for final air balance.
- .3 Bearings and extension tubes to be easily accessible.
- .4 Access doors and access panels to be easily accessible.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC

1.2 REFERENCE STANDARDS

- .1 Not Used

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for diffusers, registers and grilles and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Capacity.
 - .2 Throw and terminal velocity.
 - .3 Noise criteria.
 - .4 Pressure drop.
 - .5 Neck velocity.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00- Closeout Submittals.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect diffuser, registers and grilles from nicks, scratches, and blemishes.

- .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

2.2 GENERAL

- .1 To meet capacity as indicated.
- .2 Frames:
 - .1 Full perimeter gaskets.
 - .2 Plaster frames and as specified where set into plaster or gypsum board.
 - .3 Concealed fasteners.
- .3 Concealed manual volume control damper operators.
- .4 Colour: As specified.

2.3 MANUFACTURED UNITS

- .1 Grilles, registers and diffusers of same generic type, products of one manufacturer as specified on drawings.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for diffuser, register and grille installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Consultants.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's instructions.
- .2 Install with screws in countersunk holes where fastenings are visible.
- .3 Bolt grilles, registers and diffusers, in place, in gymnasium and similar game rooms.
- .4 Install all new branches to main. Coordinate with Consultant for alternative positioning.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11- Cleaning.
- .3 Waste Management: separate waste materials for reuse or recycling in accordance with sections 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCE STANDARDS

- .1 National Fire Protection Association (NFPA)
 - .1 NFPA 96-11, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .2 National Research Council Canada (NRC)
 - .1 National Building Code of Canada 2015(NBC).
- .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00- Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for vents and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Pressure drop.
 - .2 Face area.
 - .3 Free area.
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Test Reports: submit certified data from independent laboratory substantiating acoustic and aerodynamic performance to ASTM E90.
- .5 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location indoors.

- .2 Store and protect louvers, intakes and vents from nicks, scratches, and blemishes.
- .3 Replace defective or damaged materials with new.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

2.2 VENTS

- .1 Factory manufactured galvanized or stainless steel.
 - .1 Complete as specified with bird screen of 2.7 mm diameter steel wire.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for louvers, intakes and vents installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Consultant.
 - .2 Inform Consultant of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 In accordance with manufacturer's and SMACNA recommendations.
- .2 Anchor securely into opening. Seal with caulking to ensure weather tightness.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11- Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: in accordance with Section 01 74 11- Cleaning.
- .3 Waste Management: separate waste materials for recycling or reuse in accordance with Section 01 74 21- Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION