



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS A:
Bid Receiving/Réception des
sousmissions**

**RCMP / GRC
Procurement & Contracting services
c/o Commissionaires, F Division
6101 Dewdney Avenue
Regina, SK S4P 3K7**

**Facsimile Number for Amendments:
(306) 780-5232**

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les memes.

Comments - Commentaries

**Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Facsimile No. - No de télécopieur:

Telephone No. - no de téléphone:

Title-Sujet Fire Wall and Roof Upgrades	
Solicitation No. - No. de l'invitation M5000-18-6323/A	Date 24 April 2018
Amendment No. - No modif. 03	
Client Reference No. - No. De Référence du Client M5000-18-6323/A	
GETS Reference No. - No. de Référence de SEAG PW-18-00823595	
Solicitation Closes -L'invitation prend fin at - à 2 :00 pm Central Standard Time on - le 30 April 2018	
F.O.B. - F.A.B. Destination	
Address Enquiries to: - Adresser toutes questions à: Teresa Hengen, Contracting Officer	
Telephone No. - No de téléphone (639) 625-3449	Fax No. - N° de FAX: (306) 780-5232
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: Royal Canadian Mounted Detachment 12230 Main Ave Chateh, AB T0H 0S0	
This document does not contain a PERSONNEL SECURITY Clearance requirements	
Delivery Required - Livraison exigée: See Herein Voir aux présentes	Delivery Offered - Livraison proposée
Name and title of person authorized to sign on behalf of Vendor/Firm Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur	



This amendment is to answer the following:

Q6. Please advise the procedure to repair & reinforce the exhaust fans in the cell areas.

R6. In the attic space there is a requirement to properly secure the exhaust fans to the surrounding roofing structure. This is to be accomplished by adding wood structure 2x6 framing and securing the exhaust fans to this structure with fasteners.

Q7. Are you asking us to remove the drywall on the Detachment side in the attic space on separation wall . And are we to spray foam after removing the drywall on the detachment side of block wall & do we put the drywall back after spray foaming.

R&. Do not remove existing drywall on the detachment side or the cell block side. Apply spray foam to the bare/exposed concrete block on the detachment and cell block side only.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME