



1	ISSUED FOR TENDER	MAR 09 2018
B	ISSUED FOR 99% REVIEW	JUN 23 2017
A	ISSUED FOR 66% REVIEW	MAY 25 2017
revisions		date
project		projet

**FUNDY NATIONAL PARK  
HEADQUARTERS &  
WOLFE LAKE CAMPGROUNDS**

**PHASE II**

drawing dessin

**STRUCTURAL  
HQ SERVICE BUILDING  
TYPICAL DETAILS  
AND SECTIONS**

designed	P. MILLER	conçu
date	MAY 2017	
drawn	R. CLAHANE	dessiné
date	MAY 2017	
approved		approuvé
date		
Tender	Submission	
PWSS Project Manager	Administrateur de projets TPSG	
project number		no. du projet
	R.086534.001	
drawing no.		no. du dessin
	S03	

LINTEL SCHEDULE		
WALL TYPE	OPENING LENGTH	REINFORCEMENT
190 BLOCK (NON-LOAD BEARING)	UP TO 900	1 COURSE 1 - 15M BOT.
190 BLOCK (LOAD BEARING)	UP TO 900	2 COURSES 1 - 15M BOT.
190 BLOCK (LOAD BEARING)	900 TO 1800	3 COURSES 1 - 15M BOT.

BLOCK WALL REINFORCING SCHEDULE		
WALL TYPE	VERTICAL REINFORCING	HORIZONTAL REINFORCING
190 BLOCK (NON-LOAD BEARING)	15M AT 1200	EXTRA HEAVY DUTY TRUSS TYPE AT 400
190 BLOCK (LOAD BEARING)	15M AT 1200	EXTRA HEAVY DUTY TRUSS TYPE AT 400

NOTE:  
SHORE LINTELS UNTIL GROUT HAS REACHED 14 DAY STRENGTH

