

**The following changes in the bid documents are effective immediately.
This addendum will form part of the contract documents**

DRAWINGS

- .1 E-002 - Electrical Legend | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Add symbol Low Voltage Switch.
- .2 E-003 – Electrical Partial Single Line | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Replace panel RP-RBA by a new one.
- .3 E-011 – Electrical Panel Rooms | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Replace panel RP-RBA by a new one.
- .4 E-110 – Electrical – Lighting Sussex Pavilion New Layout | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Addition of emergency lighting in washrooms. Move the switches in the Security Post. Some lighting devices will stay on 24 hours.
- .5 E-120 – Electrical – Lighting King Edward Pavilion New Layout | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Addition of emergency lighting in washrooms. Move the switches in the Security Post. Some lighting devices will stay on 24 hours.
- .6 E-140 – Electrical Lighting - Details | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Adjustment of Detail 4.
- .7 E-210 – Electrical – Services Sussex Pavilion New Layout | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Outlets must be installed with a weather proof cover.
- .8 E-251 – Electrical Panels | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Replace panel RP-RBA by a new one.
- .9 E-310 – Electrical – Fire Alarm Sussex Pavilion New Layout | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Horn added in room S110.
- .10 E-320 – Electrical – Fire Alarm King Edward New Layout | Revision 1 | May 8, 2018 | Issued with addendum
 - .1 Horn moved.

ADDENDUM No.

004

Project :

R.070731.002

**The following changes in the bid documents are effective immediately.
This addendum will form part of the contract documents**

SPECIFICATIONS

- .1 Section 26 05 00 – Common Work Results for Electrical
 - .1 Modify article 3.8.4.1 as follows:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of fire alarm, vehicle barrier and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Section 26 05 34 – Conduits, Conduit Fastenings and Conduit Fittings
 - .1 Delete article 3.2.3 entirely.
- .3 Section 26 50 00 - Lighting
 - .1 Add article 2.4.10.11 as follows:
 - .11 Light temperature: 3500K.
 - .2 Modify article 2.4.14.6 as follows:
 - .6 Light temperature: 4000K.
 - .3 Modify article 2.4.16.3 as follows:
 - .3 Fixed to handrails using construction adhesive and support clips.
 - .4 Delete article 2.4.18 entirely.

END OF ADDENDUM No. 004