



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Travaux publics et Services gouvernementaux
Canada
Place Bonaventure, portail Sud-Oue
800, rue de La Gauchetière Ouest
7e étage, suite 7300
Montréal
Québec
H5A 1L6

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Travaux publics et Services gouvernementaux Canada
Place Bonaventure, portail Sud-Oue
800, rue de La Gauchetière Ouest
7e étage, suite 7300
Montréal
Québec
H5A 1L6

Title - Sujet Rehabilitation Chambly Wharf	
Solicitation No. - N° de l'invitation EE520-182837/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client R.077244.001	Date 2018-05-17
GETS Reference No. - N° de référence de SEAG PW-\$MTC-250-14833	
File No. - N° de dossier MTC-7-40378 (250)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-06-21	
Time Zone Fuseau horaire Heure Avancée de l'Est HAE	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Cyr, Nicolas	Buyer Id - Id de l'acheteur mtc250
Telephone No. - N° de téléphone (514) 601-6503 ()	FAX No. - N° de FAX (514) 496-3822
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

THIS INVITATION TO TENDER IS, HERBY, MODIFIED AS FOLLOW

Answers to questions:

Q: For the payment measure of 3,000 m² of sheet piles, you say that it will be measured after cutting-off, therefore excluding the 300 mm minimum cut-off strip. On the other hand, in the next sentence, you say that you will pay us only 300 mm of cut-off. The question is as follows: Should we consider an additional quantity of square meters to 3,000 m² to cover the cut-off strip or if the allowance for the cut-off strip is included in the 3,000 m²?

A: The quantities must include the cut-off strip. We will correct it in addendum.

Q: Can the lamppost bases be precast concrete?

A: Attention, there are specific details of lamppost bases because they must be removable with winter covers, etc. Therefore, if the bases are prefabricated concrete, they will have to include all the details indicated on the plans.

Q: On the plan "ee520-182837_plans_drawings_634206_structure" on page C22 / 28, "anchor details for floating docks", as well as the specifications, we are told "anchor hold provided by Parks Canada Agency". In the following quote from section 01 11 01 point 1.2.3.6.1: "Reinstall floating docks and floating dock guides including anchor holds provided by PCA". We would like to have a clarification. Are only the holds supplied and installed by PCA or are the guides also provided?

A: Only the holds are provided by PCA. Everything else is provided by the Contractor and coordinated with PCA.

Q: In plan "ee520-182837_plans_drawings_634206_structure" on page C22 / 28, "floating docks guide detail", there is no detail on the thickness of the desired plates and their anchors.

A: Yes, this detail had been forgotten. It will be issued in addendum.

Q: On plan "ee520-182837_plans_drawings_634206_structure" on page C03 / 28, it is asked to set up a temporary access corridor for boaters with a width of at least 2.5 meters for phase 1 of the work. Would it be possible to install in phase 1, the temporary floating dock access bridge that is proposed in phase 3 instead of the temporary access corridor?

A: Response to come in addendum.

Q: In plan "ee520-182837_plans_drawings_634206_structure" on page C07 / 28 we are told 15 existing bollards, as also mentioned on page C12 / 28 of the same plan. We would like to validate if there is a concrete base for each existing bollard, because on page C12 / 28, we are told 10 concrete bases to demolish.

A: Yes, there is a large concrete base for each existing bollard. We will correct the note in addendum.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED