



**RETURN BIDS TO:
 RETOURNER LES SOUMISSIONS A:
 Bid Receiving/Réception des
 sousmissions**

**RCMP / GRC
 Procurement & Contracting services
 c/o Commissionaires, F Division
 6101 Dewdney Avenue
 Regina, SK S4P 3K7**

**Facsimile Number for Amendments:
 (306) 780-5232**

**SOLICITATION AMENDMENT
 MODIFICATION DE L'INVITATION**

**The referenced document is hereby
 revised; unless otherwise indicated, all
 other terms and conditions remain the
 same.**

**Ce document est par la présente révisé;
 sauf indication contraire, les modalités
 de l'invitation demeurent les memes.**

Comments - Commentaries

**Vendor/Firm Name and Address
 Raison sociale et adresse du
 fournisseur/de l'entrepreneur**

Facsimile No. - No de télécopieur:

Telephone No. - no de téléphone:

Title-Sujet Interior and Exterior Renovations, Provost, AB	
Solicitation No. - No. de l'invitation M5000-18-7113/A	Date 24 May 2018
Amendment No. - No modif. 03	
Client Reference No. - No. De Référence du Client M5000-18-7113/A	
GETS Reference No. - No. de Référence de SEAG PW-18-00826843	
Solicitation Closes -L'invitation prend fin at - à 2 :00 pm Central Standard Time on - le 01 June 2018	
F.O.B. - F.A.B. Destination	
Address Enquiries to: - Adresser toutes questions à: Teresa Hengen, Contracting Officer	
Telephone No. - No de téléphone (639) 625-3449	Fax No. - N° de FAX: (306) 780-5232
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: Royal Canadian Mounted Detachment Provost, AB	
This document does not contain a PERSONNEL SECURITY Clearance requirements	
Delivery Required - Livraison exigée: See Herein Voir aux présentes	Delivery Offered - Livraison proposée
Name and title of person authorized to sign on behalf of Vendor/Firm Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur	



This amendment is to answer the following:

Delete:

Solicitation Closes –L'invitation prend fin

at - à 2 :00 pm Central Standard Time

on - le 30 May 2018

Insert:

Solicitation Closes –L'invitation prend fin

at - à 2 :00 pm Central Standard Time

on - le 01 June 2018

Q1. Do you know the source of the water?

R1. The RCMP is of the belief that ground water from the exterior of the residence is finding its way into the basement of the unit due to the negative grading of the property through the poor window seals, possible cracks in the wooden foundation, and possibly through the larger cracks in the concrete flooring.

Add to the existing Scope of Work:

h) **ADD:** Remove existing bathroom shower pan and all associated materials, glass insert panels and door, vanity cabinet, counter, sink and faucet, and toilet. Remove all existing Barker Tile Board and ceramic tile from the basement bathroom walls. Remove existing light fixture, ceiling exhaust fan and wall mirror. Provide and install new bathroom vanity cabinet and countertop to replace existing. New cabinet shall be an equivalent height and length as existing, but shall be only 36" in width. Cabinets shall exceed or be equivalent to Thomasville Standard cabinet construction, and shall include new metal hinges and pulls, and soft close hardware on all drawers. Cabinet doors shall exceed or be equivalent to Thomasville Thermofoil Nelson style door profile. New cabinetry to include the supply and install of new chrome finish metal drawer and door hardware. Supply and install new Arborite (or equivalent) countertop to replace existing bathroom countertop; Quality to be equal to or greater than existing. Supply and install new bathroom sink and faucet to replace existing; new lavatory shall be white in colour and shall be of similar or greater quality than existing; acceptable product is the American Standard Marquete Bathroom Sink Basin, or equivalent. New metal faucet shall be chrome finish and modern in design; acceptable product is the Moen Genta Signel Hole 1-Handle Low Arc Bathroom Faucet in Chrome, or equivalent. Supply and install new white ceramic toilet to replace existing; acceptable product is the American Standard Cadet 4.8L Round Front Complete Toilet, or equivalent. Supply and install new white ceramic shower base, approximately 40" square to replace existing. Acceptable product is the Mirolin Strada Base, or equivalent. Supply and install new glass wall and door insert panels as part of the new shower system, to replace existing. New glass shower door should provide access to the shower from the West side (opposite the valve and controls), with the door swinging out, flat against the South wall of the bathroom. New glass door hardware to be chrome-finish and modern in design. Supply and install new chrome finish shower control valve, shower head and any other associated/required controls to replace existing; acceptable product is the Moen Genta Single-Handle Posi-Temp Shower Faucet, or equivalent. Supply and install new white subway-style ceramic tile to the entirety of the interior walls of the new shower unit, minimum 40" x 40" x 78", and above the newly installed vanity cabinet as a backsplash, minimum 36" x 4", flush with the top of the countertop, walls and new mirror. Supply and install new white grout to all newly tiled surfaces. Supply and professionally install new white or clear water-proof caulking around newly installed shower enclosure, around the top of the newly installed tile within the shower, glass inserts and door, toilet, vanity cabinet, countertop and backsplash tiles, as required. Supply and install new High CFM (minimum 100) fan and cover, exhausted to the exterior of the residence, to replace existing fan and cover within the bathroom of the residence. Ensure exhaust is installed properly, and not blocked or kinked to restrict air movement. Supply and install new modern chrome-finish wall-mounted light fixture to replace existing light fixture. Supply and install new wall mirror, approximately 36" wide x 42" tall to replace existing wall mirror. Supply and install new chrome-finish modern bathroom towel bars (minimum 2 full-



size bars), hand towel ring and toilet paper holder to replace existing. Reinstatement of new finishes may require additional building materials such as wood framing, water-proof membranes, ceramic tiles, insulation, polyethylene sheeting, drywall, drywall joint compound and paint; all new materials required are to be included for as part of this Contract. Colour, design and styles of all new materials, including tile installation plan, to be pre-approved by Asset Manager prior to ordering or installing.

o) **ADD:** Excavation to the footing around the entirety of the residence may not necessarily include the front of the residence where the driveway is located, however it must include all three other sides of the residence. This will include the removal of the concrete walkway on two sides, the removal (and proper storage of for later reinstatement) the Air Conditioner, as well as the removal of the wooden deck at the rear of the residence. Reinstatement of these materials is further detailed in v), however final positioning and design of the concrete walkway, air conditioner and deck to be approved by the Asset Manager before installation.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME