



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Wells PWC-2 and TWC-1 Upgrades	
Solicitation No. - N° de l'invitation F1700-176142/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client F1700-176142	Date 2018-05-29
GETS Reference No. - N° de référence de SEAG PW-\$PWY-025-8345	
File No. - N° de dossier PWY-7-40395 (025)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-06-01	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Fung, Donna(PWY)	Buyer Id - Id de l'acheteur pwy025
Telephone No. - N° de téléphone (604) 671-9689 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Chehalis River Hatchery - Agassiz, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Amendment 004 is raised to:

- 1) extend the closing date of the solicitation, and
- 2) incorporate Addendum 3.

Extension of Time

Wells PWC-2 and TWC-1 Upgrades
Chehalis River Hatchery, Agassiz, BC

Solicitation No: F1700-176142/A

Notice is hereby given that the time for reception of tenders previously due at
2:00 p.m. on 30 May 2018 is hereby extended to
2:00 p.m. on 1 June 2018.

Please see the attached Addendum 3.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

Chehalis River Hatchery – Tender Questions – Addendum 3

2018-05-29

1. Please find attached our Pump Submittals for both PWC-2 and TWC-1 as well as the general arrangement drawing for our proposed 40HP Motor for PWC-2.
 - The 14RJMC-1 for PWC-2 is an approved alternate as per the spec sheet provided.
 - The 12CLC-2 for TWC-1 is not an approved alternate as per the spec sheet provided. The supplier has indicated that they are using a 25HP motor although the spec sheet indicates it is 27HP at design and rated for 30HP.
2. Going off the TWC-1 well pump replacement and As-built drawing, the parts for replacement are:
 - Reducer (250 x 300 with Victaulic coupler)
 - Air Valve
 - Swing Check Valve
 - 300mm dia. Butterfly Valve
 - Pressure Gauge with stop cock
 - 300mm dia. Mag Meter (Sparkling PDS 103 meter or an equivalent)
 - Ball Valve
 - 300mm 90 Degree Elbow

The as-built drawing provides the only details on the current equipment setup, and all fittings to be ductile iron.

TWC-A Upgrade specification under the Summary of Work, note 3 says to connect the pump to the existing water supply, replacing the existing equipment with new valves, air release valves, water meter, etc. but no detail on what is expected to be replaced.

- The parts indicated on drawing 11-29-344 that are to be installed are:
 - (250 x 300) Reducer
 - 300mm Spool piece with Air Release Valve
 - 300mm Swing Check Valve
 - 300mm Butterfly Valve
 - 300mm Spool piece with Pressure Gauge
 - 300mm (12") Proline Promag W 400 Electromagnetic Flowmeter or approved equal.
 - 300mm Ball Valve
 - 300mm Spool Piece to connect to the 90' Elbow
- Fittings to be Ductile Iron and as per section 33 11 01 - 2.1.1.2. All fittings to AWWA C110 (Latest Edition).
- The Magnetic Flow Meter is to be a "Proline Promag W 400 - 12" Electromagnetic Flowmeter" or approved equal.

End of Addendum 3