

## QUESTIONS & ANSWERS

### Question 13

Because the new unit is 90% eff we have to add a discharge plenum so the unit will overhang the back of the curb around 15-20" (contractor will need to offset RA ductwork). Confirm unit can overhang off the curb on this end.

Can you confirm the above comment about overhang will be acceptable?

### Answer 13

Refer to Amendment No. 004, Addendum #1. The dimensions of the unit and plenums may change due to lowering the heater efficiency from 91% to 80%. The comment cannot be confirmed due to Addendum #1.

### Question 14

On the drawing it specifies duct work to be acoustic lined.

Are we not insulating the exterior of the duct work for thermal energy saving?

### Answer 14

No. The exterior ducting is not required to have external insulation.