



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
PWGSC/TPSGC Acquisitions Bid
Receiving/Réception des Soumissions
The Cambridge Building
3 Queen Street/ 3, rue Queen
Charlottetown
Prince Edward Island
C1A 4A2
Bid Fax: (902) 566-7514

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Veuillez adresser toute demande de renseignements par écrit à l'attention de l'autorité contractante, Crystal Bysterveldt, soit par télécopieur ou par courriel à: crystal.bysterveldt@tpsgc.gc.ca.

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Commercial Acquisitions (PEI)
The Cambridge Building
3 Queen Street/3 rue, Queen
Charlottetown, PEI C1A 4A2

Title - Sujet Clôtures de sécurité	
Solicitation No. - N° de l'invitation 21C11-186378/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client 21C11-186378	Date 2018-07-03
GETS Reference No. - N° de référence de SEAG PW-\$PEI-001-4323	
File No. - N° de dossier PEI-8-41009 (001)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-07-05	
Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Bysterveldt (PEI), Crystal	Buyer Id - Id de l'acheteur pei001
Telephone No. - N° de téléphone (902) 940-7122 ()	FAX No. - N° de FAX (902) 566-7514
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

LE PRÉSENT ADDENDA VISE À PRÉSENTER LES RÉPONSES SUIVANTES AUX QUESTIONS POSÉES PAR LES SOUMISSIONNAIRES.

LES CHANGEMENTS SUIVANTS AUX DOCUMENTS D'APPEL D'OFFRES ENTRENT EN VIGUEUR IMMÉDIATEMENT. CET ADDENDA FERA PARTIE DES DOCUMENTS CONTRACTUELS.

1. **Question:** Section 32 31 13 – Part 3.2.12 – Will there be an expectation for “anti-tunnel sand/cement mix” to be installed between posts as noted here on the Construction Fence or the Security Fence (or both)? If the construction fence is to include this, can it be assumed that it will not be a requirement in the areas that have existing asphalt?

Answer: No requirement for “anti-tunnel/cement mix” on either fence.

2. **Question:** Which contractor will be responsible for filling the post holes from the Construction Fence after the fence is removed? Fence or demolition?

Answer: The Fencing contractor is responsible.

3. **Question:** Can you confirm that the removal of electronics from the fence will be part of the Electrical contract scope of work?

Answer: Yes, it is Electrical/Security Responsibility.

4. **Question:** Section 32 31 13 Chain link Fence and Gates; Section 2.1.3 & 2.1.4 is not really clear as it is listing pipe sizes that are either not available, or are not listed appropriately for the intended use. Can you confirm if the pipe sizes and intended use listed below, are appropriate for the project?

Gate Posts	168mm (6 5/8" OD) schedule 40 galvanized steel
Corners and ends	114mm (4 1/2" OD) schedule 40 galvanized steel
Line Posts	73mm (2 7/8" OD) schedule 40 galvanized steel
Top, brace and bottom rails	43mm 1 11/16" OD schedule 40 galvanized steel

Answer:

Gate posts – 143mm OD Schedule 40 galvanized steel minimum
 Corners and ends – 143mm OD Schedule 40 galvanized steel minimum
 Line posts - 73mm OD Schedule 40 galvanized steel minimum
 Top and bottom rails – 42.2mm OD Schedule 40 galvanized steel minimum

5. **Question:** Spec Section 32-31-13; The requirement for concertina barb tape on the plans and the spec section shows different dimensions. Does the specification take precedence?

The specifications call for a sand cement mix between the posts. Is this an actual requirement for a construction fence?

Answer:**Replace the following article: 3.3.4**

Install 450 mm steel concertina wire along top of fence c/w 2 strands of barbed wire, and fasten to purpose made bracket fastened to each upright.

With this one:

Install 635/710 mm steel concertina wire along top of fence c/w 2 strands of barbed wire, and fasten to purpose made bracket fastened to each upright. Refer to details on drawing L-104.

No requirement for "anti-tunnel/cement mix" on either fence.

SPECIFICATION CLARIFICATION

Section 32 31 13

ITEM 1**Replace the following article: 3.2.3**

Space line post 3.1m apart maximum, measured parallel to the ground surface.

With this one:

Space line post 2.5m apart maximum, measured parallel to the ground surface.

ITEM 2**Remove the following article from the specification: 2.1.1**

Fencing: as indicated manufactured by New Brunswick Wire Fence Co., Expert Fence Co. Ltd, or an approved alternate.

DRAWING CLARIFICATION**ITEM 1**

Drawing L-104, detail 2-L104 indicates 410mm diameter concertina and it should read 635mm diameter.

ITEM 2

Drawing L-104, detail 3-L104, remove the following note from the drawing.

"Steel post at maximum 3050mm C/C"