

**Part 1 General**

**1.1 REFERENCES**

- .1 U.S. Environmental Protection Agency (EPA) / Office of Water
  - .1 EPA 832R92005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

**1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

**1.3 INSTALLATION AND REMOVAL**

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

**1.4 DEWATERING**

- .1 Provide temporary drainage and pumping facilities to keep excavations and site free from standing water.

**1.5 WATER SUPPLY**

- .1 Potable water is not available on site.
- .2 Contractor is responsible to arrange and pay for supply of potable water for workers and construction use.

**1.6 TEMPORARY POWER AND LIGHT**

- .1 Temporary power during construction for temporary lighting and operating of power tools is not available on site.
- .2 Contractor is responsible to arrange and pay for temporary power and light for construction use.

**1.7 TEMPORARY COMMUNICATION FACILITIES**

- .1 Provide and pay for temporary telephone, fax, data hook up, lines, equipment necessary for own use.

**1.8 FIRE PROTECTION**

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL**

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction sediment and erosion control plan, specific to site, that complies with EPA 832/R-92-005 or requirements of authorities having jurisdiction, whichever is more stringent.
- .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

**END OF SECTION**