

Part 1 General

1.1 SUMMARY

- .1 This section specifies the Contractor requirements for the provision of temporary facilities for the proper implementation of the Contract.

1.2 INSTALLATION AND REMOVAL

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Identify areas which have to be gravelled to prevent tracking of mud.
- .3 Indicate use of supplemental or other staging area.
- .4 Provide construction facilities in order to execute Work expeditiously.
- .5 Remove from site all such work after use.

1.3 ACCESS

- .1 Provide and maintain adequate access to project site.
- .2 Build and maintain temporary access roads where indicated or approved and provide snow removal during period of Work.
- .3 If authorized to use existing roads for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractors' use of roads.

1.4 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of work with weight or force that will endanger Work.

1.5 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work.
- .2 Provide and maintain adequate access to project site as well as existing roadways.
- .3 Maintain existing roads for duration of construction and make good damage resulting from Contractor use of roads.

1.6 SITE OFFICES

- .1 Contractor to provide temporary office onsite of sufficient size to accommodate site meetings and furnished with drawing laydown table.
- .2 Provide temporary office for sole use of the Departmental Representative and their representatives.
- .3 Provide a clearly marked and fully stocked first-aid case in a readily available location.

1.7 SECURITY

- .1 Provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays.

1.8 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

1.9 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.10 POWER AND WATER SUPPLY SYSTEMS

- .1 If required, arrange, provide and pay for and maintain connection with the appropriate utility company for temporary power and water supply required during the remediation work, in accordance with governing regulations and ordinances.
- .2 On-site water supply is not available. If required, Contractor shall arrange, provide and pay for water and storage tanks to be used during construction.

1.11 DRAINAGE

- .1 Refer to Section 01 35 43 Environmental Procedures for site drainage.

1.12 PROTECTION AND MAINTENANCE OF TRAFFIC

- .1 Provide access and temporary relocated roads as necessary to maintain traffic.
- .2 Maintain and protect traffic on affected roads during construction period except as otherwise specifically approved by Departmental Representative.

- .3 Provide measures for protection and diversion of traffic, including provision of watch-persons and flag-persons, erection of barricades, placing of lights around and in front of equipment and work, and erection and maintenance of adequate warning, danger, and direction signs
- .4 Protect travelling public from damage to person and property.
- .5 Contractor's traffic on roads selected for hauling material to and from site to interfere as little as possible with public traffic.
- .6 Verify adequacy of existing roads and allowable load limit on these roads. Contractor responsible for repair of damage to roads caused by construction operations.
- .7 Construct access and haul roads necessary.
- .8 Haul roads constructed with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic shall be avoided.
- .9 Provide necessary lighting, signs, barricades, and distinctive markings for safe movement of traffic.
- .10 Dust control adequate to ensure safe operation at all times.
- .11 Location, grade, width, and alignment of construction and hauling roads subject to approval by Departmental Representative.
- .12 Lighting to assure full and clear visibility for full width of haul road and work areas during night work operations.
- .13 Provide snow removal during period of Work.
- .14 Remove, upon completion of Work, haul roads designated by Departmental Representative.

1.13 REMOVAL OF TEMPORARY FACILITIES

- .1 Remove temporary facilities and power from site when approved by Departmental Representative. The ground surface is to be restored to a similar condition of the adjacent areas of the project. Provide appropriate sediment and erosion control to promote re-vegetation on the areas.
- .2 When project is closed down, keep facilities operational until close down is approved by Departmental Representative.
- .3 All garbage and debris generated by work activities shall be collected and disposed off-site, in disposal areas approved by the Departmental Representative.

1.14 SAFETY

- .1 Conform to the safety requirements of the Canadian Construction Safety Code and the Occupational Health and Safety Regulations of the Newfoundland and Labrador Department of Government Services.
- .2 Refer to Section 01 35 29.14 – Health and Safety for Contaminated Sites for complete health and safety requirements.

1.15 CLEAN-UP

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

1.16 METHOD OF PAYMENT

- .1 No separate or direct payment will be made for work specified in this section. The cost of all work specified in this section is deemed to be included in the lump sum and unit prices quoted in the Schedule of Quantities and Prices.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION