



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving - PWGSC / Réception des soumissions -  
TPSGC

11 Laurier St. / 11, rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau, Québec K1A 0S5

Bid Fax: (819) 997-9776

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

THIS DOCUMENT CONTAINS A SECURITY  
REQUIREMENT / DOCUMENT CONTIENT DES  
EXIGENCES RELATIVES À LA SÉCURITÉ

### Vendor/Firm Name and Address

Raison sociale et adresse du  
fournisseur/de l'entrepreneur

### Issuing Office - Bureau de distribution

Electrical & Electronics Products Division  
11 Laurier St./11, rue Laurier  
7B3, Place du Portage, Phase III  
Gatineau, Québec K1A 0S5

<b>Title - Sujet</b> Audio-Visual Technology	
<b>Solicitation No. - N° de l'invitation</b> W8474-197662/A	<b>Amendment No. - N° modif.</b> 003
<b>Client Reference No. - N° de référence du client</b> 6000436037	<b>Date</b> 2018-07-11
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$\$HN-331-74963	
<b>File No. - N° de dossier</b> hn331.W8474-197662	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2018-07-24</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Eastern Daylight Saving Time EDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Turner, Louie	<b>Buyer Id - Id de l'acheteur</b> hn331
<b>Telephone No. - N° de téléphone</b> (873) 469-3342 ( )	<b>FAX No. - N° de FAX</b> ( ) -
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Amendment # 3 is issued to answer potential bidder's questions

**Question # 1:**

**Page 41 Section 3 EQT\_1 (3)**

Please confirm the make and model of the HD Cable Tuner. Also are these to be considered GFE provided by Canada.

**Answer # 1:**

Analog Cable TV and Digital box will be provided by CANADA. Room will use both solution, the plan is to decommission Analog TV later on...

Analog Cable TV goes into those device equipped with tuners;

- TOSHIBA DVD-R/TUNER - D-R7—K-TC3 (qty 1)
- PANASONIC – DVD-R/TUNER - DMR-EZ48V (qty 1)

Digital Cable Box to be implemented;  
BELL HD 6131 receivers (qty 4)

**Question # 2:**

**ANNEX B STATEMENT OF WORK**

**Scope and instructions**

**16. The Contractor must remove, sort and discard all packing material (e.g., boxes, pallets, foam) pursuant to local rules.**

Q: Please confirm if this is removing from rack room and floor area and leave at recycling facility on site or remove from the site all together

**Answer # 2:**

To be taken to Recycling Facility near loading dock

**Question # 3:**

**Appendix A to Annex B-Statement of Work**

**Section 3 EQT\_1 A) Specifications ii)8 Power Controller**

Q: No power controller on the equipment list. Please confirm requirement and quantity.

**Answer # 3:**

If power controller(s) are necessary in the bidder's proposed solution please list criteria's and details of recommended item(s) in a table such as example below;

(I.E.) <ul style="list-style-type: none"><li>• Relay control</li><li>• Power Input...</li><li>• Power Outputs...</li><li>• Other...</li></ul>	2	(I.E.) <ul style="list-style-type: none"><li>• Brand</li><li>• Model</li></ul>
---	---	--

**Question # 4:**

**Section 3 EQT 1 A) Specifications ii) 9 UPS rack unit**

**Appendix E to Annex A-Equipment list indicate 2 Middle Atlantic UPS-S1500R while Appendix B to Annex B Drawing package rack layout indicate a Middle Atlantic UPS-2200-R**

Q: Please confirm model and quantity

**Answer # 4:**

Drawing(s) is conceptual, please refer to criteria in equipment list

**Question # 5:**

**Section 4 FLOOR AREA a) Requirements ii) Ability to select local PC sources through computer KVM at the identified Operation desks**

Q: Please clarify if both physical KVM switches, provided by CANADA, will be used in addition to remote KVM of EQT\_1 PC via Keyboard Hot Keys & Think Logical OSD interface.

**Answer # 5:**

Yes Desk with KVM (**Desk # 3 and #7**) will have a computer KVM with multiple sources connected into it, the Think logical receiver being one of those, the user can select this input to display the Thinklogical receiver feed onto the monitor.

**Question # 6:**

**Section 4 FLOOR AREA b) Specifications ii) (1) Floor Area Operation Desks**

**(a) Think Logical Fibre Receiver (Qty 27);**

**(i) Video onto CANADA PC monitors - 4 display setup (Qty 13)**

**ii) Video onto CANADA PC monitors – 6 Display setup (Qty 1)**

Q: Appendix B to Annex B Drawing package floor plan layout indicate 12 x 4 display station + 1 x 6 display station

Please confirm the number of –each type of work station.

**Answer # 6:**

Desk 10B has two setup of 4 displays, so with the other desks with 4 displays the total is 13 – (Qty 13)

Desk 6 has 6 Displays – (Qty 1)

**(i) Video onto CANADA PC monitors - 4 display setup (Qty 13)**

**ii) Video onto CANADA PC monitors – 6 Display setup (Qty 1)**

**Question # 7:**

**Cabling from Fiber transmitter or receiver and GFE equipment.**

Q: Can you confirm the DVI, USB, AUDIO cabling provided with Thinklogical transmitter(s) and receiver(s) are accepted for secure installation.

**Answer # 7:**

YES they can be used. For Video such as secured PC (i.e. Level II and Level III) we will recommend going with shielded cable for Video (DVI, HDMI)

**Question # 8:**  
**Room control**

- a. Q: Can you confirm how the 6 room large displays will be controlled, the equipment list does not appear to have any provision for RS-232 insertion. Is contractor required to provide serial connection between control processor and display?
- b. Can we assume a separate AV network connection over fiber is required for each TS-1542-TILT touch panel?
- c. Can we assume CANADA provide all cable trays and surface raceways for any speaker or serial cables between EQT\_1 and each room device?

**Answer # 8:**

A: Yes contractor is required to provide serial connection between control processor and displays, should your proposed solution require RS-232 insertion you may list the recommended item/accessory;

(I.E.) <ul style="list-style-type: none"><li>• RS-232...</li><li>• Other...</li></ul>	2	(I.E.) <ul style="list-style-type: none"><li>• Brand</li><li>• Model</li></ul>
---	---	--

B: The room being into short distance shielded copper can be run to each panel location.

C: Yes CANADA will have cable trays and surface raceways provided, we recommend bidder to furnish accessories such as mouldings (i.e. Panduits) to complete the solution and have cable run esthetical, done properly

All other terms and conditions remain the same.