

- 1.3 INSTALLATION AND REMOVAL .3 Remove from site all such work after use.
(Cont'd)
- 1.4 SCAFFOLDING .1 Scaffolding in accordance with CAN/CSA-S269.2.
.2 Provide and maintain scaffolding ladders platforms.
- 1.5 HOISTING .1 Provide, operate and maintain hoists cranes required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for their use of hoists.
.2 Hoists cranes to be operated by qualified operator.
- 1.6 ELEVATORS .1 Designated existing elevators to not to be used by construction personnel and transporting of materials. Co-ordinate use with Departmental Representative.
- 1.7 SITE STORAGE/LOADING .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
.2 Do not load or permit to load any part of Work with weight or force that will endanger Work.
- 1.8 CONSTRUCTION PARKING .1 Parking will be permitted on site provided it does not disrupt performance of Work.
.2 Provide and maintain adequate access to project site.
-

- 1.9 SECURITY .1 Conform to security protocols in place.
- 1.10 EQUIPMENT,
TOOL AND MATERIALS
STORAGE .1 Provide and maintain, in clean and orderly
condition, lockable weatherproof sheds for
storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in
weatherproof sheds on site in manner to cause
least interference with work activities.
- 1.11 SANITARY
FACILITIES .1 Provide sanitary facilities for work force in
accordance with governing regulations and
ordinances.
- .2 Post notices and take precautions as required
by local health authorities. Keep area and
premises in sanitary condition.
- 1.12 CONSTRUCTION
SIGNAGE .1 NO other signs or advertisements, other than
warning signs, are permitted on site.
- 1.13 PROTECTION AND
MAINTENANCE OF
TRAFFIC .1 Provide measures for protection and diversion
of traffic, including provision of
watch-persons and flag-persons, erection of
barricades, placing of lights around and in
front of equipment and work, and erection and
maintenance of adequate warning, danger, and
direction signs.
- .2 Provide snow removal during period of Work.
- 1.14 CLEAN-UP .1 Remove construction debris, waste materials,
packaging material from work site daily.
-

