

PART 1 - GENERAL

- | | | |
|--------------------------------|----|--|
| <u>1.1 DESCRIPTION OF WORK</u> | .1 | In general, Work of this section consists of all removals and relocation work to extent shown and/or specified. Coordinate the removal work with the construction progress to the approval of the Departmental Representative. |
| <u>1.2 REFERENCE STANDARDS</u> | .1 | All removal or modification work of electrical construction to be done in accordance with the safety standards outlined in the Canadian Electrical Code and requirements of the National Building and Labour Codes of Canada. |
| | .2 | Ensure electrical circuits are deenergized and locked out before commencing work. Work on live circuits is expressly prohibited. |
| | .3 | Lockout procedures to Canada Labour Code and regulations. |
| <u>1.3 EXAMINATION</u> | .1 | Carefully examine the site and contract documents to determine the nature and extent of the Work. |
| <u>1.4 EQUIPMENT</u> | .1 | Provide necessary equipment to carry out the work. Perform all cutting and patching. |
| <u>1.5 PROTECTION</u> | .1 | Erect barriers around where demolition is being carried out. |
| <u>1.6 DISPOSAL</u> | .1 | Except as noted elsewhere, removed materials become the property of the contractor for disposal off the construction site. |
-

1.7 SCHEDULING .1 Schedule and coordinate this Work with the Departmental Representative to minimize shut downs to the electrical system. Advise the Departmental Representative 48 hours in advance of any electrical service disruptions. All removal work requiring electrical shutdowns shall be carried out during periods as designated by the Departmental Representative with all premium pay rates being the responsibility of the contractor.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 GENERAL .1 Before doing any removal work ensure that all electrical circuits connected to the equipment designated for removal have been disconnected and locked out in accordance with the Canada Labour Code and CEC.