

Project Title:	Addendum No:
NAB Storm Drainage	1
Project Location:	PWGSC Project No:
Stony Mountain, Manitoba	R.086418.001
Consultant's Name:	Date:
DGH Engineering Ltd.	July 18, 2018
The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.	
Specifications	
<p>1 Section 01 11 00 – Summary of Work</p> <p>.1 Revise Article 1.2 to reflect that guide rails will not be installed for pumps in sump pits. Galvanized (hot-dipped) steel pump chains, fasted to pit walls will be used, as specified in Section 33 32 13.</p>	