

**The following changes in the bid documents are effective immediately.  
This addendum will form part of the contract documents.**

**Page 1 of 1**

**Drawings:**

1. Reference: Drawing A-6 - Partial Interior Elevations – Existing Conditions, Selective Demolitions, New Construction – Building “B” South Wall – Building “A” North Wall (previously issued)
  - a. Refer to Detail 2 on A-6:
    - i. Delete: Backwater valve shown at funnel drain.
2. Drawing A-9 - Freezers Construction Details, dated 2018-05-14 (previously issued)
  - a. Refer to Detail 7 on A-5:
    - i. Add: Apply sealant of type indicated in Specification Section 11 41 00 – Walk-in Freezers, Item 2.4.2, typical at Walk-in Freezer No.1 and No.2 between top of radiant floor heating perimeter angle and freezer box floor panel.
3. Drawing E-1 - Electrical Lighting Plan: Existing Conditions and Demolitions – New Construction (previously issued)
  - a. Refer to Detail 1 on E-1:
    - i. Revise: Switch symbol shown in Walk-in Freezer No.2 box to be new weatherproof light switch (supply and install by refrigeration only).

**Specifications:**

1. Reference: Specifications Table of Contents (previously issued)
  - a. Refer to Table of Contents Division 22:
    - i. Revise: Section Number for Common Work Results for Plumbing to 22 05 00.
2. Reference: Section 11 41 00 – Walk-in Freezers

**Section 23 23 00 – Refrigerant Piping**

- a. Clarification: Add the following.
  - i. Meet all requirements of Federal Halocarbon Regulations 2003 complete with all relevant Amendments, including but not limited to:
    1. Prohibitions
    2. Recovery
    3. Installation Servicing, Leak Testing and Charging
    4. Service Logs
    5. Permits
    6. Records and Reports.

**End of Addendum No.1**