

ADDENDUM NUMBER: THREE

ISSUED BY: SEPW Architecture Inc.
109 – 3725 Pasqua St., Regina, SK. S4S 6W8
PH. (306) 569-2255

**PROJECT: WINDOW REPLACEMENT
REGINA, SASKATCHEWAN**

This Addendum forms part of the Contract Documents and amends the original Drawings and Specifications dated 2018-04-19, previous Addenda if applicable and as noted below. This Addendum consists of 1 page and attached Specification Sections and Drawings as listed below.

Ensure that all parties are aware of all items included in this Addendum.

The following revised or additional Specification Sections accompany and form an integral part of this Addendum:

Section No.	Title	Pages	Date of Issue
	N/A		

The following revised or additional Drawings accompany and form an integral part of this Addendum:

Dwg. No.	Title	Date of Issue
	N/A	

A-3 -1 REF. SECTION 07 42 46 FIBRE REINFORCED CEMENTITIOUS PANELS

3.2.8 CLARIFICATION: the prefinished metal strip at each panel joint must be continuous for height of the panels.

A-3 -2 REF. SECTION 07 42 46 FIBRE REINFORCED CEMENTITIOUS PANELS

NOTE: Tabs over the face of the panels at joints will not be acceptable. Easy Trim Reveals for 8mm panels is not acceptable.

A-3 -3 BIDDER QUERY

Q. Are there any details as to what's behind the existing metal panels that are to be removed before the W-2 Wall can be framed in. Please advise.

A. Wall W-2 is at the location of the removed windows. It has existing framing as noted on our drawing. The W-1 wall is where the existing metal panes are. The record drawings show the existing porcelain enamel panels installed in front of 6" concrete block. There are no details provided in the record drawings as to how the existing panels are fastened to the concrete block.