

5		
4		
3		
2		
1		
0	ISSUED FOR TENDER	2018
Revision	Description	D
Client		

**CORRECTIONAL SERVICES
CANADA**

Project

CHURCHILL UNIT REDEVELOPMENT

Designed by	Con
PM	

Drawn by	Dess
MM, BH	

Approved by	Approved
-------------	----------


PWGSC Project Manager	Administrateur de Projets
-----------------------	---------------------------

Drawing title	Titre du
---------------	----------

LARGE SCALE PLANS AND ELEVATIONS

Project no./No. du projet	Drawing no./No. du dessin	Revision
---------------------------	---------------------------	----------

R.082215.001	A5.0	0
--------------	------	---




NEW BARRIER FREE SHOWER


1 : 25

INTERIOR ELEVATIONS LEGEND:


- | | |
|----|--|
| 1 | TOILET TISSUE DISPENSER - RECESSED MOUNTED, 600mm FROM FLOOR TO C.L. |
| 2 | PAPER TOWEL DISPENSER - SURFACE MOUNTED, 1000mm FROM FLOOR TO UNDERSIDE, UNLESS OTHERWISE NOTED |
| 3 | SOAP DISPENSER - SURFACE MOUNTED, 1000mm FROM FLOOR TO UNDERSIDE. |
| 4 | WASTE RECEPTACLE - SURFACE MOUNTED. 1000mm FROM FLOOR TO C.L. OF OPENING. |
| 5 | SHOWER CONTROL UNIT - SURFACE MOUNTED |
| 6 | VERTICAL GRAB BAR - SHOWER |
| 7 | HORIZONTAL GRAB BAR - SHOWER |
| 8 | STAINLESS STEEL, SEAMLESS LAVATORY, 860mm MAX. FROM FLOOR TO TOP OF LAVATORY |
| 9 | STAINLESS STEEL, SEAMLESS TOILET 460mm MAX. FROM FLOOR TO TOP OF TOILET |
| 10 | STAINLESS STEEL, SEAMLESS LAV/TOILET COMBO 850mm MAX. FROM FLOOR TO TOP OF LAVATORY. |
| 11 | SAFETY TOWEL/ROBE HOOK - 1200mm FROM FLOOR TO C.L. |
| 12 | SAFETY MIRROR - BARRIER FREE - 1000mm FROM FLOOR TO UNDERSIDE. TYPICAL - 1450mm FROM FLOOR TO UNDERSIDE. |
| 13 | SHOWER CURTAIN AND COLLAPSIBLE ROD 1800mm FROM FLOOR TO C.L. OF ROD |
| 14 | FOLD-DOWN SHOWER SEAT 430mm FROM FLOOR TO BOTTOM OF BENCH |
| 15 | BED - PLASTIC - REFER TO SPECIFICATIONS |
| 16 | LOCKER |
| 17 | SHELF - METAL & SECURED/ANCHORED. |
| 18 | RUBBER COVE BASE |
| 19 | PAINTING OVER CONCRETE, GLOSS ENAMEL 100mm (4") |
| 20 | CELL - PAINTED GLOSS ENAMEL COVE BASE |
| 21 | TELEPHONE JACK |
| 22 | WHITEBOARDS |
| 23 | STAINLESS STEEL, SEAMLESS SINK |
| 24 | STORAGE UNIT |
| 25 | EXISTING INTERIOR WINDOW, TO BE RE-PAINTED |
| 26 | POLYCOM HARDENED WALL UNIT (N.I.C.) PROVIDE BACKING AS REQUIRED |
| 27 | BARRIER FREE WASHROOM SIGNAGE |
| 28 | BARRIER FREE PUSH BUTTON POWER ASSISTED DOOR OPENER |
| 29 | STAINLESS STEEL SHELF 400 LONG X 200 WIDE |
| 30 | MILLWORK CABINETS, REFER TO DWG. A5.1 |
| 31 | EXISTING WINDOW TO BE REGLAZED AND REPAINTED |
| 32 | BARRIER FREE GRAB BAR |
| 33 | CALL BATTON - RECESSED IN BLOCK WALL |
| 34 | 30mm LEXAN SPI SHIELD WITH STAINLESS STEEL FRAME SCREWED TO GATE WITH SECURITY SCREWS |
| 35 | CABINET ON ROLLERS |




ELEVATION A
NEW BARRIER FREE SHOWER




ELEVATION B



ELEVATION C



ELEVATION D



ELEVATION A


NEW BARRIER FREE WASHROOM

1 : 25


WASHROOM ACCESSIBLE DESIGN REQ.

ALL ACCESSORIES BY SUPPLIER TO ADHERE TO THE FOLLOWING AS
PER CSA Standards B-651-12;


- 1. SHALL HAVE NO DIMENSION LESS THAN 1700MM
- 2. SHALL HAVE A TURNING DIAMETER NOT LESS THAN 1500,
- 3. DESIGNED TO PERMIT A PERSON USING A WHEELCHAIR TO BACK IN ALONG SIDE THE WATERCLOSET.
- 4. MINIMUM DOOR WIDTH - 900MM
- 5. DOOR CATCHABLE FROM THE INSIDE AND RELEASED FROM THE OUTSIDE
- 6. DOOR TO HAVE: OPERATING MECHANISMS LOCATED NOT LESS THAN 900MM AND NOT MORE THAN 1000MM AFF.
- 7. IF AN OUTWARD SWINGING DOOR: A DOOR PULL NOT LESS THAN 140MM LONG LOCATED ON THE INSIDE SO THAT ITS MIDPOINT IS NOT LESS THAN 900MM FROM MORE THAN 300mm FROM THE INSIDE, AND NOT LESS THAN 900mm AND NOT MORE THAN 1000mm ABOVE FLOOR.
- 8. LAVATORY (SINK):
 - CENTERLINE = 460 mm FROM WALL
 - CLEARANCE UNDERNEATH = 760mm; 735 HIGH@FRONT, 685 HIGH @ POINT 205 BACK FROM FRONT, 250 HIGH OVER A DISTANCE FROM A POINT 280-430 BACK FROM FRONT
 - EXPOSED PARTS TO BE INSULATED IF PRESENT A BURN HAZARD.
 - FACET HANDLES TO BE LEVER TYPE WITHOUT SPRINGLOADING
 - SOAP AND TOWEL DISPENSERS NOT TO BE MORE THAN 1200 ABOVE FLOOR
- 9. MIRROR
 - BOTTOM EDGE IS NOT MORE THAN 1000 AFF
 - INCLINED TO THE VERTICAL TO A PERSON IN A WHEELCHAIR
- 10. WATER CLOSETS (TOILET); BARRIER FREE
 - SEAT LOCATED NOT LESS THAN 430 AND NOT MORE THAN 485mm AFF.
 - HAND OPERATED FLUSHING CONTROLS THAT ARE EASILY ACCESSIBLE TO WHEELCHAIR USER
 - EQUIPPED WITH A SEAT LID OR OTHER BACK SUPPORT
- 11. GRAB BARS: LOCATED HORIZONTAL BESIDE THE WATERCLOSET, 1200mm LONG, POSITION BETWEEN 300 &330 ABOVE TOILET SEAT, MIDPOINT @ FRONT EDGE OF THE TOILET
 - LOAD = 1.3kN
 - DIAMETER BETWEEN 30 & 40 mm
 - CLEARANCE FROM WALL BETWEEN 35 & 45 mm





ELEVATION B



ELEVATION C



ELEVATION D

NEW BARRIER FREE SINK
1 : 25

NEW BARRIER FREE WASHROOM