PUMP HOUSE EXISTING AND PROPOSED PLANS

LEGEND, PLANS & SINGLE LINE DIAGRAM

Contract No. 170825.01 | SABLE ISLAND WATER INFRASTRUCTURE UPGRADE










Project No. 170825.01

MAY 17, 2018









	Power:	120/240V	1ø, 3-WIRE		PANEL: A								SYM. IC.:	10,000	T
	# OF CCTS:				LOCATION: PUMP HOUSE MAINS:							100A	1		
	INCOMING:														
Remarks	Designation INISIDE LIGHT		LOAD				PHASE			LOA		AD	Designation	Remarks	
Ren			Α	В	CCT#	BKR	а	a b	BKR	CCT#	Α	В		Ren	
				100		1	15	•		15	2			OUTSIDE LIGHT	1
1	PLUG - WATER SOFTENER HEATER				3	15		•	25	4		560		2	
			750		5	15	•		25	6	560		MAIN PUMP		
				750	7	13		•	25	8		560		2	
	RECEPTACL			460		9	15	•		23	10	560		STANDBY PUMP	
	RECEPTACL				460	11	15		•	15	12		48	HEAT TRACE	3
	RECEPTACL			300		13	15	•		15	14	500		WELL PUMP CONTROL PANEL	3
	RECEPTACL				300	15	15		•	15	16			SPARE	
	SPARE				17	15	•		15	18			SPARE		
	SPARE					19	15		•	20	20			SPARE	
	SPARE SPARE				21	15	•		-	22			SPACE		
					23	15		•	-	24			SPACE		
	Т	TOTAL [VA]		1610	1510							1620	1168	TOTAL [VA]	
SOU	RCE:					TOTAL A:		32	3230 AVERAGE POWER/PH		HASE:		2954.00		
					TOTAL B:		26	78	MAXIMUM LINE CURF		RENT:		26.92		
FEE	DER:									[%] PHASE IMBALANCE:					
						TOTAL:		59	08	FEEDER BREAKER:				N/A	\top
	Remarks:	1	RE-FEED E	EXISTING LO	DAD										
		2													
		3													

BILL OF MATERIAL						
ITEM	QTY.	DESCRIPTION	SUPPLIED BY	INSTALLED B		
1	1	ENCLOSED MOULDED CASE CIRCUIT BREAKER, 600V, 20A, 2 POLE, 10,000 KA INTERRUPTING RATING, NEMA TYPE 4X ENCLOSURE, HEAVY DUTY, MANUFACTURED BY EATON, SIEMENS, OR SCHNEIDER ELECTRIC.	CONTRACTOR	CONTRACTOR		
2	1	7.5kVA EPOXY ENCAPSULATED TRANSFORMER, 600-120/240VAC, 10	CONTRACTOR	CONTRACTOR		
3	1	PANELBOARD, 100A, 120/240V, 1ø, 3 WIRE, 24 CIRCUITS, SURFACE MOUNT, MAIN LUGS, EATON POWERLINE PRL1a PANELBOARD, NEMA 12 ENCLOSURE AND BRANCH BREAKERS. REFER TO PANEL SCHEDULE FOR RATINGS AND QUANTITY OF BRANCH BREAKERS.	CONTRACTOR	CONTRACTOR		
4	2	COMBINATION MOTOR STARTER NEMA SIZE 1 c/w HOA SWITCH, GREEN RUN LED INDICATOR LIGHT, AND RED FAULT LED INDICATOR LIGHT. MOTOR STARTER TO HAVE PADLOCKABLE MAIN SWITCH WITH A MOULDED CASE CIRCUIT BREAKER, SIZED AS INDICATED. STARTER TO BE 240V, 1 PHASE, IN A NEMA TYPE 4X ENCLOSURE. STARTER TO BE RATED 1.5HP AT 240VAC.	CONTRACTOR	CONTRACTOR		
5	1	SPLITTER BOX, 600V, 60A, 1¢, 3W, EUROBEX OR APPROVED EQUIVALENT COMPLETE WITH NEMA 12 ENCLOSURE AND SPLITTER BLOCKS. SIZED AS REQUIRED.	CONTRACTOR	CONTRACTOR		
6	1	WELL PUMP CONTROL PANEL c/w A 3 POSITION SELECTOR SWITCH, 2 POSITION SELECTOR SWITCH, SOLID STATE ALTERNATOR, CONTROL COMPONENETS AND NEMA 4X ENCLOSURE AS SPECIFIED. REFER TO CONTROL SCHEMATIC #1 ON THIS DRAWING AND THE SCOPE OF WORK DOCUMENT FOR DETAILED SPECIFICATIONS.	CONTRACTOR	CONTRACTOR		

LIGHTING SCHEDULE									
LUMINAIRE TYPE	SUPPLY VOLTAGE	LAMP SOURCE	NUMBER OF LAMPS	LAMP WATTAGE	GENERAL DESCRIPTION				
L1	120Vac	LED	N/A	38	1219mm LED ENCLOSED AND GASKETED NON-METALLIC INDUSTRIAL VAPORTIGHT				


REFER TO SPECIFICATIONS FOR COMPLETE REQUIREMENTS.






240V POWER FIELD WIRING IN CONDUIT

- ELECTRONIC OVERLOAD



- ALL ELECTRICAL EQUIPMENT IS NEW UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
- 3. FIELD CONTROL WIRING TO BE #14AWG RW90, NUMBER OF CONDUCTORS AS INDICATED PLUS #14AWG BOND IN CONDUIT.



SABLE ISLAND WATER
INFRASTRUCTURE UPGRADE

ELECTRICAL

SCHEDULES



CBCL No Contract No Date Scale SEPT 2017 AS NOTED



SEPT 2017 AS NOTED

Designed Drawn
DK TS

Checked Approved
LH

Sheet No
2 of 2

Drawing No E02