



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada - Pacific  
Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Float Reconstruction	
<b>Solicitation No. - N° de l'invitation</b> F1571-188003/A	<b>Amendment No. - N° modif.</b> 001
<b>Client Reference No. - N° de référence du client</b> F1571-188003	<b>Date</b> 2018-08-13
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-036-8395	
<b>File No. - N° de dossier</b> PWY-8-41070 (036)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2018-08-20</b>	
<b>Time Zone</b> Fuseau horaire Pacific Daylight Saving Time PDT	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Martin (PWY), Delia	<b>Buyer Id - Id de l'acheteur</b> pwy036
<b>Telephone No. - N° de téléphone</b> (778) 707-2139 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> DFO - Port Alberni Small Craft Harbour - Port Alberni, BC	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation. - N° de l'off. à comm.  
F1571-188003/A

Amd. No. - N° de la modif.  
001

Buyer ID - Id de l'acheteur  
pwy036

Client Ref. No. - N° de réf. du client

File No. - N° du dossier  
PWY-8-41070

CCC No./N° CCC - FMS No/ N° VME

---

This Amendment #001 is raised to:

Issue Addendum No. 1.

Please see Addendum No. 1 attached.

The addendum will form part of the contract documents.

**All other terms and conditions remain unchanged.**

**The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.**

**1.0 Response to Bidders' Inquiries:**

- 1.1 Please find below a response to bidder's inquiries received as of 10:00am PST, Aug 13<sup>th</sup>, 2018.

Q1: What fungicide can be used on the piles?

A1: Examples of fungicide include: Bora-Care and Cobra Rods Fungicide.

Q2: Will there be a laydown area that material can be stored onsite during construction?

A2: Yes, bidders shall assume a laydown area will be provided on the wharf. The specific size and location will be provided after award.

Q3: What are the sizes of the concrete panels?

A3: Typical concrete panel sizes are provided on Drawing PA-FR-002.

Q4: Will the new joists be the Standard "DPW" float kit materials?

A4: Refer to Specifications Section 01 11 00, 4.5.2.2. The contractor is required to supply and install new ACZA salt treated timber joists. Joists shall be field treated where cut or drilled, as per Section 00 99 00.

Q5: How many risers shall we allow for in the 100m of bull rail to be replaced?

A5: Bidders shall assume riser blocks are required every 1.5m. The exact number of riser blocks required shall be determined during the Contractor's site visit, as part of item 4.5.1.1.

Q6: What length should the Fascia Boards be supplied in?

A6: Fascia Boards shall be supplied minimum 6.09m (20 feet) long. New Fascia Boards shall be custom cut to match the length of the replaced fascia boards.

Q7: Is the decking to be surfaced S1S2E?

A7: Yes.

**2.0 Specification Amendments**

**2.1 Refer to Specifications, Summary of Work - Section 01 11 00, 4.5.2.1:**

Delete Clause 4.5.2.1.1:

“Some hardware has already been removed from the concrete panels. Bidders shall assume 10% of hardware has been removed and therefore, a credit for this shall be applied to this item.”

Add Clause 4.5.2.1.1:

“All hardware securing the concrete panels has been disconnected. Therefore, this work shall not be included in this item.”