

CLARIFICATIONS  
Assignment of R.079800.009  
Rideau Canal Jones Falls Locks 39-42 Rehabilitation and Timber Bridge Replacement

**Question 1:** Regarding the Temporary Bridge supplied by Park Canada, please provide the weight of the bridge. Please advise the max traffic load rating of the temporary bridge?

**Answer 1:** The weight of the Temporary Bridge (with decking to be supplied by Contractor) is approximately 16 tonnes. The bridge is unposted for legal Highway Loads. See Amendment #004 for additional requirements.

**Question 2:** Spec section 01 22 01 lists 68 (L1 to L68) lump sum items for Part A and 35 items (L69 to L103) for part B. Should the Tender form include these items?

**Answer 2:** These items are already included in the tender form. All lump sum items noted in Specification 01 22 01 for Part A and Part B are to be included in the Lump Sum Amount (LSA) in Appendix 1 – Combined Price Form. The break-down of the Lump Sum price as per Part 1.5 and Part 1.6 of Section 01 22 01 are to be submitted 7 days after award as per Article 1.3.2 in Section 01 22 01.

**Question 3:** Please confirm if the anchor supply for item U77 to U88 is included in item U77 to U88 or is included in item U17.

**Answer 3:** The supply of anchors and dowels is included in Items U77 to U88 as per Section 05 05 20 – Anchorages, article 1.3 Measurement and Payment Procedures, Paragraph .3.

**Question 4:** Part 1.1.3 of spec section 06 05 73 Wood Treatment Part B, refers to section 06 15 00 – Wood Decking. This section was not included in the specifications?

**Answer 4:** Reference to Section 06 15 00 – Wood Decking to be removed from Part 1.1.3 of Specification Section 06 05 73. See Amendment #004.

**Question 5:** The specification List of Contents lists “Geotechnical Investigation Report No.171-01726-00 prepared by WSP Canada Inc. and dated June 2016”. Should this be June 2018?

**Answer 5:** It should be dated June 2018. See Amendment # 3 for the revised Tender Specifications.

**Question 6:** On the Bid and Acceptance Form the Construction Time is 185 weeks. Assuming notification of acceptance in Oct 2018, then the completion would be April/May 2022 approx. Part 1.38.4 spec section 01 10 00 states that “Contractor to complete all construction works, have site restored and demobilize entirely from site by end of day on May 7, 2021” We assume the Tender Form takes precedence over the specifications.

**Answer 7:** BA06 Construction Time on the Bid and Acceptance Form will be deleted and replaced with the following:

The Contractor must perform and complete the Work by May 7, 2021, refer to other work restrictions in Section 01 10 00.

See Amendment #004.

**Question 8:** I am reading the Jones Falls Lock Rehab & Replacement (EQ754-190325/A), and I am not sure if there are new gates considered in this RFP or just a remove and install.

**Answer 8:** Existing Gates, where specified, are to be removed, stored and reinstalled as part of the work. No new gates are part of the project.