



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS Á:

**Parks Canada Agency
1869 Upper Water Street,
Suite AH 201
Halifax, Nova Scotia
B3J 1S9**

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaries

Vendor/Firm Name and Address
Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

**Parks Canada Agency
1869 Upper Water Street,
Suite AH 201
Halifax, Nova Scotia
B3J 1S9**

Title-Sujet Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs, Rideau Canal National Historic Site		
Solicitation No. - No. de l'invitation 5P201-18-0119/A		Amendment No./N° de modification de l'invitation 002
Client Ref. No. - No. de réf du client. 872		Date: 27 August 2018
GETS Reference No. - No de reference de SEAG PW-18-00838233		
Solicitation Closes:		
at - á 14:00	on - le 06 September 2018	Time Zone - Fuseau horaire ADT - HAA
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Inquiries to: - Adresser toute demande de renseignements à : Jaime Creaser, Jaime.Creaser@pc.gc.ca		
Telephone No. - No de téléphone (902) 426-7513		Fax No. - No de FAX: (902) 426-1775
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: See Herein - Voir aux présentes		

TO BE COMPLETED BY THE BIDDER (type or print)
À ÊTRE COMPLÉTER PAR LE SOUMISSIONNAIRE (taper ou écrire en caractères d'imprimerie)

Vendor/Firm Name - Nom du fournisseur/de l'entrepreneur	
Address - Adresse	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur	
Titale - Titre	
Telephone No. - N° de téléphone: _____	
Facsimile No. - N° de télécopieur: _____	
Signature	Date

Solicitation No. - N° de l'invitation
5P201-18-0119/A

Amd. No. - N° de la modif.
002

Buyer - l'acheteur
Jaime Creaser

Client Ref. No. - N° de réf. du client
872

File Name - Nom du dossier
Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs,
Rideau Canal National Historic Site

AMENDMENT 002

This amendment is being raised to revise Appendix 1 Combined Price Form, and the specifications to solicitation 5P201-18-0119/A:

1. MODIFICATION TO APPENDIX 1 – COMBINED PRICE FORM

DELETE:

Unit Price Table in its entirety.

REPLACE WITH:

**THE ATTACHED PRICE FORM MUST BE USED IN ORDER FOR A BID TO BE DEEMED RESPONSIVE.
ANY BIDS SUBMITTED USING THE PREVIOUS PRICE FORM WILL NOT BE ACCEPTED.**

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(es) extra (PU)	Extended amount (EQ x PU) applicable tax(es) extra
1	04 03 07	Remove and reset large displaced stones including consolidation, collar joints, bedding mortar, and pointing. See 09/S06. Average stone size: 450x800x500mm deep	Sq. m	16.0	\$ _____	\$ _____
2	04 03 07	Remove and reset small displaced stones including consolidation, collar joints, bedding mortar and pointing. See 09/S06. Average stone size: 200x300x300mm deep	Sq. m	3.0	\$ _____	\$ _____
3	04 03 42	New Large Stone: Remove and replace with new stone unit. Including all required consolidation, collar joints, bedding mortar and pointing. Average stone size for walls: 450x800x500mm deep.				
		a) Sandstone	Sq. m	2.1	\$ _____	\$ _____
		b) Limestone	Sq. m	4.9	\$ _____	\$ _____
4	04 03 42	New Small Stone: Remove and replace with new stone unit. Including all required consolidation, collar joints, bedding mortar and pointing. Average stone size for walls: 200x300x300mm deep.				
		c) Sandstone	Sq. m	1.0	\$ _____	\$ _____
		d) Limestone	Sq. m	1.0	\$ _____	\$ _____

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(es) extra (PU)	Extended amount (EQ x PU) applicable tax(es) extra
5	04 03 41	Dutchman Repair (Large): Average size: 450x800x200mm deep. Include all required collar joints, bedding mortar, pointing, and pins. See 05/S06.				
		e) Sandstone	Sq. m	74.2	\$ _____	\$ _____
		f) Limestone	Sq. m	31.8	\$ _____	\$ _____
6	04 03 41	Dutchman Repair (Small) Average size: 450x300x100mm deep. Including all required collar joints, bedding mortar, pointing and pins. See 04/S06.				
		g) Sandstone	Sq. m	21.0	\$ _____	\$ _____
		h) Limestone	Sq. m	9.0	\$ _____	\$ _____
7	04 03 41	Dutchman Repair (Edge) Average size: 1500x100x125mm deep. Including all required collar joints, bedding mortar, pointing and pins. See 03/S07.				
		i) Sandstone	Sq. m	9.8	\$ _____	\$ _____
		j) Limestone	Sq. m	4.2	\$ _____	\$ _____
8	04 03 41	Dutchman repair at concrete patch (Dc). Include all concrete removal, drilling concrete to verify depth, collar joints, bedding mortar, pointing and pins. See 11/S07				
		k) Sandstone	Sq. m	1.8	\$ _____	\$ _____
		l) Limestone	Sq. m	4.2	\$ _____	\$ _____
9	03 30 00	Shallow concrete repair on wall surface as per 04/S07.	Sq. m	2.0	\$ _____	\$ _____
10	03 30 00	Deep concrete repair on wall surface as per 05/S07.	Sq. m	4.0	\$ _____	\$ _____
11	04 03 41	In-situ Fracture Repair: In-situ repair to fractured limestone units. Including all pinning and stone repair. See 01/S06.	Each	66	\$ _____	\$ _____
12	04 03 41	Remove existing steel inserts and repair with Dutchman plugs.	Each	76	\$ _____	\$ _____

Solicitation No. - N° de l'invitation
5P201-18-0119/A

Amd. No. - N° de la modif.
002

Buyer - l'acheteur
Jaime Creaser

Client Ref. No. - N° de réf. du client
872

File Name - Nom du dossier
Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs,
Rideau Canal National Historic Site

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(es) extra (PU)	Extended amount (EQ x PU) applicable tax(es) extra
13	04 05 19	Stainless steel anchors at mooring lines. See note 9 on drawing S03 and S05.	Each	24	\$ _____	\$ _____
14	04 03 07	Grouting of wall core, including installation and removal of tubing. See 08/S06. a) Install grout at Lock (Measurement to be verified daily).	Liters	8000	\$ _____	\$ _____
15	03 30 00	Skyward concrete repairs as per drawing 10/S06.	Sq. m	8.0	\$ _____	\$ _____
16	01 35 43	Removal of debris and material from Lock floor. Does not include mortar or stone waste.	Cubic m	40	\$ _____	\$ _____
TOTAL EXTENDED AMOUNT (TEA) Excluding applicable tax(es)						\$ _____
TOTAL BID AMOUNT (LSA +TEA) Excluding applicable tax(es)						\$ _____

Solicitation No. - N° de l'invitation
5P201-18-0119/A

Amd. No. - N° de la modif.
002

Buyer - l'acheteur
Jaime Creaser

Client Ref. No. - N° de réf. du client
872

File Name - Nom du dossier
Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs,
Rideau Canal National Historic Site

2. MODIFICATION TO SPECIFICATIONS

At section 01 10 00 General Requirements, subsection .2 Sequence of Work

INSERT: .5 For the Phase 1 work commencing in Fall 2018, navigation will be closed as of October 9, 2018 however, the lock must remain operational until October 23, 2018 to allow Parks Canada's maintenance vessel to pass through. Water levels will then be dropped by Friday, October 26, 2018. Therefore, it is anticipated that the coffer dam installations can commence as of October 27, 2018. For the Phase 2 work in Fall 2019, it is anticipated that the lock may be dewatered as of November 1, 2019.

ALL OTHER TERMS AND CONDITONS REMAIN THE SAME.
