



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

| | |
|---|--|
| Title - Sujet Port Edward Harbour Development | |
| Solicitation No. - N° de l'invitation F1571-188001/A | Amendment No. - N° modif. 002 |
| Client Reference No. - N° de référence du client F1571-188001 | Date 2018-08-28 |
| GETS Reference No. - N° de référence de SEAG PW-\$PWY-020-8399 | |
| File No. - N° de dossier PWY-8-41055 (020) | CCC No./N° CCC - FMS No./N° VME |
| Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-09-04 | Time Zone Fuseau horaire Pacific Daylight Saving Time PDT |
| F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/> | |
| Address Enquiries to: - Adresser toutes questions à: Ly, Ronny(PWY) | Buyer Id - Id de l'acheteur pwy020 |
| Telephone No. - N° de téléphone (604) 318-5750 () | FAX No. - N° de FAX (604) 775-6633 |
| Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Port Edward Harbour - Port Edward, BC | |

Instructions: See Herein

Instructions: Voir aux présentes

| | |
|--|--|
| Delivery Required - Livraison exigée | Delivery Offered - Livraison proposée |
| Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur | |
| Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur | |
| Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie) | |
| Signature | Date |

Solicitation No. - N° de l'invitation

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur

F1571-188001/A

002

pwy020

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

Les documents français seront disponibles sur demande

This Amendment 002 is raised to revise Appendix 1 – Combined Price Form and issue Addendum #1.

DELETE and REPLACE: Item 4 of the Mandatory Work Items on Appendix 1 – Combined Price Form with Removal and storage of existing Wharf (421) approach structure, including steel piles, pile caps and grating in the Port Edward Harbour Authority Storage Area.

See Addendum #1 below.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

Port Edward – Harbour Development Phase 2 Addendum #1

The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

Response to Bidders' Inquiries:

Please find below a response to bidder's inquiries received to date.

- Q1 How many of the lock blocks located on the south side of the fill lot can be relocated?**
- A1 30 lock blocks.
- Q2 Section 01 35 43 of the Specifications discuss environmental monitoring. Is this to be provided by and paid for by the contractor?**
- A2 No. The monitor is provided by Owner. The Contractor is responsible to provide notice of activities as described in 01 35 43 section 3.1 "Project Scheduling"
- Q3 There are existing users on the wharf areas requiring demolition. Is it assumed these users and the structures they utilize will be removed from the work area before construction commences or is this to be included in the demolition works?**
- A2 Yes. Contractor is to assume tenant (ie."existing users") structures will be relocated by Owner prior to the start of construction works.

Amendments:

Please find amendments to the specifications.

- 1. The Item 2.2.4 of the "Work Included" in the Technical Specifications – Section 01 01 00 – Summary of Work is revised to read as follows**

Item 2.2.4 – Removal and storage of the existing Wharf (421) approach structure
The lump sum cost for this item shall include the supply of materials, equipment, tools, services, labour and all things necessary to complete the removal of approximately 8.5m long and 3.7m wide existing Wharf (421) approach structure , and stored in the Port Edward Harbour Authority storage yard. The wharf approach consists of a steel grate deck supported by steel stringers, pile caps and steel pipe vertical bearing piles; see reference drawing E582-01 to -05. The wharf approach structure must be removed as an entire unit separated from support piles and abutment. Steel pipe piles to be extracted or cut at a minimum of 2 m below finished grade and left in place.

END OF ADDENDUM