

PART 1 **GENERAL**

1.1 **SUMMARY**

- .1 Related Sections.
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 74 19 - Construction/Demolition Waste Management and Disposal
 - .3 Section 01 45 00 - Quality Control
 - .4 Section 01 35 43 - Environmental Procedures
 - .5 Section 01 35 29.06 - Health and Safety Requirements
 - .6 Section 31 23 33.01 - Excavating, Trenching and Backfilling.

1.2 **REFERENCES**

- .1 Canadian Council of Ministers of the Environment (CCME).
- .2 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act, 1999 (CEPA), c. 33.
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .4 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act, 1992 (TDGA), c. 34.

1.3 **DEFINITIONS**

- .1 Waste Audit (WA): detailed inventory of materials in building. Indicates quantities of reuse, recycling and landfill.
 - .1 Involves quantifying by volume/weight amounts of materials and wastes generated during construction, demolition, deconstruction, or renovation project.
 - .2 Indicates quantities of reuse, recycling and landfill.
- .2 Waste Management Coordinator (WMC): contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.
- .3 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. WRW is based on information acquired from WA.

1.4 **SUBMITTALS**

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings.
 - .1 Submit for approval drawings, diagrams or details showing sequence of demolition work required by authorities having jurisdiction.

- .3 Waste Reduction Workplan: prior to beginning of Work on site submit detailed Waste Reduction Workplan in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal indicate:
 - .1 Descriptions of and anticipated quantities in percentages of materials to be salvaged reused, recycled and landfilled.
 - .2 Schedule of selective demolition.
 - .3 Number and location of dumpsters.
 - .4 Anticipated frequency of tippage.
 - .5 Name and address of haulers waste facilities waste receiving organizations

1.5 QUALITY ASSURANCE

- .1 Regulatory Requirements: ensure Work is performed in compliance with CEPA, CEAA, TDGA, and applicable Provincial/Territorial regulations.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Perform Work in accordance with Section 01 35 43 - Environmental Procedures.
- .2 Storage and Protection.
 - .1 Protect existing items designated to remain and items designated for salvage. In event of damage to such items, immediately replace or make repairs to approval of Departmental Representative and at no cost to Departmental Representative.
 - .2 Remove and store materials to be salvaged, in manner to prevent damage.
 - .3 Store and protect in accordance with requirements for maximum preservation of material.
 - .4 Handle salvaged materials as new materials.
- .3 Waste Management and Disposal.
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
 - .2 Divert excess materials from landfill to site approved by Departmental Representative.
 - .3 Place materials defined as hazardous or toxic in designated containers.
 - .4 Handle and dispose of hazardous materials in accordance with CEPA, Regional and Municipal regulations.
 - .5 Ensure emptied containers are sealed and stored safely.
 - .6 Source separate for recycling materials that cannot be salvaged for reuse including wood, metal and concrete.
 - .7 Remove materials that cannot be salvaged for reuse or recycling and dispose of in accordance with applicable codes at licensed facilities.

1.7 SITE CONDITIONS

- .1 Site Environmental Requirements.
 - .1 Perform work in accordance with Section 01 35 43 - Environmental Procedures.
 - .2 Ensure that selective demolition work does not adversely affect adjacent watercourses, groundwater and wildlife, or contribute to excess air and noise pollution.
 - .3 Do not dispose of waste of volatile materials including but not limited to, mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers.
 - .1 Ensure proper disposal procedures are maintained throughout the project.

- .4 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers or onto adjacent properties.
- .5 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authorities as directed by Departmental Representative.
- .6 Protect trees, plants and foliage on site and adjacent properties where indicated.
- .2 Existing Conditions.
 - .1 Remove contaminated or hazardous materials listed as hazardous as defined by authorities having jurisdiction as directed by Departmental Representative from site, prior to start of demolition Work, and dispose of at designated disposal facilities in safe manner in accordance with applicable regulatory requirements.

1.8 SCHEDULING

- .1 Employ necessary means to meet project time lines without compromising specified minimum rates of material diversion.
 - .1 Notify Departmental Representative in writing when unforeseen delays occur.

PART 2 PRODUCTS

2.1 EQUIPMENT

- .1 Leave machinery running only while in use, except where extreme temperatures prohibit shutting machinery down.

PART 3 EXECUTION

3.1 PREPARATION

- .1 Inspect site with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

3.2 REMOVAL OF HAZARDOUS WASTES

- .1 Remove contaminated or dangerous materials defined by authorities having jurisdiction, relating to environmental protection, from site and dispose of in safe manner to minimize danger at site or during disposal.

3.3 REMOVAL OPERATIONS

- .1 Remove items as indicated.
- .2 Do not disturb items designated to remain in place.
- .3 Remove as many trees designated trees during demolition.
 - .1 Obtain written approval of Departmental Representative prior to removal of trees.

- .4 Salvage.
 - .1 Dismantle items containing materials for salvage and stockpile salvaged materials at locations.
- .5 Disposal of Material.
 - .1 Dispose of materials not designated for salvage or reuse on site Departmental Representative at authorized facilities approved in Waste Reduction Workplan.
 - .2 Trim disposal areas to approval of Departmental Representative.
- .6 Backfill.
 - .1 Backfill in areas as indicated and in accordance with Section 31 23 33.01 - Excavating, Trenching and Backfilling.

3.4 STOCKPILING

- .1 Label stockpiles, indicating material type and quantity.
- .2 Designate appropriate security resources/measures to prevent vandalism, damage and theft.
- .3 Locate stockpiled materials convenient for use in new construction to eliminate double handling wherever possible.
- .4 Stockpile materials designated for alternate disposal in location which facilitates removal from site and examination by potential end markets, and which does not impede disassembly, processing, or hauling procedures.

3.5 REMOVAL FROM SITE

- .1 Remove stockpiled material as directed by Departmental Representative, when it interferes with operations of project.
- .2 Remove stockpiles of like materials by alternate disposal option once collection of materials is complete.
- .3 Transport material designated for alternate disposal using facilities and in accordance with applicable regulations.

3.6 RESTORATION

- .1 Restore areas and existing works outside areas of demolition to match condition of adjacent, undisturbed areas.
- .2 Use soil treatments and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.

3.7 CLEANING

- .1 Remove debris, trim surfaces and leave work site clean, upon completion of Work.

END OF SECTION