



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS Á:

Parks Canada Agency
1869 Upper Water Street,
Suite AH 201
Halifax, Nova Scotia
B3J 1S9

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaries

Vendor/Firm Name and Address
Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Parks Canada Agency
1869 Upper Water Street,
Suite AH 201
Halifax, Nova Scotia
B3J 1S9

Title-Sujet Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs, Rideau Canal National Historic Site		
Solicitation No. - No. de l'invitation 5P201-18-0119/A		Amendment No./N° de modification de l'invitation 003
Client Ref. No. - No. de réf du client. 872		Date: 31 August 2018
GETS Reference No. - No de reference de SEAG PW-18-00838233		
Solicitation Closes:		
at - á 14:00	on - le 06 September 2018	Time Zone - Fuseau horaire ADT - HAA
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Inquiries to: - Adresser toute demande de renseignements à : Jaime Creaser, Jaime.Creaser@pc.gc.ca		
Telephone No. - No de téléphone (902) 426-7513		Fax No. - No de FAX: (902) 426-1775
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: See Herein - Voir aux présentes		

TO BE COMPLETED BY THE BIDDER (type or print)
À ÊTRE COMPLÉTER PAR LE SOUMISSIONNAIRE (taper ou écrire en caractères d'imprimerie)

Vendor/Firm Name - Nom du fournisseur/de l'entrepreneur	
Address - Adresse	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur	
Titale - Titre	
Telephone No. - N° de téléphone: _____	
Facsimile No. - N° de télécopieur: _____	
Signature	Date

AMENDMENT 003

This amendment is being raised to respond to questions for solicitation 5P201-18-0119/A:

1. QUESTIONS AND ANSWERS

Q1: Can the downstream cofferdam and work associated with its installation be completed in phase 2?

A1: No. The work required in Phase 1 must be completed as noted, in order to complete the work in two years.

Q2: Can the contractor tie into the power on-site power if it agrees to pay all bills while the work is happening?

A2: We have allowed hydro hook-ups in past project. We will allow it on this project and will charge the costs to the contractor and the end.

Q3: Please confirm if all temporary roads must be removed and reinstalled between phases?

A3: Yes, with the exception of the access road created through the bush from the water plant, which is to remain. In phase 2, only the roads adjacent to the PCA office need to be reinstalled, assuming access is not required from the west lawn.

Q4: Can the contractor maintain a small on-site presence during the summer of 2019?

A4: No, the Contractor must fully demobilize between phases.

Q5: We could not find soil sample test results in the project documentation. Have you had these completed and if so can you please provide for us so that we know exactly what type of contamination we are dealing with.

A5: The soil sample results are in Appendix 5 of the BIA "Risk Assessment and Environmental Monitoring Report (AEL Environmental, 2018). Refer to "10888_OldSly_RA_Environ_Monitoring_Final" which will be posted on B&S. (See folder DPS 003 5P201-18-0119)

Q6: Please confirm that an emergency management plan must be provided by the contractor and that this plan must meet the requirements outlined in the project documentation? Also, please outline where the costs for this plan and the implementation and maintenance should be carried for on the tender form.

A6: Emergency management plans are usually included in the Health and Safety Plans. Perhaps the question refers to the environmental management plans? If the case, the EMP must be provided by the Contractor. The EMP is prepared by a qualified environmental consultant, as described in the documents. Requirements for the EMP are described in the ESG. There is a line in the bid form for all environmental measures, which should include the EMP, the monitoring and mitigation measures.

Q7: Please confirm what types of cofferdams are acceptable and what types are not acceptable for installation?

A7: Refer to section 31 23 19. Earth cofferdams or cofferdams with granular materials with sand and fines are not acceptable. Otherwise it is up to the bidder. In the past we have used sheet piles and sandbags.

Q8: Are the railings being replaced/brought up to code?

A8: No work is required on the railings, except to remove and reinstall where noted.

Q9: Is there limestone and sandstone present?

A9: Yes. See revised bid form for quantities. Generally the procedure is to repair limestone units with limestone, and repair sandstone units with sandstone.

Solicitation No. - N° de l'invitation
5P201-18-0119/A

Amd. No. - N° de la modif.
003

Buyer - l'acheteur
Jaime Creaser

Client Ref. No. - N° de réf. du client
872

File Name - Nom du dossier
Old Slys Locks 26 & 27 Heritage Stone Masonry Repairs,
Rideau Canal National Historic Site

Q10: Is there a conduit across the downstream approach walls?

A10: No there is no conduit at this location.

Q11: The excavation on the upstream west wall might damage the roots of the adjacent tree. Does the tree have to remain?

A11: Protect the tree and roots as much as possible. If it is determined that the tree cannot stay, contact PCA for direction.

Q12: Can the silt at the cofferdam remain?

A12: It can remain if the cofferdam designer feels it can remain and the seal can be maintained. Turbidity limits during cofferdam installation/removal must also be respected.

Q13: We request clarification on restoring or replacing the ladders.

A13: The ladders should be new and galvanized as noted on the drawings.

ALL OTHER TERMS AND CONDITONS REMAIN THE SAME.
