

Project No.: R.082215.001

September 4, 2018

The following changes to the tender documents are effective immediately and will form part of the contract documents:

1. RESPONSE TO INQUIRIES DURING THE SOLICITATION PERIOD

ITEM #	QUESTION	ANSWER
1	Please provide a specification for the new acoustic ceilings	Please find attached Specification section 09 51 00 Acoustic Ceiling
2	There is a discrepancy between the drawings and the specifications for the paper towel dispenser and waste receptacle. Please clarify	Revise Specification section 10 28 00 Washroom Accessories item 3.3.1: Delete reference to the Combination towel dispenser/waste receptacle and replace with the following: ' Towel dispenser: surface mounted, interior of galvanized steel, exterior of 0.8mm stainless steel. Suitable for dispensing roll paper towels. Also provide a wall mounted 15 gallon capacity heavy duty plastic garbage bin with a self closing lid. Measurements approximately 500mm W x 300mm D x 850mm H. " Also refer to updated drawings 03/A5.0 and 05/A5.0
3	There is a discrepancy between the drawings and the specifications for the toilet tissue dispenser. Please clarify	Revise Specification section 10 28 00 Washroom Accessories item 3.3.1: Revise the reference to Toilet tissue dispenser to read: surface mounted, stainless steel or cast aluminum with satin finish frame, plastic spindles, concealed locking device, theft-resistant, holds two rolls up to 150mm diameter (2000 sheets), under spring tension for controlled delivery Also refer to updated drawings 03/A5.0
.4	The specification calls for knurling of the grab bars and nearly every manufacturer now peens grab bars as the grooves in knurled grab bars were a dirt and bacteria location and so in most cases, knurling is no longer used.	Peened grab bars are acceptable in lieu of the knurled
.5	Back plates are no longer provided with grab bars as manufacturers have discontinued them due to lack of demand. They had to be installed while the wall was being framed and they never arrived in time so wood backing was put in by the contractors.	Wood backing is acceptable in lieu of steel back plates

Project No.: R.082215.001

September 4, 2018

.6	Could you please tell me where I can find the revised drawing with the new floor finishes?	No new finishes drawing has been issued. Updated written instruction for the finishes were provided in the previous addendum
	Type of Fire Alarm in building?	2 stage fire alarm system Siemens (Cerberus Pyrotronics)
	Is there a cable tray in crawl space or above ceiling? For data and security in the Churchill unit?	no cable tray
	Crawl space below Churchill Unit if we have to run all horizontal runs below for security, data and other systems?	Yes there is a crawl space under all areas.
	How hard will it be to get through floor and into crawl space if needed?	The floor is 8" reinforced concrete. Nothing else is in the floor. Crawl space is +-6' high and clean.

2. Specifications

Insert New Section 09 51 00 Acoustic Ceiling.pdf (ATT A013.PDF)

3. Drawings

Replace Drawing A5.0 - Large Scale Plans and Elevations with Revised Drawing A5.0 R1.pdf (ATT A014.PDF)

END OF ADDENDUM NO. 4