

GENERAL NOTES:

GENERAL

1. ALL ELEVATIONS ARE EXPRESSED IN METERS.
2. ALL DIMENSIONS ARE EXPRESSED IN METERS, UNLESS OTHERWISE NOTED.
3. VERIFY ALL ELEVATIONS AND DIMENSIONS OF EXISTING STRUCTURES AND FEATURES IN THE FIELD.
4. ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL BUILDING CODE OF CANADA, CANADIAN CONSTRUCTION SAFETY CODE AND ALL REGULATIONS AS SET OUT BY LOCAL AUTHORITIES HAVING JURISDICTION.
5. COMPLY WITH ALL THE REQUIREMENTS OF THE TECHNICAL SPECIFICATIONS BOUND SEPARATELY.
6. PRIOR TO BEGINNING ANY CONSTRUCTION IT IS REQUIRED FOR CONTRACTORS AND ANY SUB CONTRACTORS TO CALL THE APPROPRIATE NUMBERS TO REQUEST LOCATES FOR UNDERGROUND UTILITIES..

ENVIRONMENTAL

1. WORK OPERATIONS SHALL BE CARRIED OUT AT ALL TIMES SO AS TO CAUSE A MINIMUM OF DISTURBANCE AND SILTATION TO STREAMS.
2. USE SILT FENCE AND ALL OTHER APPROPRIATE MEANS TO PREVENT SEDIMENT FROM DISTURBED AREAS FROM ENTERING ANY WATERCOURSE. LOCATE AS REQUIRED AND DIRECTED.
3. MONITOR EFFECTIVENESS OF EROSION AND SEDIMENT CONTROL MEASURES DURING AND AFTER RAINFALL EVENTS. REPAIR AND REPLACE AS NECESSARY.
4. REVEGETATE ALL DISTURBED AREAS WITH APPROVED SEED MIX TO THE SATISFACTION OF THE DEPARTMENTAL REPRESENTATIVE




EXCAVATION

1. PROVIDE PROTECTION TO ALL SURVEY AND LAYOUT MARKERS, INCLUDING BENCHMARKS AND EXISTING FACILITIES, EQUIPMENT, ETC.
2. EXCAVATE TO ELEVATIONS INDICATED AND TO WELL DEFINED LINES SUFFICIENT TO ALLOW INSTALLATION, CONSTRUCTION AND INSPECTION OF WORK WITH MINIMUM FILL.
3. EXCAVATIONS SHALL BE LEVEL, DRY, FREE OF LOOSE OR ORGANIC MATTER.
4. PROTECT BOTTOM OF EXCAVATION FROM SOFTENING. SOFTENED SOIL SHALL BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE WITH DENSE STRUCTURAL FILL COMPACTED TO 95% OF MODIFIED PROCTOR.
5. STOCKPILE EXCAVATED MATERIAL SO AS TO NOT INTERFERE WITH SITE OPERATIONS OR DRAINAGE.
6. CORRECT UNAUTHORIZED EXCAVATION UNDER BEARING SURFACES AND OTHER AREAS WITH DENSE STRUCTURAL FILL COMPACTED TO 95% OF MODIFIED PROCTOR, AT NO EXTRA COST.
7. DO NOT PROCEED WITH FURTHER WORK UNTIL EXCAVATION HAS BEEN INSPECTED AND APPROVED BY THE DEPARTMENTAL REPRESENTATIVE.

BACKFILL

1. DO NOT COMMENCE BACKFILLING UNTIL AREAS OF WORK TO BE BACKFILLED HAVE BEEN INSPECTED AND APPROVED BY THE DEPARTMENTAL REPRESENTATIVE.
2. AREAS TO BE BACKFILLED SHALL BE FREE OF DEBRIS, SNOW, ICE, WATER OR FROZEN GROUND.
3. BACKFILL ONLY WITH MATERIAL APPROVED BY THE DEPARTMENTAL REPRESENTATIVE IN CONTINUOUS HORIZONTAL LAYERS NOT EXCEEDING SPECIFIED THICKNESS AND COMPACT AS SPECIFIED.
4. COMPACT MATERIAL AS SPECIFIED.

GENERAL LOCATION PLAN



1	ISSUED FOR TENDER	AUG.16 2018
revisions		date

project project

**SOURIS MARSHALLING  
YARD PAVING  
SOURIS, PEI**

drawing dessin

**GENERAL NOTES  
AND  
GENERAL LOCATION PLAN**

designed	GC	conçu
date	JUN 2018	
drawn	GC	dessiné
date	JUN 2018	
approved		approuvé
date		
Tender	2018-08-27	Submission
PWSC Project Manager	Administrateur de projets TPSCG	
project number		no. du projet
	<b>R. 090692.001</b>	
drawing no.		no. du dessin
	<b>G2</b>	