



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave. Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6

Title - Sujet GOCB Renovations	
Solicitation No. - N° de l'invitation EV385-191036/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client PSPC	Date 2018-09-10
GETS Reference No. - N° de référence de SEAG PW-\$PWU-183-11442	
File No. - N° de dossier PWU-8-41098 (183)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-09-19	Time Zone Fuseau horaire Mountain Daylight Saving Time MDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Tikhonovitch (RPC), Alex	Buyer Id - Id de l'acheteur pwu183
Telephone No. - N° de téléphone (780) 901-7940 ()	FAX No. - N° de FAX (780) 497-3510
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Project Title:	Addendum No:
Government of Canada Buildings Renovation, Inuvik and Hay River	I
Project Location:	Solicitation Number:
Inuvik and Hay River, NT	EV385-191036/A
Consultant's Name:	Date:
Sanayut Consulting Professional Engineers Corporation	September 7, 2018
The following changes in the solicitation documents are effective immediately. This addendum will form part of the contract documents	
Drawings	
<p>The drawings listed below have been revised.</p> <ul style="list-style-type: none"> • 01-Cover Sheet-List of Drawings • A1-Inuvik Exterior Elevations • A2-Inuvik Snow Lip Remediation Details • A3-Inuvik Loading Dock Repair-Inuvik <p>The drawing list and drawings have been modified to provide clarity on which drawings apply to Inuvik and which apply to Hay River. The drawing list also now includes the additional two electrical drawings.</p> <p>The drawings listed above have been revised according to comments below. Please use the attached versions.</p>	
Questions	
<p>Responses are provided in red font below to questions received from potential bidders:</p> <ol style="list-style-type: none"> 1. Please provide detailed scope of work for the tender. A detailed scope of work is attached. 2. Are the building facilities available for use during construction? Namely, the building washrooms and the building power and water supply. Yes, the building facilities are available for use during construction. 3. The following questions are in regard to the tender drawings: <ol style="list-style-type: none"> a. The drawing numbers are incorrectly labelled and referenced. For example, details A3-1 and A3-2 shows up on drawing A2 and there are two extra electrical drawings than was shown on the drawings list. See above. Details have been re-numbered on Drawing A-2. The two electrical drawings have been added to the attached drawings list. b. Which building does the elevations drawing A1 show - the Inuvik building or the Hay River building? It shows the Inuvik building. The drawing has been re-named accordingly. Does the snow lip remediation only apply to this building? Yes, the snow lip remediation only applies to the Inuvik building and the drawing has been renamed accordingly 	

Project No. R.015592.040/.472/.474/.512
Government of Canada Buildings Bundled Project
Inuvik and Hay River, NT

DETAILED DESCRIPTION OF THE WORK

The above-referenced project includes upgrades and renovations to the government buildings in Inuvik and Hay River. The work includes the following scope:

1. Inuvik Building – snow falling on patrons around the entire building was identified as an issue. It was determined that the source of the falling snow is an approximately 50mm wide lip on the siding located near the top of the exterior wall. This issue impacts the entire perimeter of the building. Based on this information, a plan has been developed to modify the cladding to prevent snow from accumulating and falling on patrons and employees. The remedial option chosen involves the addition of a Z channel above the lip around the entire building.
2. Inuvik Building – the loading dock has deteriorated and specifically, the side slopes have become a hazard to employees loading and unloading goods. The goal of this work is to modify the loading dock ramp to allow for safe, effective unloading. The remedial option selected involves placing cast in place retaining walls on the sides of the ramp with a railing mounted on the top of the wall and re-grading the ramp and surrounding area.
3. Inuvik and Hay River Lighting – after years of tenant fit up and customization, the lighting throughout the Inuvik and Hay River buildings is inconsistent, with a variety of lighting levels, lamping types, and light temperatures. Upgrades have been designed to provide adequate and more consistent interior lighting throughout the interiors of both buildings. After a thorough review of the existing conditions and needs, remedial recommendations were made to ensure the buildings are in compliance with building standards and to set forth a basis on which improvement can be made.

Project No:
R.015992.040 / .472 / .474 / .512
GOCB Bundled Projects
Inuvik & Hay River, NT

Section 00 01 10
TABLE OF CONTENTS
Page 1 of 2

Section Number	Section Title	No. of Pages
DIVISION 01 – GENERAL REQUIREMENTS		
Section 01 11 00	Summary of Work	6
Section 01 33 00	Submittal Procedures	4
Section 01 35 29.06	Health and Safety Requirements	3
Section 01 45 00	Quality Control	2
Section 01 74 11	Cleaning	2
Section 01 74 21	Construction Demolition Waste	6
DIVISION 03 - CONCRETE		
Section 03 10 00	Concrete Forming and Accessories	3
Section 03 20 00	Concrete Reinforcing	3
DIVISION 09 - FINISHES		
Section 09 51 13	Acoustic Unit Ceilings	3
DIVISION 26 - ELECTRICAL		
Section 26 05 00	Common Work Results - Electrical	7
Section 26 05 20	Wire & Box Connectors 0-1000V	2
Section 26 05 21	Wires & Cables 0-1000V	2
Section 26 05 22	Connectors & Terminations	1
Section 26 05 28	Grounding - Secondary	2
Section 26 05 29	Hangers & Supports for Electrical Systems	2
Section 26 05 31	Splitters, Junction, Pull Boxes & Cabinets	1
Section 26 05 32	Outlet Boxes, Conduit Boxes & Fittings	2
Section 26 05 34	Conduits, Conduit Fastenings & Conduit Fittings	3
Section 26 27 26	Wiring Devices	2
Section 26 50 00	Lighting	1
DIVISION 31 - EARTHWORK		
Section 31 00 99	Earthwork for Minor Works	3
DIVISION 32 – EXTERIOR IMPROVEMENTS		
Section 32 11 16.01	Granular Sub-Base	3
Section 32 11 23	Aggregate Base Courses	3
DRAWING LIST		
ARCHITECTURAL		
01	Cover Sheet	1
A1	Inuvik Exterior Elevations	1
A2	Inuvik Snow Lip Remediation Details	1
A3	Inuvik Loading Dock Repair	1
A4	Hay River Ceiling Plan	1
A5	Inuvik Ceiling Plan	1

Project No:
R.015992.040 / .472 / .474 / .512
GOCB Bundled Projects
Inuvik & Hay River, NT

Section 00 01 10
TABLE OF CONTENTS
Page 2 of 2

DRAWING LIST (continued)

ELECTRICAL

E1	Electrical Legend	1
E2	Hay River Lighting Demolition Plan	1
E3	Inuvik Lighting Demolition Plan	1
E4	Hay River Lighting Renovation Plan	1
E5	Inuvik Lighting Renovation Plan	1

APPENDIX A –SAMPLE REPORT and COMMISSIONING FORMS

No. of Pages

Field Inspection Form	1
Soil Bearing Job Order Form	1
Inspection Report	2
Commissioning Issue Log	1
Lighting Commission Form	1

END OF SECTION



- SAFETY RAILING - STEEL 10" SECTIONS (TYPICAL 6 LOCATIONS)
- HEAVY DUTY 1 1/2" DIAMETER STEEL PIPE WITH WELDED 21" HIGH MIDRAIL
- POWDER COATED OSHA YELLOW FOR SAFETY
- SINGLE AND DOUBLE MOUNTING SOCKETS PROVIDED AS REQUIRED