

Solicitation No. - N° de l'invitation

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur

EA003-191148/A

001

PWD-010

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

R.089932.001

PWD-8-41088

AMENDMENT # 1
ADDENDUM NO. 1

**CP2 – Buildings Phase – DFO Facility –
Search and Rescue (SAR) Station, Old Perlican, NL**

EA003-191148/A

THE FOLLOWING AMENDMENT TO THE TENDER DOCUMENTS IS EFFECTIVE IMMEDIATELY.
THE AMENDMENT SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

ADDENDUM NO. 1

SPECIFICATIONS:

1. In specification Section 08 36 13 – Sectional Doors: 1.4.1 Wind Loads, replace 1.5kPA with “minimum of 1.0kPA”.

DRAWINGS:

1. On Drawing A103, Reference Detail 1 Room Schedule: Add following comment to Room # 117: “CT required to be installed at backsplash locations.”
2. On Drawing A103, Reference Detail 4 Equipment Schedule: Replace E:010 description with “Tackboard: factory framed, 1200mm high x 2500mm wide; 6mm thick cork surface laminated to 6mm hardboard backing; extruded aluminum frame to have satin anodized finish.”
3. On Drawing A501, Reference Detail 2: Replace portion of Detail 2 with revised Sketch Sk-1, attached herewith.
4. On Drawing S304: Reference Roof Plan: Delete reference to plywood deck.
5. Delete Drawing H105 and replace with revised Drawing H105 R1, attached herewith.
6. On Drawing E107: Electrical Equipment layout in Generator Room to be arranged as per Sketch ESK001, attached herewith.
7. On Drawings E106 And E703: Add Power connection for Gas Detection System in FRC Storage. Coordinate exact location of panel with mechanical. System to be powered from new 15A, 1P breaker on circuit F35 and wire to breaker using 2- #12 AWG RW90 copper plus 1 - #21 AWG copper bond in 21mm conduit. Include lock-on device for this breaker/circuit.

Solicitation No. - N° de l'invitation

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur

EA003-191148/A

001

PWD-010

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

R.089932.001

PWD-8-41088

8. On Drawing E602, Riser Diagrams: Delete references to Class A for fire alarm loops servicing The Ready Locker and FRC Building. Both sides of the loops to these exterior facilities are to be installed within the same underground conduit as per the drawing details.
9. On Drawing C101 and Appendix B - Geotechnical Investigation. Add the following clarification:
"Remove all existing materials from building footprint, and replace in a controlled manner."

By submission of its tender, the Tenderer confirms that it has read and understands the requirements expressed in all addenda and has included all costs of these requirements in its Total Tender Amount.

All other terms & conditions remain unchanged.
