

**The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.**

In Section 01 11 00 Part 1.12.3.1,

Add the following requirements to Remove, temporarily store, clean, alter to suit and reinstall water, rain and flow gauges at the North Pier:

1. The power of gauges can be interrupted up to maximum 4 hours at one time.
2. The flow gauge is VERY fragile, and must remain within 5-10 feet of its current location; or it requires re-calibration to the bed of the river. Contractor can install temporary pile to mount the gauge during the rehabilitation of the Rest Piers.
3. The Contractor MUST coordinate the temporary relocation of all gauges with Trent Severn Waterway Water Management.
4. PCA will provide a couple of manual gauges for the Contractor to install as backup.
5. The contractor shall set TWO (2) Temporary benchmarks as reference points prior to removing the existing benchmark on the center pier. This should be coordinated with PCA.
6. The contractor shall reinstate THREE (3) benchmarks, and coordinate with PCA to re-survey the three benchmarks to the correct Datum (GSC 1978).