

APPENDIX 1 - COMBINED PRICE FORM

- 1) The prices per unit will govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

LUMP SUM AMOUNT (LSA) Excluding applicable tax(s)

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(s) extra (PU)	Extended amount (EQ x PU) applicable tax(s) extra
1	02 41 16	Removal of Asphalt	Square Metre	3000		
2	02 41 16	Removal of Timber Piles	Each	30		
3	02 41 16	Removal of Concrete Deck	Square Metre	10000		
4	02 41 16	Removal of Concrete Deck Barrier Curb	Cubic Metre	2		
5	31 23 33.01	Excavation (underwater)	Linear Metre	2400		
6	31 62 16.13	Steel Sheet Pile Wall (Type 1)	Linear Metre	1440		
7	31 62 16.13	Steel Sheet Pile Wall (Type 2)	Linear Metre	700		
8	31 62 16.13	Steel Sheet Pile Anchor Wall	Linear Metre	720		
9	31 62 16.13	Walers, Splice Plates and Connections	Linear Metre	2850		
10	31 62 16.13	Tie Rods	Linear Metre	7400		
11	31 62 16.16	Closure Ends	Each	8		
12	35 59 14	Steel Cap for Sheet Pile Walls	Linear Metre	2120		
13	33 62 16.13	Toe Pins	Each	20		
14	31 32 19.01	Geotextile	Square Metre	4800		
15	03 30 00	Concrete in Deck	Cubic Metre	2400		
16	03 30 00	Concrete Overlay	Cubic Metre	210		

17	03 30 00	Concrete in Sidewalk	Cubic Metre	120		
18	03 30 00	Concrete in Curb	Linear Metre	190		
19	03 30 00	Grout for Voids	Cubic Metre	150		
20	03 30 00	Electrical Conduit (75 mm diameter)	Linear Metre	300		
21	31 05 16	Granular A	Tonne	29000		
22	31 05 16	Clear Stone Fill	Tonne	23000		
23	31 05 16	Stone for Toe Berm	Tonne	9000		
24	31 05 16	Stone for Core Fill	Tonne	31000		
25	31 05 16	Stone for Under Layer (200 to 300 kg)	Tonne	7000		
26	31 05 16	Armour Stone	Tonne	38000		
27	32 12 19	Asphalt Paving	Tonne	340		
28	35 59 14	Safety Ladders	Each	42		
29	33 11 00	Water Service Line	Linear Metre	205		
30	35 59 14	Chain Link Fencing (galvanized) 1.5m High	Linear Metre	120		
31	35 59 14	Chain Link Fencing (Black Vinyl) 1.8m High	Linear Metre	80		
32	04 03 07	Masonry Repointing	Square Metre	170		
33	04 03 07	Masonry Stone	Square Metre	10		
34	04 03 08	Grout for Voids in Masonry	Cubic Metre	5		
TOTAL EXTENDED AMOUNT (TEA)						
Excluding applicable tax(es)						

TOTAL BID AMOUNT (LSA +TEA)	
Excluding applicable tax(es)	

