

QUESTIONS AND ANSWERS

Q1. Has any exemption been applied for regarding in water work windows or are we expected to shut down operations for the restricted periods? If no exemption is allowed, has a more refined in water work window been defined? The guidelines posted online by MNR suggest work in water will only be allowed July 15th to Sept 15th. This would prohibit achieving the interim milestones set out in 0111 02 for completion of some sections by next March.

A1: The only timing window to be enforced for this project is no in-water work between March 15th through July 15th.

Q2. Section 01 52 00 Clause 1.8.1 states "Provide floating plant to install steel sheet piling and installation of aggregate materials for rock berms." This contradicts the Steel Sheet Piles specification which states in 31 62 16.13 clause 3.1.3 "Provide access for sheet piling operations, including but not limited to barges." Is it the intent that sheet piling may be completed from land for some sections of wall, or must all sheet piling be completed from barge?

A2: Section 31 62 16.13 Part 3.1.3 is deleted and replaced with the following: "Provide access for sheet piling operations, including but not limited to barges."