

LEGEND

- ⊙ POWER POLE
- FUEL LINE
- - - POWER LINES
- - - WATER LINES
- ▨ EXISTING BUILDING
- B.H.#1 ⊕ BORE HOLE
- ⊕ SITE BM SITE BENCH MARK
- + 2.308 EXISTING ELEVATIONS
- + -1.775 SOUNDINGS



0	ISSUED FOR TENDER	08/14/2018
revisions		date


project RECONSTRUCTION
BOAT PEN 414A & 414B
NORTH LAKE HARBOUR
KING'S CO. PEI

drawing NEW WHARF
SITE PLAN

designed N.L., P.ENG	conçu
date 2 August 2018	
drown NL	dessiné
date 2 August 2018	
approved	approuvé
date	
Tender	Soumission

PWSSC Project Manager Administrateur de projets TPSSC
project number no. du projet
R.094623.001

drawing no. no. du dessin
M3 OF 8



PLAN-WHARF 414A & 414B RECONSTRUCTION

SCALE : 1:100
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

NOTE A:
1. REMOVE AND REINSTATE EXISTING SITE SERVICE & OTHER COMPONENTS SECURED TO WHARF AS NECESSARY TO SAFELY EXECUTE WORK
2. NEW CLEATS TO BE SPACED @ 7m (ALLOW FOR 19 CLEATS).
3. NEW LADDERS TO BE SPACED @ 10m (ALLOW FOR 16 LADDERS).
4. VERIFY FINAL LOCATION OF SERVICES, CLEATS, LADDERS, ETC. WITH DEPARTMENTAL REPRESENTATIVE.

NOTE B:
WHARF STRUCTURE IS DESIGNED FOR MS200 TRUCK LOADING

AXLE LOAD	40KN	160KN	160KN
WHEEL LOADS	20KN	80KN	80KN

4.24m VARIES 4.25m to 9.25m