






- NOTES**
1. REMOVE FUEL PUMP, FUEL LINES, ELECTRICAL & WATER SERVICES AND OTHER SITE ITEMS. STORE ON SITE AT A LOCATION AS DIRECTED BY DEPARTMENT REPRESENTATIVE & HA.
 2. REMOVE & DISPOSE OF EXISTING CONCRETE DECK, FENDER & OTHER ASSOCIATED ITEMS.
 3. REMOVE & DISPOSE OF CRIBWORK MEMBERS THAT ARE DESIGNATED TO BE REMOVED TO ELEVATION AS INDICATED.
 4. EXERCISE CAUTION & DO NOT DISTURB WHARF STRUCTURE 403. IF REQUIRED, EXECUTE REMOVAL & RECONSTRUCTION IN PHASES & PROVIDE TEMPORARY SUPPORT.
 5. RECONSTRUCT CRIBWORK USING SIMILAR MEMBER SIZES AND ARRANGEMENT. INSTALL BALLAST, FILTER FABRIC, GRAVEL, CONCRETE DECK, FENDERS, CURBING AS INDICATED.
 6. FOR BIDDING PURPOSE ALLOW REMOVAL TO LNT.
 7. DEPARTMENT REPRESENTATIVE TO ASSESS CONDITIONS OF CRIBWORK AFTER FENDERS AND DECK REMOVAL. PARTIAL REPAIRS MAY BE REQUIRED IN LIEU OF REPLACEMENT OF ENTIRE UPPER CRIBWORK STRUCTURE.



0	ISSUED FOR TENDER	08/14/2018
revisions		date
project	RECONSTRUCTION BOAT PEN 414A & 414B NORTH LAKE HARBOUR KING'S CO. PEI	

NEW WHARF SECTIONS AND DETAILS

designed N.L., P.ENG	conçu
date 2 August 2018	
drawn NL	dessiné
date 2 August 2018	
approved	approuvé
date	
Tender	Soumission

IPWSC Project Manager	Administrateur de projets TPSCG
project number	no. du projet
R.094623.001	
drawing no.	no. du dessin