

Marginal Wharf Reconstruction  
Foxtrap, NL  
P/N: 721924

Page 1  
2018-03-31

PART 1 - GENERAL

1.1 RELATED  
SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 21 - Construction/Demolition  
Waste Management And Disposal.
- .3 Section 32 12 16 - Asphalt Paving.

1.2 REFERENCES

- .1 American Society for Testing and Materials  
(ASTM)
  - .1 ASTM D4791-05, Standard Test Method  
for Flat Particles, Elongated Particles,  
or Flat and Elongated Particles in Coarse  
Aggregate.

1.3 SAMPLES

- .1 Submit samples in accordance with Section  
01 33 00 - Submittal Procedures.
- .2 Allow continual sampling by Departmental  
Representative during production.
- .3 Provide Departmental Representative with  
access to source and processed material  
for sampling.
- .4 Install sampling facilities at discharge  
end of production conveyor, to allow  
Departmental Representative to obtain  
representative samples of items being  
produced. Stop conveyor belt when  
requested by Departmental Representative  
to permit full cross section sampling.
- .5 Pay cost of sampling and testing of  
aggregates which fail to meet specified  
requirements.

1.4 WASTE  
MANAGEMENT AND  
DISPOSAL

- .1 Divert unused granular materials from  
landfill to local quarry facility as  
approved by Departmental Representative.

Marginal Wharf Reconstruction  
Foxtrap, NL  
P/N: 721924

Page 2  
2018-03-31

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- .1 Aggregate quality: sound, hard, durable material free from soft, thin, elongated or laminated particles, organic material, clay lumps or minerals, or other substances that would act in deleterious manner for use intended.
- .2 Flat and elongated particles of coarse aggregate: to ASTM D4791.
  - .1 Greatest dimension to exceed five times least dimension.
- .3 Fine aggregates satisfying requirements of applicable section to be one, or blend of following:
  - .1 Natural sand.
  - .2 Manufactured sand.
  - .3 Screenings produced in crushing of quarried rock, boulders, gravel or slag.
- .4 Coarse aggregates satisfying requirements of applicable section to be one of or blend of following:
  - .1 Crushed rock.
  - .2 Gravel and crushed gravel composed of naturally formed particles of stone.
  - .3 Light weight aggregate, including slag and expanded shale.

### 2.2 SOURCE QUALITY CONTROL

- .1 Inform Departmental Representative of proposed source of aggregates and provide access for sampling at least 2 weeks prior to commencing production.
- .2 If, in opinion of Departmental Representative, materials from proposed source do not meet, or cannot reasonably be processed to meet, specified requirements, locate an alternative source or demonstrate that material from source

Marginal Wharf Reconstruction  
Foxtrap, NL  
P/N: 721924

Page 3  
2018-03-31

in question can be processed to meet specified requirements.

- .3 Advise Departmental Representative 2 weeks in advance of proposed change of material source.
- .4 Acceptance of material at source does not preclude future rejection if it fails to conform to requirements specified, lacks uniformity, or if its field performance is found to be unsatisfactory.

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- .1 Aggregate source preparation
  - .1 Prior to excavating materials for aggregate production, clear and grub area to be worked, and strip unsuitable surface materials. Dispose of cleared, grubbed and unsuitable materials as directed by Departmental Representative.
  - .2 Where clearing is required, leave screen of trees between cleared area and roadways as directed.
  - .3 Clear, grub and strip area ahead of quarrying or excavating operation sufficient to prevent contamination of aggregate by deleterious materials.
  - .4 When excavation is completed dress sides of excavation to nominal 1.5:1 slope, and provide drains or ditches as required to prevent surface standing water.
  - .5 Trim off and dress slopes of waste material piles and leave site in neat condition.
- .2 Processing
  - .1 Process aggregate uniformly using methods that prevent contamination,

Marginal Wharf Reconstruction  
Foxtrap, NL  
P/N: 721924

Page 4  
2018-03-31

segregation and degradation.

.2 Blend aggregates, if required, to obtain gradation requirements, percentage of crushed particles, or particle shapes, as specified. Use methods and equipment approved by Departmental Representative.

.3 Wash aggregates, if required to meet specifications. Use only equipment approved by Departmental Representative.

.4 When operating in stratified deposits use excavation equipment and methods that produce uniform, homogeneous aggregate.

.3 Handling

.1 Handle and transport aggregates to avoid segregation, contamination and degradation.

.4 Stockpiling

.1 Stockpile aggregates on site in locations as indicated unless directed otherwise by Departmental Representative. Do not stockpile on completed pavement surfaces.

.2 Stockpile aggregates in sufficient quantities to meet Project schedules.

.3 Stockpiling sites to be level, well drained, and of adequate bearing capacity and stability to support stockpiled materials and handling equipment.

.4 Except where stockpiled on acceptably stabilized areas, provide compacted sand base not less than 300 mm in depth to prevent contamination of aggregate.

Stockpile aggregates on ground but do not incorporate bottom 300 mm of pile into Work.

.5 Separate different aggregates by strong, full depth bulkheads, or stockpile far enough apart to prevent intermixing.

.6 Do not use intermixed or contaminated materials. Remove and dispose of rejected materials as directed by Departmental Representative within 48 hours of

Marginal Wharf Reconstruction  
Foxtrap, NL  
P/N: 721924

Page 5  
2018-03-31

rejection.

.7 Stockpile materials in uniform layers of thickness as follows:

.1 Max 1.5 m for coarse aggregate and base course materials.

.2 Max 1.5 m for fine aggregate and sub-base materials.

.3 Max 1.5 m for other materials.

.8 Uniformly spot-dump aggregates delivered to stockpile in trucks and build up stockpile as specified.

.9 Do not cone piles or spill material over edges of piles.

.10 Do not use conveying stackers.

.11 During winter operations, prevent ice and snow from becoming mixed into stockpile or in material being removed from stockpile.

### 3.2 CLEANING

.1 Leave aggregate stockpile site in tidy, well drained condition, free of standing surface water.

.2 Leave any unused aggregates in neat compact stockpiles as directed by Departmental Representative.

.3 For temporary or permanent abandonment of aggregate source, restore source to condition meeting requirements of authority having jurisdiction.