

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Removal of the existing wharf, slipway and boat storage area, as noted on the drawings. Note that creosote timber is present in the infrastructure to be removed. Assume that all demolition debris is to be disposed of at Robin Hood Bay in St. John's, NL.
 - .2 Relocation of the existing floating docks and floating dock gangways, as noted on the drawings.
 - .3 Temporary removal and reinstallation of the waterline running along the face of the existing wharf, as noted on the drawings. Divers will be required for this work.
 - .4 All temporary shoring measures to protect the existing site infrastructure and buildings during demolition and new work activities.

1.2 GENERAL
REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately

Marginal Wharf Reconstruction
Foxtrap, NL
P/N: 721924

Page 2
2018-03-31

replace or make repairs to approval of and
at no additional cost to Canada.

- .2 Place a floating boom around entire
demolition site to prevent loss of any
materials. If required by DFO Habitat, place
a silt curtain around the work area and
maintain throughout the period of
construction.
- .3 Remove all floating debris from water on a
routine and timely basis.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental
Representative objects designated for
removal.
- .2 Locate and protect utility lines. Preserve
in operating condition active utilities
traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and
objects specified for removal.
- .2 Do not disturb adjacent work designated to
remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials
designated to be reused, will become property
of contractor and will be removed from site
and disposed of to satisfaction of

Marginal Wharf Reconstruction
Foxtrap, NL
P/N: 721924

Page 3
2018-03-31

Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.

- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.