

**ROYAL CANADIAN MOUNTED POLICE
DEPOT DIVISION
REGINA, SASKATCHEWAN**

**Supply and Install Rubber Flooring
Project #828729**

Supply all labour, material, tools, and equipment required to supply and install rubber flooring in the IARD training building at the RCMP Academy, Depot Division in Regina, Saskatchewan without the disruption of RCMP employees during normal working hours (7 00 to 19 00 hrs).

SCOPE OF WORK

1. The intent of this project is to install rubber floor matting on the finished floor of a fabric structure measuring approximately 100ft wide x 220ft long.
2. Slope of floor should be 2% and if the finished floor is not at this, the contractor will need to adjust the floor to meet the installation needs.
3. The contractor will need to confirm that there is 95% standard proctor compaction in the existing floor, and if not they will need to bring additional base to achieve 95% compaction. Quality assurance testing will need to be arranged by the contractor to confirm compaction.
4. A filter fabric is necessary prior to the installation of the rubber floor matting. This will have to be supplied and installed by Contractor. Fabric will be commercial quality and for long term use. Approval of filter fabric being used must be done prior to solicitation closing date.
5. Rubber floor matting will need to be purchased for this project, the specifications of this flooring are as follows:
 - LongHorn Button Top mats
 - 100% recycled rubber mat
 - ¾" double vulcanized rubber
 - Slip resistant even when wet
 - Large button Ultimate traction design on one side, smooth finish on other side
 - Insulating from cold
 - Mat size 4 feet x 6 feet

Approval of rubber floor matting being used must be done prior to solicitation closing date.