

**SPECIFICATIONS FOR
FLOAT WHARF REPLACEMENT
HAY RIVER, NT**



Department of Fisheries & Oceans
Small Craft Harbours Branch
Winnipeg, Manitoba

October 2018

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
01 11 05 – General Instructions	3
01 35 29 – Health and Safety Requirements	9
01 35 43 – Environmental Procedures	12
01 45 00 – Quality Control	15
01 77 00 – Closeout Procedures.....	17
02 41 13 – Selective Site Demolition.....	19
05 50 00 – Metal Fabrications	21
06 05 73 – Wood Treatment	24
35 59 11 – Float Wharf Fabrication.....	26

END OF SECTION

01 11 05 – GENERAL INSTRUCTIONS

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No measurement will be made under this Section.

1.2 DESCRIPTION OF WORK

- .1 The work site described in this specification is located in Hay River, NT. See Location Plan on Drawing C-1.

The Hay River harbour is located on the east channel of the Hay River on Vale Island in the community of Hay River, NT. The community is accessible year round by road on the Mackenzie Highway and Hay River Highway.

- .2 The work under this contract covers:
 - .1 Supply and install eight (8) new 2.438m x 6.706m float wharves.
 - .2 Repair and install eight (8) existing 1.829m x 6.706m float wharves.
 - .3 Supply and install four (4) new-float-to-SSP (Steel Sheet Pile) connections.
 - .4 Remove, salvage, and re-install 11.35 lineal metres of existing horizontal timber fenders.
 - .5 Remove and dispose of one (1) 4.8 metre long section of existing horizontal timber fenders.
 - .6 Repair and install one (1) existing float access stairway.
 - .7 Supply and install one (1) new float access stairway.
 - .8 Repair and install four (4) existing float-to-SSP connections.
 - .9 Pick-up and install fourteen (14) float transition plates on new and repaired float wharves.
 - .10 Remove and dispose of one (1) existing angle bracket

- .3 The work to be done by the Contractor under this Contract shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, insurance, and all things necessary for and incidental to the satisfactory performance and completion of all work as specified herein. All work to be done in accordance with details shown on the accompanying plans as specified herein.

1.3 DEFINITIONS

- .1 The word "provide" means "supply and install".
- .2 For purposes of this contract, "Departmental Representative", "Architect/Engineer" and "Engineer" shall have the same meaning.

1.4 WORK SCHEDULE

- .1 Provide within 10 working days after Contract award, schedule showing anticipated progress stages and final completion of work within time period required by contract documents.

- .2 Provide sufficient details in schedule to clearly illustrate entire instrumentation plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones.
- .3 As a minimum, work schedule to be prepared and submitted indicating work activities, tasks and other projects elements, their anticipated durations and planned dates for achieving key activities and major project milestones. It shall include sufficient details and supported by narratives to demonstrate a reasonable plan for completion of project within designated time.
- .4 Submit schedule updates on a minimum monthly basis and more often, when requested by Engineer. Provide a narrative explanation of necessary changes and schedule revisions at each update. Take all necessary measures to complete work within approved time.
- .5 Work under this contract is to be performed to completion in a timely manner. Commence planning and preparatory work immediately upon receipt of official notification of acceptance of Contract and schedule the work so that the project will be complete by the following dates:
 - .1 No work on site to be performed the week of and during the Polar Pond Hockey Tournament in **March 2019**. Dates to be confirmed with SCH.
 - .2 The work in the contract shall be completed by **March 31, 2019**, except as noted in 1.4.5.3 below.
 - .3 Float wharves not to be installed on top of ice. Installation of float wharves, stairways, and float-to-SSP connections must be completed after all ice is off the Hay River and be completed by **June 15, 2019**.
- .6 Work sequence:
 - .1 Before work is undertaken, ensure that all materials and trades required are available to finish work in as short a period as possible.
 - .2 No area to be renovated shall be placed out of service until it is confirmed that there shall be no need to stop the work waiting for receipt of materials, equipment or labour.

1.5 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.

1.6 FEES, PERMITS AND CERTIFICATES

- .1 Provide authorities having jurisdiction with information requested.
- .2 Pay fees and obtain certificates and work permits required.
- .3 Furnish certificates and permits when requested.

1.7 MEASUREMENT FOR PAYMENT

- .1 Notify Engineer sufficiently in advance of operations to permit required measurements for payment.
- .2 Submit to Engineer, at least 14 days before Information for first application for payment, cost breakdown, Progress Payment in detail as directed by Engineer, for parts of Work, aggregating total amount of Contract Price, so as to facilitate evaluation of applications

for payment. After approval by Engineer, cost breakdown will be used as basis for progress payments.

1.8 INTERPRETATION OF DOCUMENTS

- .1 In the event of discrepancies or conflicts in interpreting the Plans (drawings) and Specifications, Specifications take precedence over drawings bound with specifications.
- .2 Drawings and specifications are complementary. When work is shown or mentioned on the drawings but is not indicated in the specifications, or when work is indicated in the specifications but is not shown or mentioned on the drawings, it shall nevertheless be included in the Contract.
- .3 The sub-division of the Specification into sections, identified by title and number, is for convenience only and does not modify the singularity of the document, nor does it operate to make or imply that the Engineer is an arbiter to establish the limits or extent of contract between Contractor and Subcontractors or to determine the limits or extents of work that may be decided by trade unions or contractors' organizations. Extras to the Contract will not be considered on the grounds of differences in interpretation of the Specification and/or Drawings as to which trade performs the work.
- .4 Do not scale off drawings.

1.9 CONTRACTOR'S USE OF SITE

- .1 Co-ordinate use of premises under direction of the Engineer.
- .2 Do not unreasonably encumber the site with materials and equipment.
- .3 Assume full responsibility for protection and safekeeping of products under this Contract.
- .4 Move stored products or equipment which interfere with operations of Engineer or other harbour users.
- .5 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .6 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .7 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Engineer.
- .8 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

1.10 EXISTING SERVICES

- .1 Notify Engineer and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Engineer 72 hours notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions.
- .3 Establish location and extent of service lines in area of work before starting Work. Notify Engineer of findings.

- .4 Submit schedule to and obtain approval from Engineer for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .5 Where unknown services are encountered, immediately advise Engineer and confirm findings in writing.
- .6 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .7 Record locations of maintained, re-routed and abandoned service lines.

1.11 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 Change Orders.
 - .6 Other Modifications to Contract.
 - .7 Copy of Approved Work Schedule.
 - .8 Health and Safety Plan and Other Safety Related Documents.
 - .9 Other documents as specified.

1.12 CONTRACT METHOD

- .1 Construct Work under a combined price contract. All costs for work not specifically identified as a unit price item shall be included in the lump sum arrangement.

1.13 CODES AND STANDARDS

- .1 Perform work in accordance with latest editions of National Building Code of Canada (NBC) and any other code of provincial or local application provided that in any case of conflict or discrepancy, the more stringent requirements shall apply.
- .2 Work to meet or exceed requirements of contract documents, specified standards, codes and referenced documents.

1.14 PROJECT MEETINGS

- .1 Engineer will arrange project meetings and assume responsibility for setting times and recording and distributing minutes.

1.15 SETTING OUT OF WORK

- .1 Engineer will provide only those survey control points and set such stakes as necessary to define general location, alignment and elevations of work. Give engineer reasonable notice of requirements for such control points and stakes.
- .2 Set grades and lay out work in detail from control points and grades established by Engineer.
- .3 Provide devices needed to lay out and construct work.
- .4 Supply such devices needed to lay out and construct work.

- .5 Supply such devices as straight edges and templates required to facilitate Engineer's inspection of work.
- .6 Supply stakes and other survey markers required for laying out work.

1.16 ADDITIONAL DRAWINGS

- .1 Engineer may furnish additional drawings for clarification. These additional drawings have same meaning and intent as if they were included with plans referred to in Contract documents.
- .2 When additional drawings and instructions are required by the Contractor, provide reasonable notice in writing to the Engineer in advance of the date they are required.

1.17 EXAMINATION

- .1 Before submitting tender, examine existing conditions and determine conditions affecting work.
- .2 Obtain all information which may be necessary for proper execution of Contract.

1.18 SITE INSPECTION

- .1 The submission of a tender is deemed to be a confirmation of the fact that the Tenderer has inspected the site and is fully conversant with all the conditions under which the work is to be carried out.

1.19 MATERIAL AND EQUIPMENT

- .1 Use new products unless otherwise specified.
- .2 Deliver and store material and equipment to manufacturer's instructions with manufacturer's labels and seals intact.
- .3 When material or equipment specified by standard performance specifications, upon request of Departmental Representative, obtain from manufacturer an independent testing laboratory report, stating that material or equipment meets or exceeds specified requirements.

1.20 SECURING WORK AREA

- .1 Secure the work areas in each stage in an approved manner. This includes fencing or barricades to prevent public access to any areas where construction activities occur and construction materials are stored.

1.21 VEHICLE AND PEDESTRIAN PROTECTION

- .1 Provide snow fencing, wooden barriers, or other approved barriers to prevent vehicles and pedestrians from accessing the site during construction.
- .2 Contractor shall provide appropriate signage for vehicle and pedestrian protection.
- .3 All barriers shall include delineation and reflectors to stand out at nightfall.

1.22 DRAWINGS

- .1 The following drawings are to be read in conjunction with this specification:
 - .1 C-1 Float Wharf Replacement – Plan and Construction Details

- .2 C-2 Float Wharf Replacement – Existing 1.829m x 6.706m Float Wharf and Mooring Details
- .3 C-3 Float Wharf Replacement – 2.438m x 6.706m Float Wharf Construction Details
- .4 C-4 Float Wharf Replacement – Float Wharf Hinge Connection Details
- .5 C-5 Float Wharf Replacement – Float-To-SSP Anchors - Construction Details

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.
- .1

END OF SECTION

01 35 29 – HEALTH AND SAFETY REQUIREMENTS

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No measurement will be made under this Section.

1.2 REFERENCES

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .3 Province or Territory having jurisdiction:
 - .1 The Workers Compensation Act (latest edition).

1.3 SUBMITTALS

- .1 Submit site-specific Health and Safety Plan: Within 10 days after date of Notice to Proceed and prior to commencement of Work.
- .2 Submit copies of incident and accident reports to Engineer.
- .3 Submit WHMIS MSDS – Material Safety Data Sheets to Engineer.
- .4 Engineer will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor after receipt of plan. Revise plan as appropriate and resubmit plan to Engineer within 5 days after receipt of comments from Engineer.
- .5 Engineer's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .6 On-site Contingency and Emergency Response Plan: address standard operating procedures to be implemented during emergency situations.

1.4 FILING OF NOTICE

- .1 File Notice of Project with Provincial authorities prior to beginning of Work.

1.5 SAFETY ASSESSMENT

- .1 Perform site specific safety hazard assessment related to project.

1.6 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Observe and enforce construction safety measures required by Canadian Construction Safety Code, Provincial Government, Worker's Compensation Board and municipal statutes and authorities.
- .3 In the event of a conflict between any provisions of above authorities having the most stringent provision will apply.

1.7 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.8 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of the Province having jurisdiction and advise Engineer verbally and in writing.

1.9 HEALTH AND SAFETY CO-ORDINATOR

- .1 Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must:
 - .1 Have site-related working experience specific to activities associated with dock reconstruction at an active harbour site.
 - .2 Have working knowledge of occupational safety and health regulations.
 - .3 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work.
 - .4 Be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan.
 - .5 Be on site during execution of Work.

1.10 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative verbally and in writing.

1.11 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

01 35 43 – ENVIRONMENTAL PROCEDURES

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No separate measurement will be for work of this section. Work is incidental to the project cost.

1.2 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.3 DRAINAGE

- .1 Provide temporary drainage and pumping required to keep excavations and site free from water.
- .2 Ensure pumped water into waterways, sewer or drainage systems is free of suspended materials.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

1.4 WORK ADJACENT TO WATERWAYS

- .1 Construction equipment will enter and leave the river at such a location and in such a manner that disturbance to the lakeshore is minimized.
- .2 Construction equipment may not enter the river unless the river is frozen. If construction equipment will be located on the frozen surface of the river, it will be removed from the river each night if the on-ice component of the projects spans more than one day.
- .3 No construction debris from work activities will be allowed to enter the river. The work site must be cleaned daily. Every effort will be made to minimize the introduction of sediment to the lake during work activities.
- .4 Any sediment tracked onto the ice during the project must be cleaned off at the end of the project.
- .5 Do not use waterway beds for borrow material.
- .6 Waterways to be free of excavated fill, waste material and debris.
- .7 Design and construct temporary crossings to minimize erosion to waterways.
- .8 Do not skid logs or construction materials across waterways.
- .9 Avoid damage to shoreline.
- .10 Supply, install, and maintain approved erosion control blankets to unprotected slopes until revegetation is established.
- .11 Any impacts below ordinary high water mark that are not shown on the site plan are not permitted without written approval from the Engineer. Up to 30 days may be required for approval.
- .12 Reclaim and restore disturbed areas to previous or better condition.

- .13 Areas used for stockpiling construction materials, including fill or other equipment storage will be well back from the edge of the water body and, if possible, in areas which have already been disturbed or are devoid of vegetation.
- .14 All required machinery should be supplied with appropriate spill containment kits as a precaution in the event of accidental fuel spills or hydraulic leaks. Additional kits should be available on site with the capacity to contain any spills of deleterious substances that may be reasonably expected to occur. Contractors should ensure that all personnel are familiar with the spill kits.
- .15 The Contractor shall report spills of fuels or other contaminants to the Engineer.
- .16 The Contractor shall not remove, destroy or disturb species pursuant to Provincial Threatened Endangered and Extirpated Species regulation, or species listed in the federal Species at Risk Act.
- .17 The Contractor shall not disturb migratory bird nests.

1.5 POLLUTION CONTROL

- .1 Control emissions from equipment and plant to local authorities' emission requirements.
- .2 Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area.
- .3 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.
- .4 Locate temporary fuel storage 100 metres from shore and comply with Provincial or Territorial Environmental Legislation.
- .5 Refueling, servicing, or cleaning of equipment on ice or within 100 metres of shore is prohibited. Contractor to ensure all equipment operating on project is free of external fluid leaks, grease, oil, and mud.
- .6 Contractor to contain all oil leaks from equipment working adjacent to waterways.
- .7 No maintenance of vehicles or equipment in construction areas.
- .8 Use drip pans to catch leaking oil from compressors, pumps, etc.
- .9 Keep an emergency spill kit for in-water use on site during construction.

1.6 DISPOSAL OF WASTES:

- .1 Do not bury rubbish and waste materials on site.
- .2 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways. Hazardous wastes including fuels, oils and lubricants to be disposed of by a licensed hazardous waste carrier/handler in accordance with Provincial Environment Legislation.
- .3 Collect all rubbish and waste material and dispose of in accordance with applicable governing authorities.
- .4 Do not allow debris of any type to enter waterway.

1.7 PLANT PROTECTION

- .1 Protect trees and plants on site and adjacent properties.

- .2 Avoid disturbance of topsoil and vegetation unless otherwise specified. Contractor is responsible to restore all impacted areas to original state.
- .3 The Contractor shall revegetate soil in areas exposed by construction with vegetation species native to the area. These areas shall be revegetated as quickly as possible following construction to prevent soil erosion and establishment of noxious weeds.

1.8 PRODUCTS

1.9 NOT USED

- .1 Not Used.

Part 2 Execution

2.1 NOT USED

- .1 Not Used.

END OF SECTION

01 45 00 – QUALITY CONTROL

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No measurement will be made under this Section.

1.2 INSPECTION

- .1 Allow Engineer access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Engineer.
- .3 Engineer will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction.

1.3 INDEPENDENT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies may be engaged by Engineer for purpose of inspecting and/or testing portions of Work.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Engineer at no cost to. Pay costs for retesting and re-inspection.

1.4 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.5 PROCEDURES

- .1 Notify Engineer in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.6 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Engineer as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Engineer it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Engineer.

1.7 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.

1.8 MILL TESTS

- .1 Submit mill test certificates as requested.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

01 77 00 – CLOSEOUT PROCEDURES

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No measurement will be made under this Section.

1.2 ADMINISTRATIVE REQUIREMENTS

- .1 Acceptance of Work Procedures:
 - .1 Contractor's Inspection: Contractor to conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .2 Final Inspection:
 - .1 When completion tasks are done, request final inspection of Work by Engineer.
 - .2 When Work incomplete according to Engineer, complete outstanding items and request re-inspection.
 - .3 Final Payment:
 - .1 When Engineer considers final deficiencies and defects corrected and requirements of Contract met, make application for final payment.
 - .4 Payment of Holdback: after issuance of Certificate of Substantial Performance of Work, submit application for payment of holdback amount in accordance with contractual agreement.

1.3 FINAL CLEANING

- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

1.4 RECORD DRAWINGS

- .1 Maintain project “as-built” record drawings and record accurately significant deviations from Contract documents caused by site conditions and changes ordered by Engineer.
- .2 Mark “as-built” changes in red coloured ink.
- .3 Record the following information:
 - .1 Field changes of dimension and detail.
 - .2 Changes made by Change Order or Field Order.
- .4 At completion of project and prior to final inspection, neatly transfer “as-built” notations to second set and submit both sets to Engineer.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

02 41 13 – SELECTIVE SITE DEMOLITION

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 Payment for mobilization and demobilization shall be included in the lump sum amount for the project and shall include all works required to:
 - .1 Mobilize equipment, materials, tools, supplies, labour and supervisors.
 - .2 Insurance(s) required for the duration of construction.
 - .3 Fees, certificates and work permits.
 - .4 Temporary construction facilities.
 - .5 Signage.
 - .6 Securing work and storage areas.
 - .7 Vehicle and pedestrian protection.
 - .8 Daily site cleaning, and
 - .9 Demobilization of aforementioned items upon completion of construction.
- .2 Removal and disposal of one (1) existing angle bracket to be included in the lump sum costs for the project.
- .3 Removal and disposal of existing clip angles for horizontal timber fenders to be included in the lump sum costs for the project.
- .4 Removal and disposal of one (1) 4.8 metre long section of existing horizontal timber fenders to be included in the lump sum costs for the project.

1.2 DELIVERY, STORAGE AND HANDLING

- .1 Storage and Protection.
 - .1 Protect existing items designated to remain and items designated for salvage. In event of damage to such items, immediately replace or make repairs to approval of Engineer and at no cost to Engineer.
 - .2 Remove and store materials to be salvaged, in manner to prevent damage.
 - .3 Store and protect in accordance with requirements for maximum preservation of material.
 - .4 Handle salvaged materials as new materials.

1.3 SITE CONDITIONS

- .1 Site Environmental Requirements:
 - .1 Ensure that selective demolition work does not adversely affect adjacent watercourses, groundwater and wildlife, or contribute to excess air and noise pollution.
 - .2 Ensure proper disposal procedures are maintained throughout the project.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 PREPARATION

- .1 Inspect site and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

3.2 REMOVAL OPERATIONS

- .1 Remove items as indicated.
- .2 Do not disturb items designated to remain in place.

3.3 REMOVAL FROM SITE

- .1 Dispose of materials not designated for salvage or re-use in work, off-site at location acceptable to Engineer.

3.4 RESTORATION

- .1 Remove debris, trim surfaces and leave work site clean, upon completion of Work.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

END OF SECTION

05 50 00 – METAL FABRICATIONS

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 Float wharf brackets, backing plates, bollards, mooring cleats, and any required fasteners shall be incidental to the cost of the Timber Float Wharves – Section 35 59 11.
- .2 Pick-up and installation of fourteen (14) float transition plates from SCH to be included in the lump sum costs for the project.
- .3 New float access stairway to be paid for per unit supplied and delivered to the jobsite.
- .4 Installation of the new float access stairway to be included in the lump sum amount, including any brackets and fasteners.
- .5 Repair and installation of one (1) existing float access stairway to be included in the lump sum costs for the project.
- .6 Removal, salvage, and re-installation of 11.35 lineal metres of existing horizontal timber fenders to be included in the lump sum costs for the project including any clip angles and fasteners.
- .7 New float-to-SSP connections to be paid for per unit supplied and delivered to the jobsite.
- .8 Installation of the new float-to-SSP connections to be included in the lump sum amount, including any hinges and fasteners.
- .9 Repair and installation of four (4) existing float-to-SSP connections to be included in the lump sum costs for the project including any hinges, fasteners, and the removal of existing hinges.

1.2 REFERENCES

- .1 ASTM International
 - .1 ASTM A53/A53M-07, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless.
 - .2 ASTM A307[07b, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
- .2 CSA International
 - .1 CSA G40.20/G40.21-04(R2009), General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.
 - .2 CAN/CSA G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
 - .3 CSA S16-09, Design of Steel Structures.
 - .4 CSA W48-06, Filler Metals and Allied Materials for Metal Arc Welding (Developed in co-operation with the Canadian Welding Bureau).
 - .5 CSA W59-M03(R2008), Welded Steel Construction (Metal Arc Welding) Metric.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Shop Drawings:
 - .1 Submit drawings indicating materials, core thicknesses, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details, and accessories.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Storage and Handling Requirements:
 - .1 Store materials off ground in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 MATERIALS

- .1 Steel sections and plates: to CSA G40.20/G40.21, Grade 350W.
- .2 Welding materials: to CSA W59.
- .3 Welding electrodes: to CSA W48 Series.
- .4 Bolts and anchor bolts: to ASTM A307, galvanized where exposed to weather.

2.2 FABRICATION

- .1 Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
- .2 Where possible, fit and shop assemble work, ready for erection.
- .3 Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.

2.3 FINISHES

- .1 Galvanizing: hot dipped galvanizing with zinc coating 600 g/m² to CAN/CSA-G164.

2.4 SHOP PAINTING

- .1 Primer: VOC limit 250 g/L maximum to GS-11 CCD-047a CCD-048.
- .2 Apply one shop coat of primer to metal items, with exception of galvanized or concrete encased items.
- .3 Use primer unadulterated, as prepared by manufacturer. Paint on dry surfaces, free from rust, scale, grease. Do not paint when temperature is lower than 7 degrees C.
- .4 Clean surfaces to be field welded; do not paint.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify conditions of substrates previously installed under other Sections or Contracts are acceptable for metal fabrications installation in accordance with manufacturer's written instructions.

3.2 ERECTION

- .1 Do welding work in accordance with CSA W59 unless specified otherwise.
- .2 Erect metalwork square, plumb, straight, and true, accurately fitted, with tight joints and intersections.
- .3 Provide suitable means of anchorage acceptable to Engineer such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles.
- .4 Exposed fastening devices to be hot dipped galvanized and /or shall be compatible with material through which they pass.
- .5 Make field connections with bolts to CSA S16.
- .6 Touch-up field welds, bolts and burnt or scratched surfaces with primer;
 - .1 Primer: maximum VOC limit 250 g/L to GS-11.
- .7 Touch-up galvanized surfaces with zinc rich primer where burned by field welding.
 - .1 Primer: maximum VOC limit 250 g/L to GS-11.

3.3 CLEANING

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris.
- .2 Remove waste off site at regular intervals for disposal.
- .3 Do not burn waste materials on site. Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 When Work is substantially completed, remove surplus products, tools, and equipment not required to complete remaining work.

3.4 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by metal fabrications installation.

END OF SECTION

06 05 73 – WOOD TREATMENT

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 No measurement will be made under this Section.

1.2 RELATED SECTIONS

- .1 Section 35 59 11 – Float Wharf Fabrication.

1.3 REFERENCES

- .1 American Wood-Preservers' Association (AWPA)
 - .1 AWWA M2-01, Standard for Inspection of Treated Wood Products.
 - .2 AWWA M4-06, Standard for the Care of Preservative-Treated Wood Products.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA O80 Series-97(R2002) - O80S2-05, Wood Preservation.
 - .2 CSA O80.20-1.1-M97(R2002), This Standard applies to the fire-retardant treatment of lumber by pressure processes..
 - .3 CSA O80.27-1.1-M97(R2002), This Standard covers the fire-retardant treatment of Douglas Fir, hardwood, softwood, and Poplar plywood by pressure processes.
 - .4 CSA O80.201-M89, This Standard covers hydrocarbon solvents for preparing solutions of preservatives.
 - .5 CSA O322-02, Procedure for Certification of Pressure-Treated Wood Materials for Use in Preserved Wood Foundations.

Part 2 Products

2.1 MATERIALS

- .1 Preservative treatment by a pressure process to CSA O80 Series.

Part 3 Execution

3.1 APPLICATION: PRESERVATIVE

- .1 Treat timber to CSA O80 Series preservative to obtain minimum net retention of 6.4 kg/m³ of wood.

3.2 CARE OF PRESSURE-TREATED WOOD PRODUCTS

- .1 Apply the recommended and accepted practices followed in the care and handling of all wood products to pressure-treated wood products.
- .2 Avoid damage of field fabrication causing alteration of the original pressure-treated surface.
- .3 Thoroughly saturate all cuts or injuries occurring subsequent to pressure treatment by liberal brushing, spraying, dipping, soaking or coating with preservative solution.

- .4 Fill holes necessarily bored after pressure treatment with preservative solution to allow ample soaking time for penetration of solution.
- .5 Use in any of the above the same preservative solution as that used in the original pressure treatment or a field treating solution of colour to match original treatment.

END OF SECTION

35 59 11 – FLOAT WHARF FABRICATION

Part 1 General

1.1 MEASUREMENT FOR PAYMENT

- .1 New timber float wharves to be paid for per unit supplied and delivered to the jobsite.
- .2 Installation of the new and existing repaired timber float wharves to be included in the lump sum amount.
- .3 Existing timber float wharves to be paid for per unit repaired and left at the jobsite. Bollards and cleats to be considered incidental to this item.
- .4 Connections between float wharves, fastenings, and hardware shall not be measured separately for payment, but considered incidental to the work.

Part 2 Products

2.1 MATERIALS

- .1 Lumber and timber: except as otherwise specified, use lumber and timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Administration Board of CSA.
 - .1 Species: Douglas Fir Group 1b.
 - .2 Grade: structural or better
 - .3 Grading authority: BCLMA
 - .4 All timber to be S4S.
 - .5 Galvanized bolts and nuts: to ASTM A307-07b.
 - .6 Countersunk head bolts to CSA B34-67(R1972).
 - .7 Washers: pressed steel.
 - .8 Galvanized spikes and nails: spiral type to CSA B111-1974(R2003).
 - .9 Hot-dip galvanized, stainless steel, silicone, bronze or copper wood screws and fasteners: to ASTM Standards: ASTM-A153 (for hot-dip fastener products), and ASTM-A653 (coating designation G-185 for hot-dip connector and sheet products) and Type 305 and 316 for stainless steel.
 - .10 Plastic bushings: ultra-high molecular weight polyethylene (UHMWPE), density 0.94, black.
 - .11 Shapes, plates: fabricated from steel conforming to CAN/CSA-G40.20-04 and CAN/CSA-G40.20-04, Grade 300W.
 - .12 Primer: CAN\CGSB-1.40-M80 primer, structural steel, oil alkyd type.
 - .13 Preservative:
 - .1 Pressure Treatment: all specified treated timber and planks to be pressure treated with CCA or ASA preservative salts to 0.64 g/cu. cm. (0.40 lbs/cu. ft.) retention.
 - .14 Machine bolts used are to be of sufficient length to accept two washers and one fully threaded hexagonal headed nut.

- .15 Mooring Cleats: galvanized grey iron ship or dock cleat (two hole type) indicated on drawings.
- .16 Floatation units:
 - .1 Dimensions/Capacity:
 - .1 Floatation units for principal float wharves and finger float wharves shall be of size 600 mm x 1200 mm x 300 mm deep with a minimum buoyancy of 196 kg each.
 - .2 Alternate floatation units shall be used only with written approval of engineer.
 - .2 Materials:
 - .1 One piece, seamless rotational moulded outer shell.
 - .2 Manufactured from linear polyethylene resin with UV inhibitors and carbon black pigment.
 - .3 Nominal shell thickness minimum 3.8 mm.
 - .4 Heavy duty, reinforced moulded in mounting slots.
 - .5 Built in vent.
 - .6 Foam filled to 1.0-1.5 lbs/ft³
- .17 Warranty:
 - .1 Manufacturer to warrant floats for a period of ten (10) years from date of purchase against cracking, peeling, sloughing and ultraviolet deterioration. Floatation units shall retain their resiliency against being frozen in or other abrasions from normal usage.
 - .2 Contractor will submit to engineer manufacturer's documentation indicating date of purchase.
 - .3 Alternate floatation units meeting or exceeding the above specification may be used only upon written approval of the engineer.

Part 3 Execution

3.1 CONSTRUCTION

- .1 Construct timber floats as indicated on drawings.
- .2 Build work square, true, straight and accurate to the required size, with all joints closely fitted and properly secured.
- .3 Except where specified, use of shims, wedges, or short pieces of timber not permitted.
- .4 Drill holes for bolts the same size as bolt diameter.
- .5 Lay deck planks, stringers and headers in one piece.
- .6 Project all bolts at least 6 mm beyond nut.
- .7 Place a washer under the head of each bolt and under nuts in contact with wood.
- .8 Connect floatation units with bolts c/w rubber and stainless steel washer as indicated on drawings.
- .9 Install stringers as designated.

- .10 Decking: Screw planks to each stringer contact with two (2) wood screws to a minimum penetration of 50 mm. Holes in decking are to be pre-drilled. Drill all screws 2 mm below deck surface. Space planks maximum 10 mm apart.
- .11 Fabricate and install all connection hardware as indicated.
- .12 Paint all float connectors, shapes and plates with one coat of primer prior to installation.

END OF SECTION