



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
PWGSC/TPSGC Acquisitions Bid
Receiving/Réception des Soumissions
The Cambridge Building
3 Queen Street/3, rue Queen
Charlottetown
Prince Edward Island
C1A 4A2
Bid Fax: (902) 566-7514

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

All enquiries are to be submitted in writing to the Contracting Authority, Darlene Reay, either by facsimile or by e-mail at:
darlene.reay@pwgsc.gc.ca.

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
The Cambridge Building
3 Queen Street/3 rue, Queen
PO Box 1268/CP 1268
Charlottetown
Prince Ed
C1A 4A2

| | |
|---|--|
| Title - Sujet Greenhouse Demolitions-AAFC Home Fa | |
| Solicitation No. - N° de l'invitation ED001-191968/A | Amendment No. - N° modif. 002 |
| Client Reference No. - N° de référence du client R.099986.001 | Date 2018-11-09 |
| GETS Reference No. - N° de référence de SEAG PW-\$PWC-008-4358 | |
| File No. - N° de dossier PWC-8-41055 (008) | CCC No./N° CCC - FMS No./N° VME |
| Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-11-14 | Time Zone Fuseau horaire Atlantic Standard Time AST |
| F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/> | |
| Address Enquiries to: - Adresser toutes questions à: Reay, D (PWC) | Buyer Id - Id de l'acheteur pwc008 |
| Telephone No. - N° de téléphone (902) 314-7957 () | FAX No. - N° de FAX (902) 566-7514 |
| Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: | |

Instructions: See Herein

Instructions: Voir aux présentes

| | |
|--|--|
| Delivery Required - Livraison exigée | Delivery Offered - Livraison proposée |
| Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur | |
| Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur | |
| Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie) | |
| Signature | Date |

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

SPECIFICATION

Section 01 10 10 General Instructions

1. Delete

1.1.10 – Decommission all electrical components down to the service disconnects in the basement of adjacent Cereal Header House Building 38 as per the Electrical Code of Canada. Removal and disposal to include all disconnects, panels, wiring, conduit and other electrical equipment.

And Replace with

1.1.10 - Decommission all electrical components back to the sub panels beside each greenhouse door from the Cereal Header House building 38 to greenhouse 38A and 38B, and back to the sub panel of building 29 for greenhouse 38C, as per the Electrical Code of Canada. Removal and disposal to include all disconnects, panels, wiring, conduit and other electrical equipment.

2. Delete

1.1.12 – In locations where the greenhouses are connected to the Cereal Header House and Building 29, make interior and exterior walls weather tight by sealing all penetrations, adding new bricks/blocks as necessary and repointing brick mortar joints that are cracked or damaged (existing and caused by the work). Match existing wall construction.

And Replace with

1.1.12 - In locations where the greenhouses are connected to the Cereal Header House and Building 29, make interior and exterior walls weather tight by sealing all penetrations, adding new bricks/blocks as necessary and repointing brick mortar joints that are cracked or damaged (existing and caused by the work). Match existing wall construction with like products as close to the original as possible.